

U4152-8-L

0410

7335

# Mound Summary Report

for

## Old Fire Fighting Training Area Naval Station Newport Newport, Rhode Island



**Engineering Field Activity Northeast  
Naval Facilities Engineering Command  
Contract Number N62467-94-D-0888  
Contract Task Order 0833**

**January 2004**

**MOUND SUMMARY REPORT**

**FOR**

**OLD FIRE FIGHTING TRAINING AREA  
NAVAL STATION NEWPORT  
NEWPORT, RHODE ISLAND**

**COMPREHENSIVE LONG-TERM  
ENVIRONMENTAL ACTION - NAVY (CLEAN) CONTRACT**

**Submitted to:  
Northern Division  
Environmental Branch, (Code EV2)  
Environmental Field Activity, Northeast  
Naval Facilities Engineering Command  
10 Industrial Highway, Mail Stop # 82  
Lester, Pennsylvania 19113-2090**

**Submitted by:  
Tetra Tech NUS, Inc.  
600 Clark Avenue, Suite 3  
King of Prussia, Pennsylvania 19406-1433**

**Contract Number N62467-94-D-0888  
Contract Task Order 0833**

**January 2004**

**PREPARED UNDER THE DIRECTION OF:**

---

**STEPHEN PARKER, LSP  
PROJECT MANAGER  
TETRA TECH NUS, INC.  
WILMINGTON, MASSACHUSETTS**

**APPROVED FOR SUBMISSION BY:**

---

**JOHN J. TREPANOWSKI, P.E.  
PROGRAM MANAGER  
TETRA TECH NUS, INC.  
KING OF PRUSSIA, PENNSYLVANIA**

## TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE</u>
<b>1.0 INTRODUCTION .....</b>	<b>1-1</b>
1.1 SPECIFIC INVESTIGATION OBJECTIVES .....	1-1
1.2 PROJECT DELIVERABLES .....	1-2
1.3 WORK PLAN ORGANIZATION .....	1-3
1.4 CHANGES TO THE WORK PLAN .....	1-4
<b>2.0 BACKGROUND INFORMATION .....</b>	<b>2-1</b>
2.1 SITE LOCATION AND DESCRIPTION .....	2-1
2.1.1 Site Conditions .....	2-1
2.1.2 Geology and Hydrogeology .....	2-1
2.2 SITE HISTORY .....	2-2
2.3 PREVIOUS STUDIES RESULTS .....	2-4
<b>3.0 MOUND PRE-DESIGN INVESTIGATION ACTIVITIES .....</b>	<b>3-1</b>
3.1 MOUND FIELD INVESTIGATIONS .....	3-1
3.1.1 Mobilization/Demobilization .....	3-1
3.1.2 Mound Soil Boring Advancement and Soil Sampling .....	3-1
3.1.3 Surveying .....	3-3
3.2 SAMPLE ANALYSIS AND DATA REVIEW .....	3-3
3.3 FIELD DATA REDUCTION .....	3-4
<b>4.0 INVESTIGATION FINDINGS .....</b>	<b>4-1</b>
4.1 MOUND No. 1 FINDINGS .....	4-1
4.2 MOUND No. 2 FINDINGS .....	4-2
4.3 CENTRAL MOUND FINDINGS .....	4-3

## TABLES

### NUMBER

- 4-1 Mound Soil Sample Analysis
- 4-2 Mound No. 1 Soil Sample Summary
- 4-3 Mound No. 1 Soil Concentrations Exceeding PRGs
- 4-4 Mound No. 2 Soil Sample Summary
- 4-5 Mound No. 2 Soil Concentrations Exceeding PRGs
- 4-6 Central Mound Soil Sample Summary
- 4-7 Central Mound Soil Concentrations Exceeding PRGs

## FIGURES

### NUMBER

- 2-1 OFFTA Location Map
- 4-1 Soil Boring Locations, Pre-Design Investigation, Soil Removal
- 4-2 Geological Cross Sections A-A', B-B', C-C', Old Fire Fighting Training Area
- 4-3 Geological Cross Sections D-d', E-E', F-F', Old Fire Fighting Training Area

## REFERENCES

**TABLE OF CONTENTS (cont.)**

**APPENDICES**

- A    Site Photographs**
- B    Soil Boring Logs**
- C    Survey Data**
- D    Analytical Results**
- E    Calculations**

## 1.0 INTRODUCTION

This report presents the results of the pre-design investigation (PDI) for three soil/debris mounds at the Old Firefighting Training Area (OFFTA Site or Site) conducted under Contract Task Order (CTO) 833, under the Comprehensive Long-Term Environmental Action Navy (CLEAN) Contract No. N62467-94-D-0888. Pursuant to the CTO, Tetra Tech NUS, Inc. carried out a soil pre-design investigation at the OFFTA Site, at Naval Station Newport (NAVSTA Newport), in Newport, Rhode Island. The objective of the PDI included acquiring data to assess the horizontal and vertical extent of construction debris, and the extent of soil contamination to determine the volume of debris and soil that will be removed in each of two planned actions. The first action will remove debris and soil contained in the mounds, above the base grade elevation of the Site. The contaminated soil and debris located below the base grade of the site (subsurface material) will be addressed by a separate, future removal action. This report provides an evaluation of the data specific to the removal of the mounds in the first action.

Preliminary remediation goals (PRGs) were identified for the soil at the Site in the FS. Soil PRGs are concentrations of chemicals that, if allowed to remain in the soil, are not anticipated to pose an increased risk of adverse effects to human health or the environment. Soil that contains contaminant concentrations exceeding PRGs were identified and used to delineate the areas that may require removal. The estimated ~~the volume of soil and construction debris in the mounds is approximately 11,100 cubic yards (compacted in-place).~~ The FS estimated the volume of contaminated soil and debris below the base grade at the site under the mounds at approximately 37,600 cubic yards (TtNUS, September 2002). Contaminant levels in soil samples collected from the mounds are generally lower than the levels found in the subsurface soil samples.

This pre-design investigation included advancing soil borings and collecting soil samples across the site to further define the extent of debris and soil contamination. This data was used to refine estimates of the mound soil and debris volumes that will be removed under a separate action prior to the removal of contaminated subsurface soil and debris below the base grade elevation.

This report includes four sections and six appendices:

- Section 1.0 – Introduction (this section);
- Section 2.0 – Background Information provides an expanded site background discussion and a summary of previous studies and findings;
- Section 3.0 – Site investigation Activities describes the PDI activities; and
- Section 4.0 – Investigation Findings presents the results of the RI and PDI specific to the mounds.

## 2.0 BACKGROUND INFORMATION

This section presents background information for the OFFTA Site, including its location and description, its history, and a brief summary of previous investigations results.

### 2.1 SITE LOCATION AND DESCRIPTION

NAVSTA Newport is located approximately 60 miles southwest of Boston, Massachusetts, and 25 miles south of Providence, Rhode Island. It occupies approximately 1,063 acres, with portions of the facility located in the City of Newport and Towns of Middletown and Portsmouth, Rhode Island. The facility layout is long and narrow, following the western shoreline of Aquidneck Island for approximately 6 miles facing the east passage of Narragansett Bay.

#### 2.1.1 Site Conditions

The OFFTA Site is located at the northern end of Coasters Harbor Island (see Figure 2-1). Site photographs are presented in Appendix A. The Site occupies approximately 5.5 acres and is bordered by Taylor Drive to the south and is surrounded by Coasters Harbor (part of Narragansett Bay) to the east, north, and west. With the exception of the three mounds, which are the main Site topographic features, the OFFTA Site is generally flat, with base grade surface elevations ranging from 8 to 12 feet above MLW. The Central Mound, rising approximately 20 feet above the base grade, is the largest mound and is located in the center of the Site. The other two mounds are referred to as Mound No. 1 and Mound No. 2, are smaller, and located in the west area of the Site with Mound No. 1 being the furthest west.

Mounds 1 and 2 abut the shoreline and have been partially eroded by wave action. Tide change over a six month period ranges between 2.6 and 4.5 vertical feet (Newport).

The Site is entirely vegetated with grass except for the temporary parking lot located in the center portion of the site formerly occupied by a baseball field. A one-story concrete block building (Building 144), used for recruiting offices, is located along the southern side of the Site. Recreational equipment has been removed. Access to the Site is restricted by a chain link fence along its eastern, southern, and western sides.

#### 2.1.2 Geology and Hydrogeology

The geology and hydrogeologic conditions at the OFFTA Site are summarized in the RI Report (TtNUS, 2001). The following paragraphs summarize the conclusions from the RI Report.

Geologic cross sections from the RI Report indicate the Site is underlain by sand and gravel fill containing construction debris; sand and gravel containing variable amounts of silt; peat; dense silt with fine to medium sand, gravel and rock fragments (glacial till); and bedrock. Construction debris consisted generally of rock fragments, asphalt, concrete, metal, wood and glass. The thickness of the overburden ranges from approximately 6 to 27 feet excluding the thickness of the three mounds, which reportedly consist of construction debris and other materials. Two borings advanced through the largest mound, located north of Building 144, indicated it is directly underlain by bedrock. Materials underlying the two remaining mounds, located west of the former baseball field, consist of glacial till or silty sand and gravel.

Bedrock encountered beneath the Site consists of conglomerate with quartz pebbles. The Rhode Island Formation has been mapped in the area and consists of metaconglomerates, metasandstones, schist, graphite, and carbonaceous schist. In the central portion of the Site, bedrock was blasted during Site development. Bedrock surface elevation contours indicate a bedrock "high" in the southeastern portion of the Site (east of Building 144) that drops about 5 feet and extends as a "peninsula" northwest to beneath a mound located north of Building 144. From beneath this mound, the bedrock surface slopes north toward Coasters Harbor and west toward Narragansett Bay.

## **2.2 SITE HISTORY**

The NAVSTA Newport facility has been in use by the Navy since the era of the Civil War. During World Wars I and II, military activities at the facility increased significantly and the base provided housing for many servicemen. In subsequent peacetime years, use of on-Site facilities was slowly phased out until Newport became the headquarters of the Commander Cruiser-Destroyer Force Atlantic in 1962. In April 1973, the Shore Establishment Realignment Program (SER) resulted in the reorganization of naval forces, and activity at the base again declined. This reorganization resulted in the Navy excessing some 1,629 acres of its 2,420 acres. Portions of the facility are currently leased by the Navy to the State of Rhode Island Port Authority and Economic Development Corporation. Some of these areas are, in turn, subleased to private enterprises.

The entire NAVSTA Newport was listed on the U.S. Environmental Protection Agency (EPA) National Priorities List (NPL) of abandoned or uncontrolled hazardous waste Sites in November 1989. The NPL identifies those Sites that pose a significant threat to the public health and environment. The OFFTA Site was listed as one of the Sites requiring RI/FS activities. It is currently being studied by the Navy under the Department of Defense Installation Restoration Program (IRP). This program is similar to the EPA's Superfund Program authorized under CERCLA in 1980, as amended by SARA in 1986.

A Federal Facilities Interagency Agreement (FFA) for NAVSTA Newport (then NETC) was signed by the Navy, the State of Rhode Island, and the EPA on March 23, 1992. The FFA outlines response action requirements under the Department of Defense IRP at NAVSTA Newport. The FFA was developed, in part, to provide a framework to address environmental impacts associated with past and present activities at NAVSTA Newport. As part of the FFA, regulatory agencies must review all documents pertaining to cleanup of the OFFTA site.

The OFFTA Site was home to a Navy fire fighting training facility from World War II until 1972. During the training operations, fuel oils were ignited in various structures at the Site including burn pits, so-called Christmas Tree above-ground nozzle array, and small buildings that simulated shipboard compartments. Ignited fires were then extinguished by sailors. It was reported that the two "Carrier Compartment" buildings were injected with a water/oil mixture which was subsequently set on fire for fire fighting practice. Underground piping reportedly carried the water/oil mixture to the buildings and from the buildings to an oil-water separator. Drainage piping from historic photos and maps provided in the FS report (TtNUS September 2002) show pipes from the separator discharged to Coasters Harbor to the north.

The fire fighting training facility was closed in 1972. Upon closure, the training structures were reportedly demolished and buried and compacted into mounds on the Site, and then the entire area was covered with topsoil. The Site was then converted to a recreational area with a playground, a baseball field, and a picnic area with an open pavilion and barbecue grills. The field was dedicated on July 4, 1976, and used as a recreational area until its closure in October 1998.

In its 22 years as a recreational area, the Site was used for organized activities including youth day camps, picnic functions, and little league baseball (1 year only), as well as for general recreation. A child day care center operated out of Building 144 on the Site from approximately 1983 through January 1994 when it was relocated off-site to a larger facility on base.

Aerial photos and facility maps for the period from 1939 through 1988 were reviewed to better evaluate the Site history. Activity on the Site appears to date back to approximately 1943. A 1953 facility design map indicates the locations of structures and Site features associated with fire fighting training exercises. An aerial photo taken in May 1944 depicts the Site with structures in a similar layout to that shown on the 1953 facility design map. Based on the design map and subsequent facility condition maps, on-site structures included an administration building, hose house, two carrier compartments, smothering pit, separator pit, foam pit, simulated ship structures, suction pumps, and oil tanks.

The indexes that accompanied some of the facility conditions maps indicate that the on-Site structure that was used in recent years as a day care center was once used as "wash and dressing rooms." No significant visible Site changes are noted from 1944 until a 1975 aerial photo of the Site, when the structures and facilities associated with the fire fighting training area are no longer evident, with exception of the "hose house" and Building 144. As of 1987, the Site appears similar to its current condition, with soil mounds visible in the central and western portions of the Site and a pavilion in the east-central portion of the Site.

### **2.3 PREVIOUS STUDIES RESULTS**

This pre-design investigation is preceded by a Remedial Investigation and a Feasibility Study completed in 2001 and 2002, respectively. Data from all prior investigations conducted by TtNUS and TRC Environmental Corporation (TRC) were assimilated into these reports, including three phases of the RI, a source removal investigation, risk assessment reports, etc. The overall findings reported in these studies are summarized below:

- Semivolatile organic compounds (SVOCs) were detected in all media across the Site. The most prevalent SVOCs detected were polynuclear aromatic hydrocarbons (PAHs) with the highest concentrations detected in surface and subsurface soil and groundwater sampling locations near Coasters Harbor. PAH concentrations in surface soils, subsurface soils, groundwater and storm water exceed RIDEM Residential Direct Exposure Criteria for soils.
- Pesticides were detected at low concentrations in surface soils and subsurface soils across the Site, and in storm water, marine sediments, and biota samples. Only one pesticide, endrin was detected in groundwater. All pesticide concentrations were low.
- Polychlorinated biphenyls (PCBs) were detected infrequently in surface and subsurface soils at concentrations below RIDEM Residential Direct Exposure Criteria for soils.
- Metals were detected throughout the Site. Metals concentrations were generally higher in site soil and groundwater relative to the same metals in background soil and upgradient groundwater locations. Metals concentrations in both surface soils and subsurface soils exceeding RIDEM Residential Direct Exposure Criteria for soils were arsenic, beryllium, lead, and manganese.
- Total petroleum hydrocarbons (TPHs) were detected in the subsurface throughout the Site exceeding RIDEM Residential Direct Exposure Criteria at depths ranging from 3 to 11 feet bgs.

Petroleum contamination was observed visually in the central portion of the Site in soils sampled immediately above the water table.

### **3.0 MOUND PRE-DESIGN INVESTIGATION ACTIVITIES**

This section discusses the procedures and methodologies employed during the implementation of the mound-related Pre-Design Investigation (PDI) activities, including the field investigation activities, sample analysis and data review, and data evaluation and reduction.

The objective of the OFFTA Site PDI is to provide data to assess the horizontal and vertical extent of construction debris, and the extent of contamination in soil across the site. The resulting data will be evaluated to determine the volume of the debris and soil within the mounds and in the subsurface below the base grade that will be considered for removal. This section presents a summary of the mound investigation activities, which were conducted as part of the OFFTA Site PDI. The resulting data is presented in this report and will support the development of the mound removal remedial action plans.

The PDI included advancing 30 soil borings across the site, including the mounds, to characterize the subsurface conditions and to collect soil samples; advancing an additional 5 soil borings along the shoreline to evaluate design parameters for shoreline erosion protection measures; and, surveying to locate the soil borings, map the shoreline topography, and to locate the high tide line, which will be the horizontal extent of the removal action in the planned soil removal action.

#### **3.1 MOUND FIELD INVESTIGATIONS**

Mound field investigation tasks included: mobilization/demobilization, soil boring advancement and soil sample collection; and surveying. The Work Plan for Soil Pre-Design Investigation (TtNUS, November 2003) describes the objectives and tasks for the PDI.

##### **3.1.1 Mobilization/Demobilization**

As part of mobilization activities, technical specifications for drilling, surveying, and analysis subcontracts were prepared and issued. Required field equipment and supplies were ordered and mobilized to the site. Field team members reviewed the work plan, and health and safety (provided under separate cover), applicable standard operating procedures (SOPs) and applicable subcontract specifications. A field team orientation meeting was conducted prior to initiating the fieldwork to familiarize the field team and subcontractor personnel with site health and safety requirements and the scope of the field activities. The mobilization date was coordinated with the Navy project representatives.

### 3.1.2 Mound Soil Boring Advancement and Soil Sampling

Soil borings were advanced to evaluate the existing subsurface conditions and to collect soil samples to further characterize the mound contents. A total of eight soil borings were advanced within the mounds:

#### Central Mound

SB411 located at the center

SB412 located in the eastern section

#### Mound No. 1

SB415 located in the western section

SB416 located in the eastern section

#### Mound No. 2

SB406 located in the northern section

SB407 located in the northeastern section

SB418 located in the southeastern section

SB433 located at the center

Continuous samples were collected from each of the eight borings from 2-feet intervals above the base grade elevation. Representative samples were selected for laboratory analysis of volatile organic compounds (VOCs), SVOCs, pesticides/PCBs and (Target Analyte List) TAL metals. Soils more than two feet below the base grade elevation were presumed to be below the extent of the mounds, and are not described in this Mound Summary Report.

All soil samples were collected using a conventional hollow-stem auger rig equipped with a split-spoon sampler by TtNUS's drilling subcontractor, Geosearch Inc., under the supervision of a TtNUS geologist. Upon sampler retrieval, soil samples were collected for volatile organic vapor jar headspace screening, using a flame ionization detector (FID) and a photoionization detector (PID). The sample was then inspected by the TtNUS geologist for visual evidence of construction debris and potential contamination and visually classified in accordance with TtNUS SOPs. A log of each boring was maintained by the field geologist (Appendix B). Any foreign materials (brick, asphalt, concrete, glass etc.) present was described and noted in the geologic log.

*Homogenized  
before vol sample* DRAFT

Soil not containing debris, as described above, was collected and placed in a decontaminated stainless steel bowl, homogenized after gravel removal, and placed in appropriate sample containers. If insufficient sample was obtained from the soil core, the next interval was sampled in this same manner. If two consecutive intervals provide no recovery in the split barrel sampler, a second boring was advanced to acquire samples at the missed interval(s). All samples were labeled and placed on ice immediately after collection and shipped with a chain-of-custody to the analytical laboratory.

The drill rig was also decontaminated by stream cleaning before starting the drilling program, and after completion of each boring. All non-disposable sampling equipment was decontaminated in accordance with the procedures identified in work plan.

### 3.1.3 Surveying

The horizontal location and vertical elevation of each new boring was surveyed to the RI State Plane Coordinate system NAD 1927 and NAVSTA Mean Low Water datum, respectively by TtNUS's surveying subcontractor, Louis Federici and Associates. Additional topographic survey along the shoreline between the top of slope to mean low water was also performed by the land surveyor. The survey data was used to update the site base map. The soil boring location survey data is presented in Appendix C.

## 3.2 SAMPLE ANALYSIS AND DATA REVIEW

A subcontracted laboratory (Mitkem Corp.) analyzed field samples and associated quality control samples using the analytical methods listed below:

<u>Analytes</u>	<u>Method</u>
VOCs	USEPA SW-846 Method 8260B
SVOCs	USEPA SW-846 Method 8270C
PAHs	USEPA SW-846 GCMS Selected Ion Monitoring (SIM)
Pesticides/PCBs	USEPA SW-846 Method 8081A/8082
TAL Metals	USEPA SW-846 Method 6010B Trace
TPH	USEPA SW-846 Method 8015 Modified for C9-C36 Hydrocarbons
GRO	USEPA SW-846 Method 8015 Modified for C9-C36 Hydrocarbons

The analytical data was validated using a Tier 1 validation effort, which is limited to review of sample results and QC results for completeness of the analytical packages.

### **3.3 FIELD DATA REDUCTION**

Field data reduction activities consisted of the following activities:

- Preparation of final soil boring logs (transcribing field logs)
- Updating the site base map by incorporating soil boring locations and shoreline topography
- Comparison of analytical data with PRGs to determine exceedances
- Preparation of mound cross sections
- Calculation of mound volumes above the base grade

## **4.0 INVESTIGATION FINDINGS**

Section 4.0 presents a summary of the findings of the OFFTA mound investigations. The following subsections summarize the physical, geological, and analytical results from testing conducted at the mounds. Table 4-1 provides a list of the soil samples collected during these efforts and the analyses conducted on these samples. Complete RI and PDI analytical results from mound samples are provided in Appendix D.

Figure 4-1 through 4-3 present site topography, boring locations, and cross sections of the mounds described in this summary report.

### **4.1 MOUND NO. 1 FINDINGS**

Mound No. 1, smallest of the three mounds, is located in the far west portion of the Site. It is a low, rounded, grass-covered feature approximately 4 to 6 feet higher than the surrounding base grade (8 to 10 feet above MLW), with a maximum elevation of 13.7 feet above MLW. The mound's volume is approximately 600 cubic yards (See Appendix E), and it covers an area of approximately 6,000 square feet with side slopes at approximately 15 percent. The western edge of the mound has been eroded by wave action, as it is in contact with Narragansett Bay.

Mound No. 1 is characterized from evaluation of three soil borings, consisting of one boring advanced during the 1993 RI (B-10) and two borings advanced during the PDI (SB415 and SB416). Mound No. 1 boring and sample details, along with jar headspace screening results, are provided in Table 4-2. Borings SB415 and B-10 are located on the western side and the eastern side of the mound center, respectively. SB416 is located on the eastern slope near the perimeter. The borings show that the material encountered in these borings above the base grade elevation consists of fill. The fill material consists of fine to coarse sand, silt and gravel mixed with construction debris (asphalt, concrete fragments, and brick pieces), with organic material encountered in the surface sample.

A total of six samples were collected in the three borings from intervals above and just below the base grade elevation at Mound No. 1. A list of contaminants in each sample that exceed the PRGS is presented in Table 4-3. No analytes were detected above the PRGs in the sample from B-10 sample (0.0 to 1.0 feet bgs). The table below provides a summary of the analyte detections exceeding PRGs.

### Mound No. 1 PRG Exceedance Summary

Parameter	No. Samples above PRG/No. Samples	Range of PRG Exceedance	Soil PRG
Benzo(a)pyrene	4/6	440 – 820 µg/kg	400 µg/kg
Benzo(b)flouranthene	2/6	1,100 - 1,100 µg/kg	900 µg/kg
Chrysene	4/6	450 – 890 µg/kg	400 µg/kg
Arsenic	5/6	10.7 – 23.6 mg/kg	6.2 mg/kg
Beryllium	4/6	0.42 – 0.63 mg/kg	0.4 mg/kg
Lead	2/6	168 – 182 mg/kg	150 mg/kg
Manganese	1/6	570 mg/kg	390 mg/kg

#### 4.3 MOUND NO. 2 FINDINGS

Mound No. 2 is located in the west portion of the Site. The second largest mound of the three, it is bordered on the north by the shoreline for approximately 350 feet. This northern edge has been eroded by wave action from contact with Narragansett Bay. Mound No. 2 is a rounded, grass-covered feature approximately 9 feet higher than the surrounding base grade, with a maximum elevation of 17.7 feet above MLW. The volume of Mound No. 2 above the base grade elevation is approximately 3,500 cubic yards (See Appendix E). The mound base covers approximately 19,000 square feet and the side slopes range from approximately 14 to 22 percent. Large ornamental cedar trees currently grow on Mound No. 2.

Mound No. 2 is characterized from evaluation of one surface soil sample and six soil borings. The surface soil sample (SS-5) was collected from the top of the mound during the RI. The borings consist of two borings advanced during the RI (B-8 and B-9) and four borings advanced during the PDI (SB406, SB407, SB418 and SB433). Boring and sample details, along with jar headspace screening results, are provided in Table 4-4. Borings SB433 and B-9 are located on the western side and the eastern side of the mound center, respectively. SB406 is located on the northern slope. SB407 and B-8 are located in the northeastern section of the mound and SB418 is located in the southeastern section of the mound. The borings show that the material encountered in these borings above the base grade elevation consists of fill consisting of fine to coarse sand, silt and gravel mixed with construction debris (asphalt, concrete fragments, and brick pieces). Topsoil was encountered in the surface sample.

A total of nine samples were collected at Mound No. 2 from intervals above and just below the base grade elevation. A list of contaminants in each sample that exceed the PRGs is presented in Table 4-5. No analytes were detected above the PRGs in one of the samples collected from SB433 (6.0 to 8.0 feet bgs). The table below provides a summary of the analyte detections exceeding PRGs.

### Mound No. 2 PRG Exceedance Summary

Parameter	No. Samples Above PRG/No. Samples	Range of PRG Exceedance	Soil PRG
Benzo(a)anthracene	2/9	1,000 J – 1,000 J µg/kg	900 µg/kg
Benzo(a)pyrene	4/9	460 – 1,000 J µg/kg	400 µg/kg
Benzo(b)flouranthene	3/9	910 J – 1,400 J µg/kg	900 µg/kg
Chrysene	4/9	510 – 980 J µg/kg	400 µg/kg
Arsenic	5/9	6.3 J – 10.6 mg/kg	6.2 mg/kg
Beryllium	5/6	0.43 – 0.64 mg/kg	0.4 mg/kg
Lead	3/9	192 – 268 mg/kg	150 mg/kg
Manganese	4/9	417 - 450 mg/kg	390 mg/kg

#### 4.3 CENTRAL MOUND FINDINGS

The Central Mound, largest of the three mounds, is located in the center of the OFFTA Site. It is a steeply sloped, three-sided pyramid shape structure approximately 21 feet higher than the surrounding base grade. With a maximum elevation of 31.0 feet above MLW, the Central Mound is the Site's highest topographic feature. The mound base covers an area of approximately 23,000 square feet and the side slopes range from 30 to 45 percent. The volume of the Central Mound was calculated at 7,000 cubic yards based on an average base elevation of 11 feet above MLW. Calculations are provided in Appendix E. The Central Mound is vegetated with grass and several large ornamental cedar trees that range up to 20 feet in height with canopy spans of 20 to 30 feet.

The Central Mound was characterized from evaluation of soil samples from surface soil, soil borings, and test pits shown on Figure 4-1. Central Mound soil boring and sample details, including jar headspace screening results, are provided in Table 4-6.

Six surface soil samples were collected during the RI; three samples (SS-3, SS-25 and SS-26, were collected from the side slopes and an additional three surface soil samples (SS-11, SS-325 and SS-326) were collected from the base.

Four soil borings were advanced through the Central Mound, consisting of B-14 and B-15 as part of the RI, and SB411 and SB412 as part of the PDI. B-14 and SB411 were located near the center, while B-15 and SB412 were located in the eastern section. The borings show that the material encountered in these borings above the base grade elevation consists of fill. Central Mound cross-sections based the borings are presented in Figure 4-2. The fill material consists of fine to coarse sand, silt and gravel mixed with construction debris (asphalt, concrete fragments, and brick pieces), with topsoil or organic material encountered in the surface samples.

Two test pits, TP2 and TP3, were excavated on the side slope of the Central Mound just above the base. TP2 was excavated on the west side on the mound and TP3 was excavated on the north side. In TP2 construction debris was encountered throughout from the surface to a depth of 7 feet. A strong petroleum odor was noted and PID readings of 1200 ppm were recorded at the 7 to 8-feet bgs interval. In TP3 construction debris was also encountered throughout from the surface to a depth of 7 feet and black staining and a petroleum odor was noted in soils at 8 feet bgs.

A total of 23 samples were collected at Central Mound from intervals above and just below the base grade elevation. A list of contaminants in each sample that exceed the PRGS is presented in Table 4-7. No analytes were detected above the PRGs in the surface soil samples collected at SS-25 and SS-26 (both 0.0 to 0.5 feet bgs). The table below provides a summary of the analyte detections exceeding PRGs.

**Central Mound PRG Exceedance Summary**

Parameter	No. Samples Above PRG/No. Samples	Range of PRG Exceedance	Soil PRG
Benzo(a)anthracene	6/22	930 – 3600 µg/kg	900 µg/kg
Benzo(a)pyrene	10/22	410 – 2,900 µg/kg	400 µg/kg
Benzo(b)flouranthene	3/22	1,100 – 3,900 µg/kg	900 µg/kg
Benzo(g,h,i)perylene	3/22	1,300 J – 1,700 J µg/kg	800 µg/kg
Benzo(k)fluoranthene	2/22	1,400 J – 2,500 J µg/kg	900 µg/kg
Chrysene	13/22	460 J – 3,300 J µg/kg	400 µg/kg
Dibenzo(a,h)anthracene	2/22	600 J – 780 J µg/kg	400 µg/kg
Indeno(1,2,3-cd)pyrene	3/22	1,100 J – 1,700 J µg/kg	900 µg/kg
Antimony	1/23	21.2 mg/kg	10 mg/kg
Arsenic	12/23	7 – 16.3 mg/kg	6.2 mg/kg
Beryllium	8/23	0.41 – 0.55 mg/kg	0.4 mg/kg
Lead	5/23	186 – 3,090 J mg/kg	150 mg/kg
Manganese	9/23	409 – 419 J mg/kg	390 mg/kg

## REFERENCES

- TRC Environmental Corporation (TRC). 1994. Old Fire Fighting Training Area Remedial Investigation Report, Naval Education and Training Center, Newport, Rhode Island. Draft Final Report with Appendices. U.S. Department of the Navy, Installation Restoration Program Contract No. N62472-86-C-1282. August.
- TtNUS, 2000. *Background Soil Investigation for Old Fire Fighting Training Area*, Naval Station Newport, Newport, RI.
- TtNUS, 2001. *Remedial Investigation for Old Fire Fighting Training Area*, Naval Station Newport, Newport, RI. July.
- TtNUS, 2002. *Feasibility Study for Old Fire Fighting Training Area*, Naval Station Newport, Newport, RI. September.
- TtNUS, 2003. *Soil Pre-Design Investigation Work Plan for Old Fire Fighting Training Area*, Naval Station Newport, Newport, RI. November.

## **TABLES**

**TABLE 4-1**  
**MOUND SOIL SAMPLE ANALYSIS**  
**DRAFT MOUND SUMMARY REPORT**  
**OLD FIRE FIGHTING TRAINING AREA**  
**NAVSTA NEWPORT, NEWPORT, RHODE ISLAND**

Location	Event	Date	Surface Elevation (ft MLW)	Sample ID	Sample Depth (ft bgs)	Sample Elevation (ft MLW)	Analysis										
							VOC	SVOC	PAH	Pest/ PCBs	TAL Metals	Cyanide	TPH	GRO			
<b>Mound No. 1</b>																	
B-10	RI (Ph II)	11/23/1993	13.7	B101-112393	0.0 1.0	13.7 12.7	X	X	--	X	X	X	--	--			
SB415	PDI	11/18/2003	13.3	SB-415-0002	0.0 2.0	13.3 11.3	X	X	--	X	X	--	X	--			
				SB-415-0204	2.0 4.0	11.3 9.3	X	X	--	X	X	--	X	--			
				SB-415-0608	6.0 8.0	7.3 5.3	--	--	X	--	X	--	X	X			
SB416	PDI	11/19/2003	11.5	SB-416-0002	0.0 2.0	11.5 9.5	X	X	--	X	X	--	X	--			
				SB-416-0406	4.0 6.0	7.5 5.5	--	--	X	--	X	--	X	X			
Total								4	4	2	4	6	1	5 2			
<b>Mound No. 2</b>																	
SS-5	RI (Ph I)	4/11/1990	17.5	SS-05	0.0 0.5	17.5 17.0	X	X	--	X	X	--	--	--			
B-8	RI (Ph II)	11/22/1993	11.5	B81-112293	0.0 1.0	11.5 10.5	X	X	--	X	X	X	--	--			
B-9	RI (Ph II)	11/23/1993	17.7	B91-112393	0.0 1.0	17.7 16.7	X	X	--	X	X	X	--	--			
SB406	PDI	12/3/2003	11.4	SB-406-0002	0.0 2.0	11.4 9.4	X	X	--	X	X	--	see Notes	--			
SB407	PDI	12/1/2003	12.9	SB-407-0002	0.0 2.0	12.9 10.9	X	X	--	X	X	--	X	--			
				SB-407-0204	2.0 4.0	10.9 8.9	X	X	--	X	X	--	X	--			
SB418	PDI	12/3/2003	10.0	SB-418-0002	0.0 2.0	10.0 8.0	X	X	--	X	X	--	X	--			
SB433	PDI	11/26/2003	17.3	SB-433-0204	2.0 4.0	15.3 13.3	X	X	--	X	X	--	X	--			
				SB-433-0608	6.0 8.0	11.3 9.3	X	X	--	X	X	--	X	--			
Total								9	9	0	9	9	2	5 0			
<b>Central Mound</b>																	
SS-3	RI (Ph I)	4/11/1990	24	SS-03	0.0 0.5	24.0 23.5	X	X	--	X	X	--	--	--			
SS-11	RI (Ph I)		12	SS-11	0.0 0.5	12.0 11.5	--	--	--	X	--	--	--	--			
SS-25	RI (Ph II)	11/4/1993	19.5	SS25-110493	0.0 0.5	19.5 19.0	--	X	--	X	X	--	--	--			
SS-26	RI (Ph II)	11/4/1993	22.5	SS26-110493	0.0 0.5	22.5 22.0	--	X	--	X	X	--	--	--			
SS-325	RI (Ph III)	11/19/1998	12	SS-325-0001	0.0 1.0	12.0 11.0	X	X	--	--	X	--	--	--			
SS-326	RI (Ph III)	11/19/1998	11	SS-326-0001	0.0 1.0	11.0 10.0	X	X	--	--	X	--	--	--			
TP2	RI (Ph II)	1/11/1994	13	TP23	2.0 2.0	11.0 11.0	X	X	--	X	X	X	--	--			
TP3	RI (Ph II)	1/11/1994	17	TP33	3.0 3.0	24.6 24.6	X	X	--	X	X	X	--	--			
				TP32	7.0 7.0	20.6 20.6	X	X	--	X	X	X	--	--			
				TP31	7.0 8.0	20.6 19.6	X	X	--	X	X	X	--	--			
B-14	RI (Ph II)	12/13/1993	30.7	B141-121393	0.0 1.0	30.7 29.7	X	X	--	X	X	X	--	--			

TABLE 4-1 (cont.)

## MOUND SOIL SAMPLE ANALYSIS

## DRAFT MOUND SUMMARY REPORT

## OLD FIRE FIGHTING TRAINING AREA

## NAVSTA NEWPORT, NEWPORT, RHODE ISLAND

PAGE 2 OF 2

Location	Event	Date	Surface Elevation (ft MLW)	Sample ID	Sample Depth (ft bgs)	Sample Elevation (ft MLW)	Analysis										
							VOC	SVOC	PAH	Pest/PCBs	TAL Metals	Cyanide	TPH	GRO			
				B142-121393	15.0	17.0	15.7	13.7	X	X	--	X	X	--			
B-15	RI (Ph II)	12/13/1993	27.6	B151-121393	0.0	1.0	27.6	26.6	X	X	--	X	X	--			
				B152-121393	10.0	12.0	17.6	15.6	X	X	--	X	X	--			
				B153-121393	15.0	17.0	12.6	10.6	X	X	--	X	X	--			
SB411	PDI	11/24/2003	31.0	SB-411-0204	2.0	4.0	29.0	27.0	X	X	--	X	X	--			
				SB-411-0608	6.0	8.0	25.0	23.0	X	X	--	X	X	--			
				SB-411-1012	10.0	12.0	21.0	19.0	X	X	--	X	X	--			
				SB-411-1416	14.0	16.0	17.0	15.0	X	X	--	X	X	--			
				SB-411-2022	20.0	22.0	11.0	9.0	--	--	X	--	X	X			
SB412	PDI	11/25/2003	24.5	SB-412-0204	2.0	4.0	22.5	20.5	X	X	--	X	X	--			
				SB-412-0608	6.0	8.0	18.5	16.5	X	X	--	X	X	--			
				SB-412-1012	10.0	12.0	14.5	12.5	X	X	--	X	X	--			
							Total	19	21	1	19	23	9	8			
														1			

Notes:

X indicates that specified analysis was conducted.

Sample SB-406-0002 not analyzed for TPH due to low sample volume.

ft MLW feet above mean low water

ft bgs feet below ground surface

GRO gasoline range organics

ID identifier

Pest pesticides

RI (Ph I) Phase I Remedial Investigation

RI (Ph II) Phase II Remedial Investigation

RI (Ph III) Phase III Remedial Investigation

PCBs polychlorinated biphenyls

PAH polynuclear aromatic hydrocarbons

PDI Pre-Design Investigation

SVOC semivolatile organic compounds

TAL Target Analyte List

TPH total petroleum hydrocarbons

VOC volatile organic compounds

**TABLE 4-2**  
**MOUND No. 1 SOIL SAMPLE SUMMARY**  
**DRAFT MOUND SUMMARY REPORT**  
**OLD FIRE FIGHTING TRAINING AREA**  
**NAVSTA NEWPORT, NEWPORT, RHODE ISLAND**

Location/ Date	Surface Elevation (ft MLW)	Sample Depth (ft bgs)	Sample Elevation (ft MLW)	Sample ID	OVA (ppm)	PID (ppm)	FID (ppm)	Description
B-10	13.7	<b>0.0</b> 2.0	<b>13.7</b> 12.7	B101-112393	0.0	ND	na	Fill material consisting of fine sand and gravel mixed with construction debris.
		2.0 4.0	11.7 9.7		0.0	ND	na	
		4.0 6.0	9.7 7.7		NR	NR	na	
		6.0 8.0	7.7 5.7		0.0	ND	na	Sample B101-112393 collected from 0.0 - 1.0 ft bgs. Refusal at 7 ft bgs.
SB415	13.3	<b>0.0</b> 2.0	<b>13.3</b> 11.3	SB-415-0002	na	0.0	0.0	Fill material consisting of fine to coarse sand, silt and gravel mixed with construction debris.
		2.0 4.0	11.3 9.3	SB-415-0204	na	0.0	0.0	
		4.0 6.0	9.3 7.3		na	0.0	0.0	
		6.0 8.0	7.3 5.3	SB-415-0608	na	0.0	0.0	
SB416	11.5	<b>0.0</b> 2.0	<b>11.5</b> 9.5	SB-416-0002	na	0.6	0.0	Fill material consisting of silty fine to coarse sand, silt and gravel mixed with construction debris.
		2.0 4.0	9.5 7.5		na	0.9	0.0	
		4.0 6.0	7.5 5.5		na	0.9	0.0	

**Notes:**

See boring logs for detailed description.

Bold number indicates the soil sample was collected from that depth interval.

ft bgs feet below ground surface

ft MLW feet above mean low water

FID flame ionization detector

ND not detected

OVA organic vapor analyzer

ppm parts per million (above background readings)

PID photoionization detector

**TABLE 4-3**  
**MOUND No. 1 SOIL CONCENTRATIONS EXCEEDING PRGs**  
**DRAFT MOUND SUMMARY REPORT**  
**OLD FIRE FIGHTING TRAINING AREA**  
**NAVSTA NEWPORT, NEWPORT, RHODE ISLAND**

Location	Surface Elevation (ft bgs)	Sample ID	Sample Depth (ft bgs)	Sample Elevation (ft MLW)	Parameter	Concentration	units	Soil PRG					
B-10	13.7	B101-112393	0.0 1.0	13.7 12.7	No PRG exceedances								
SB415	13.3	SB-415-0002	0.0 2.0	13.3 11.3	Benzo(a)pyrene	440	ug/kg	400					
					Chrysene	450	ug/kg	400					
					Arsenic	11.5	mg/kg	6.2					
					Beryllium	0.63	mg/kg	0.4					
					Benzo(a)pyrene	800	ug/kg	400					
		SB-415-0204			Benzo(b)flouranthene	1100	ug/kg	900					
					Chrysene	880	ug/kg	400					
					Arsenic	11.1	mg/kg	6.2					
					Beryllium	0.42	mg/kg	0.4					
					SB-415-0608	2.0 4.0	7.3 5.3	Arsenic	23.6	mg/kg	6.2		
					Lead			Lead	182	mg/kg	150		
SB416	11.5	SB-416-0002	0.0 2.0	11.5 9.5	Benzo(a)pyrene	480	ug/kg	400					
					Chrysene	520	ug/kg	400					
					Arsenic	10.7	mg/kg	6.2					
					Beryllium	0.53	mg/kg	0.4					
					Lead	168	mg/kg	150					
		SB-416-0406			Benzo(a)pyrene	820	ug/kg	400					
					Benzo(b)flouranthene	1100	ug/kg	900					
					Chrysene	890	ug/kg	400					
					Arsenic	11.8	mg/kg	6.2					
					Beryllium	0.43	mg/kg	0.4					
					Manganese			Manganese	570	mg/kg	390		

**Notes:**

Soil preliminary remediation goals (PRGs) from OFFTA Feasibility Study, TtNUS September 2002

ft bgs feet below ground surface

ft MLW feet above mean low water

ID identifier

µg/kg microgram per kilogram

mg/kg milligram per kilogram

**TABLE 4-4**  
**MOUND No. 2 SOIL SAMPLE SUMMARY**  
**DRAFT MOUND SUMMARY REPORT**  
**OLD FIRE FIGHTING TRAINING AREA**  
**NAVSTA NEWPORT, NEWPORT, RHODE ISLAND**

Location/ Date	Surface Elevation (ft MLW)	Sample Depth (ft bgs)	Sample Elevation (ft MLW)		Sample ID	OVA (ppm)	PID (ppm)	FID (ppm)	Description
SS-5	17.5	0.0    0.5	17.5	17.0	SS5-411	na	na	na	Fine sand, some silt
B-8	11.5	0.0    2.0	11.5	9.5	B81-112293	0.0	0.0	na	Fill material consisting of fine sand, silt and gravel mixed with construction debris. Sample B81-112293 collected from 0.0 -1.0 ft bgs.
		2.0    4.0	9.5	7.5		0.0	0.0	na	
		4.0    6.0	7.5	5.5		NR	NR	na	
		6.0    8.0	5.5	3.5		0.0	6.0	na	
B-9	17.7	0.0    2.0	17.7	15.7	B91-112393	0.0	0.0	na	Fill material consisting of fine sand, silt and gravel mixed with construction debris. Sample B91-112393 collected from 0.0 -1.0 ft bgs.
		2.0    4.0	15.7	13.7		NR	NR	na	
		4.0    6.0	13.7	11.7		NR	NR	na	
		6.0    7.0	11.7	10.7		NR	NR	na	
		7.0    9.0	10.7	8.7		0.0	0.0	na	
		9.0    11.0	8.7	6.7		0.0	0.0	na	
		11.0    12.0	6.7	5.7		NR	NR	na	
SB406	11.4	0.0    2.0	11.4	9.4	SB-406-0002	na	0.0	20.6	Fill material consisting of fine to coarse sand, silty sand, silt and gravel, brick and asphalt, with topsoil at surface.
		2.0    4.0	9.4	7.4		na	0.9	0.0	
		4.0    6.0	7.4	5.4		na	1.8	0.0	
		6.0    8.0	5.4	3.4		na	3.8	0.0	
SB407	12.9	0.0    2.0	12.9	10.9	SB-407-0002	na	0.0	0.0	Fill material consisting of sand, sandy and gravelly silt and gravel, concrete, brick and asphalt, with topsoil at surface.
		2.0    4.0	10.9	8.9	SB-407-0204	na	0.0	0.0	
		4.0    6.0	8.9	6.9		na	0.0	0.0	
		6.0    8.0	6.9	4.9		na	0.0	0.0	
SB418	10	0.0    2.0	10.0	8.0	SB-418-0002	na	3.2	2.1	Fill material consisting of fine to medium sand, silt and gravel, concrete, brick and asphalt, with topsoil at surface.
		2.0    4.0	8.0	6.0		na	4.1	0.0	
		4.0    6.0	6.0	4.0		na	4.1	3.9	
SB433	17.3	0.0    2.0	17.3	15.3		na	NR	NR	Fill material consisting of silty fine to medium sand, sandy silt with gravel, brick pieces.
		2.0    4.0	15.3	13.3	SB-433-0204	na	0.0	0.0	
		4.0    6.0	13.3	11.3		na	0.0	0.0	
		6.0    8.0	11.3	9.3	SB-433-0608	na	20.0	38.0	
		8.0    10.0	9.3	7.3		na	17.1	34.0	
		10.0    12.0	7.3	5.3		na	0.0	0.0	

## Notes:

See boring logs for detailed description.

Bold number indicates the soil sample was collected from that depth interval.

ft bgs      feet below ground surface

ft MLW      feet above mean low water

FID      flame ionization detector

NR      No reading

na      not applicable

OVA      organic vapor analyzer

ppm      parts per million (above background readings)

PID      photoionization detector

**TABLE 4-5**  
**MOUND No. 2 SOIL CONCENTRATIONS EXCEEDING PRGs**  
**DRAFT MOUND SUMMARY REPORT**  
**OLD FIRE FIGHTING TRAINING AREA**  
**NAVSTA NEWPORT, NEWPORT, RHODE ISLAND**

Location	Surface Elevation (ft bgs)	Sample ID	Sample Depth (ft bgs)	Sample Elevation (ft MLW)	Parameter	Concentration	units	Soil PRG
SS-5	17.5	SS-05	0 0.5	17.5 17	Beryllium	0.48	mg/kg	0.4
B-8	11.5	B81-112293	0 1	11.5 10.5	Arsenic	6.3 J	mg/kg	6.2
B-9	17.7	B91-112393	0 1	17.7 16.7	Beryllium	0.43	mg/kg	0.4
SB406	11.4	SB-406-0002	0 2	11.4 9.4	Benzo(a)pyrene	460	ug/kg	400
					Chrysene	510	ug/kg	400
					Arsenic	6.7	mg/kg	6.2
					Beryllium	0.56	mg/kg	0.4
					Lead	268	mg/kg	150
					Manganese	450	mg/kg	390
					Benzo(a)anthracene	1000 J	ug/kg	900
SB407	12.9	SB-407-0002	0 2	12.9 10.9	Benzo(a)pyrene	860 J	ug/kg	400
					Benzo(b)flouranthene	1100 J	ug/kg	900
					Chrysene	930 J	ug/kg	400
					Lead	217	mg/kg	150
					Manganese	445	mg/kg	390
					Benzo(a)anthracene	1000 J	ug/kg	900
	10.0	SB-407-0204	2 4	10.9 8.9	Benzo(a)pyrene	1000 J	ug/kg	400
					Benzo(b)flouranthene	1400 J	ug/kg	900
					Chrysene	980 J	ug/kg	400
					Arsenic	6.9	mg/kg	6.2
					Lead	192	mg/kg	150
					Manganese	424	mg/kg	390
SB418	10.0	SB-418-0002	0 2	10 8	Arsenic	8.4	mg/kg	6.2
					Beryllium	0.64	mg/kg	0.4
SB433	17.3	SB-433-0204	2 4	15.3 13.3	Benzo(a)pyrene	620 J	ug/kg	400
					Benzo(b)flouranthene	910 J	ug/kg	900
					Chrysene	640 J	ug/kg	400
					Arsenic	10.6	mg/kg	6.2
					Beryllium	0.49	mg/kg	0.4
					Manganese	417	mg/kg	390
		SB-433-0608	6 8	11.3 9.3	No PRG exceedances			

Notes:

Soil preliminary remediation goals (PRGs) from OFFTA Feasibility Study, TtNUS September 2002

ft bgs feet below ground surface

ft MLW feet above mean low water

ID identifier

µg/kg microgram per kilogram

mg/kg milligram per kilogram

J quantitation approximate

**TABLE 4-6**  
**CENTRAL MOUND SOIL SAMPLE SUMMARY**  
**DRAFT MOUND SUMMARY REPORT**  
**OLD FIRE FIGHTING TRAINING AREA**  
**NAVSTA NEWPORT, NEWPORT, RHODE ISLAND**

Location/ Date	Surface Elevation (ft MLW)	Sample Depth (ft bgs)	Sample Elevation (ft MLW)	Sample ID	OVA (ppm)	PID (ppm)	FID (ppm)	Description
SS-3	24.0	0.0    0.5	24.0    23.5	SS3-411	na	na	na	Fine sand and silt, trace organics
SS-11	12.0	0.0    0.5	12.0    11.5					Not available
SS-25	19.5	0.0    0.5	19.5    19.0	SS25-110493	NR	NR	NR	Fill consisting of fine sand and organics, some silt, little rock fragments
SS-26	22.5	0.0    0.5	22.5    22.0	SS26-110493	NR	NR	NR	Fill consisting of fine sand and organics, trace medium sand and gravel
SS-325	12.0	0.0    1.0	12.0    11.0	SS-325-0001				
SS-326	11.0	0.0    1.0	11.0    10.0	SS-326-0001				
TP2	13.0	0.0    3.0	13.0    10.0	TP23	NR	NR	na	Fill consisting of fine to medium sand, silt, cobbles and rock fragments mixed with construction debris
		3.0    6.0	10.0    7.0		NR	NR	na	
TP3	17.0	0.0    4.0	17.0    13.0	TP33	NR	NR	na	Fill consisting of fine to medium sand and rock fragments mixed with construction debris
		4.0    4.5	13.0    12.5		NR	NR	na	
		4.5    7.0	12.5    10.0	TP32	NR	NR	na	
		7.0    8.0	10.0    9.0	TP31	NR	NR	na	
		0.0    2.0	30.7    28.7	B141-121393	0.0	0.0	na	Fill consisting of fine to medium sand, silt, gravel, cobbles and rock fragments mixed with construction debris Sample B141-121393 collected from 0.0 - 1.0 ft bgs
B-14	30.7	5.0    7.0	25.7    23.7		0.0	0.0	na	
		7.0    9.0	23.7    21.7		0.0	0.0	na	
		9.0    11.0	21.7    19.7		0.0	0.0	na	
		15.0    17.0	15.7    13.7	B142-121393	0.0	0.0	na	
		17.0    19.0	13.7    11.7		0.0	0.0	na	
		20.0    22.0	10.7    8.7		NR	NR	na	
		0.0    2.0	27.6    25.6	B151-121393	0.0	0.0	na	
B-15	27.6	2.0    4.0	25.6    23.6		0.0	0.0	na	Fill consisting of fine to medium sand, silt, gravel, cobbles and rock fragments mixed with construction debris Sample B151-121393 collected from 0.0 - 1.0 ft bgs
		4.0    6.0	23.6    21.6		0.0	0.0	na	
		8.0    10.0	19.6    17.6		0.0	0.0	na	
		10.0    12.0	17.6    15.6	B152-121393	0.0	0.0	na	
		15.0    17.0	12.6    10.6	B153-121393	0.0	0.0	na	
		17.0    19.0	10.6    8.6		NR	NR	na	

**TABLE 4-6**  
**CENTRAL MOUND SOIL SAMPLE SUMMARY**  
**DRAFT MOUND SUMMARY REPORT**  
**OLD FIRE FIGHTING TRAINING AREA**  
**NAVSTA NEWPORT, NEWPORT, RHODE ISLAND**  
**PAGE 2 OF 2**

Location/ Date	Surface Elevation (ft MLW)	Sample Depth (ft bgs)	Sample Elevation (ft MLW)	Sample ID	OVA (ppm)	PID (ppm)	FID (ppm)	Description
SB411	31.0	0.0	2.0	31.0 29.0	na	na	0.0	Fill material consisting of sand, silt and gravel, mixed with construction debris with topsoil at surface.
		<b>2.0</b>	<b>4.0</b>	<b>29.0</b> <b>27.0</b>	<b>SB-411-0204</b>	na	na	
		4.0	6.0	27.0 25.0	na	na	0.0	
		<b>6.0</b>	<b>8.0</b>	<b>25.0</b> <b>23.0</b>	<b>SB-411-0608</b>	na	na	
		8.0	10.0	23.0 21.0	na	na	94.1	
		<b>10.0</b>	<b>12.0</b>	<b>21.0</b> <b>19.0</b>	<b>SB-411-1012</b>	na	na	
		12.0	14.0	19.0 17.0	na	na	574.0	
		<b>14.0</b>	<b>16.0</b>	<b>17.0</b> <b>15.0</b>	<b>SB-411-1012</b>	na	na	
		16.0	18.0	15.0 13.0	na	na	489.0	
		18.0	20.0	13.0 11.0	na	na	NR	
		20.0	22.0	11.0 9.0	na	na	0.0	
SB412	24.5	0.0	2.0	24.5 22.5	na	NR	NR	Fill material consisting of silty sand and gravel, mixed with construction debris with topsoil at surface.
		<b>2.0</b>	<b>4.0</b>	<b>22.5</b> <b>20.5</b>	<b>SB-412-0204</b>	na	123.0	
		4.0	6.0	20.5 18.5	na	0.0	7.2	
		<b>6.0</b>	<b>8.0</b>	<b>18.5</b> <b>16.5</b>	<b>SB-412-0608</b>	na	51.6	
		8.0	10.0	16.5 14.5	na	0.0	8.3	
		<b>10.0</b>	<b>12.0</b>	<b>14.5</b> <b>12.5</b>	<b>SB-412-1012</b>	na	19.7	
		12.0	14.0	12.5 10.5	na	38.9	103.3	
		<b>14.0</b>	<b>16.0</b>	<b>10.5</b> <b>8.5</b>	<b>SB-412-1416</b>	na	50.3	
		16.0	18.0	8.5 6.5	na	63.0	132.6	

## Notes:

Bold number indicates the soil sample was collected from that depth interval.

ft bgs feet below ground surface

ft MLW feet above mean low water

FID flame ionization detector

NR No reading

na not applicable

OVA organic vapor analyzer

ppm parts per million (above background readings)

PID photoionization detector

**TABLE 4-7**  
**CENTRAL MOUND SOIL CONCENTRATIONS EXCEEDING PRGs**  
**DRAFT MOUND SUMMARY REPORT**  
**OLD FIRE FIGHTING TRAINING AREA**  
**NAVSTA NEWPORT, NEWPORT, RHODE ISLAND**

Location	Surface Elevation (ft bgs)	Sample ID	Sample Depth (ft bgs)	Sample Elevation (ft MLW)	Parameter	Concentration	units	Soil PRG
SS-3	24	SS-03	0.0 0.5	24.0 23.5	Beryllium	0.41	mg/kg	0.4
SS-25	19.5	SS25-110493	0.0 0.5	19.5 19.0	No PRG exceedances	na	na	na
SS-26	22.5	SS26-110493	0.0 0.5	22.5 22.0	No PRG exceedances	na	na	na
SS-11	12	SS-11	0.0 0.5	12.0 11.5	Beryllium	0.5	mg/kg	0.4
SS-325	12	SS-325-0001	0.0 1.0	12.0 11.0	Arsenic	10.4	mg/kg	6.2
SS-326	11	SS-326-0001	0.0 1.0	11.0 10.0	Arsenic	10.1	mg/kg	6.2
					Beryllium	0.47	mg/kg	0.4
B-14	30.7	B141-121393	0.0 1.0	30.7 29.7	Arsenic	8.5	mg/kg	6.2
					Arsenic	9.2	mg/kg	6.2
					Chrysene	460 J	ug/kg	400
					Lead	252	mg/kg	150
B-15	27.6	B151-121393	0.0 1.0	27.6 26.6	Arsenic	7	mg/kg	6.2
					Benzo(a)anthracene	2400	ug/kg	900
					Benzo(a)pyrene	2600	ug/kg	400
					Benzo(b)fluoranthene	3900	ug/kg	900
					Benzo(g,h,i)perylene	1300 J	ug/kg	800
					Chrysene	2400	ug/kg	400
		B152-121393	10.0 12.0	17.6 15.6	Indeno(1,2,3-cd)pyrene	1100 J	ug/kg	900
					Manganese	506 J	mg/kg	390
					Benzo(a)anthracene	1200	ug/kg	900
					Benzo(a)pyrene	730	ug/kg	400
					Benzo(b)fluoranthene	1300	ug/kg	900
					Chrysene	1100	ug/kg	400
TP2	13.0	TP23	2.0 2.0	11.0 11.0	Benzo(a)anthracene	1300	ug/kg	900
					Benzo(a)pyrene	460 J	ug/kg	400
					Chrysene	580 J	ug/kg	400
					Benzo(a)pyrene	630 J	ug/kg	400
					Chrysene	640 J	ug/kg	400
		TP32	7.0 7.0	10.0 10.0	Benzo(a)anthracene	2400 J	ug/kg	900
					Benzo(a)pyrene	2900 J	ug/kg	400
					Benzo(b)fluoranthene	2300 J	ug/kg	900
					Benzo(g,h,i)perylene	1700 J	ug/kg	800
					Benzo(k)fluoranthene	2500 J	ug/kg	900
TP3	17.0	TP31	7.0 8.0	10.0 9.0	Chrysene	2500 J	ug/kg	400
					Dibenz(a,h)anthracene	780 J	ug/kg	400
					Indeno(1,2,3-cd)pyrene	1700 J	ug/kg	900
					Manganese	413 J	mg/kg	390
					Arsenic	16.3 J	mg/kg	6.2
					Chrysene	690 J	ug/kg	400
					Lead	3090 J	mg/kg	150

**TABLE 4-7 (cont.)**  
**CENTRAL MOUND SOIL CONCENTRATIONS EXCEEDING PRGs**  
**DRAFT MOUND SUMMARY REPORT**  
**OLD FIRE FIGHTING TRAINING AREA**  
**NAVSTA NEWPORT, NEWPORT, RHODE ISLAND**  
**PAGE 2 OF 2**

Location	Surface Elevation (ft bgs)	Sample ID	Sample Depth (ft bgs)	Sample Elevation (ft MLW)	Parameter	Concentration	units	Soil PRG
SB411	31.0	SB-411-0204	2.0 4.0	29.0 27.0	Benzo(a)pyrene	410	ug/kg	400
					Chrysene	480	ug/kg	400
					Arsenic	7.8	mg/kg	6.2
					Manganese	491	mg/kg	390
	6.0 8.0	SB-411-0608	25.0 23.0		Chrysene	490	ug/kg	400
					Arsenic	12.8	mg/kg	6.2
					Beryllium	0.54	mg/kg	0.4
					Manganese	557	mg/kg	390
	10.0 12.0	SB-411-1012	21.0 19.0		Benzo(a)anthracene	930	ug/kg	900
					Benzo(a)pyrene	610	ug/kg	400
					Benzo(b)flouranthene	1100	ug/kg	900
					Chrysene	970	ug/kg	400
					Arsenic	8.8	mg/kg	6.2
					Beryllium	0.5	mg/kg	0.4
					Manganese	424	mg/kg	390
	14.0 16.0	SB-411-1416	17.0 15.0		Benzo(a)anthracene	3600	ug/kg	900
					Benzo(a)pyrene	2900	ug/kg	400
					Benzo(b)flouranthene	3300	ug/kg	900
					Benzo(g,h,i)perylene	1700 J	ug/kg	800
					Benzo(k)flouranthene	1400 J	ug/kg	900
					Chrysene	3300	ug/kg	400
					Dibeno(a,h)anthracene	600 J	ug/kg	400
					Indeno(1,2,3-cd)pyrene	1500 J	ug/kg	900
					Arsenic	9.5	mg/kg	6.2
					Beryllium	0.46	mg/kg	0.4
					Lead	559	mg/kg	150
	20.0 22.0	SB-411-2022	11.0 9.0		Manganese	409	mg/kg	390
SB412	24.5	SB-412-0204	2.0 4.0	22.5 20.5	Arsenic	11.5	mg/kg	6.2
					Beryllium	0.55	mg/kg	0.4
		SB-412-0608	6.0 8.0	18.5 16.5	Arsenic	8.9	mg/kg	6.2
					Beryllium	0.44	mg/kg	0.4
					Manganese	574	mg/kg	390
		SB-412-1012	10.0 12.0	14.5 12.5	Benzo(a)pyrene	590	ug/kg	400
					Chrysene	680	ug/kg	400
					Antimony	21.2	mg/kg	10
					Arsenic	11.6	mg/kg	6.2
					Lead	186	mg/kg	150
					Manganese	536	mg/kg	390

Notes:

Soil preliminary remediation goals (PRGs) from OFFTA Feasibility Study, TtNUS September 2002

ft bgs feet below ground surface

ft MLW feet above mean low water

ID identifier


µg/kg microgram per kilogram

mg/kg milligram per kilogram

na not applicable

J quantitation approximate

## **FIGURES**



## NOTES.

BASE MAP FROM PLAN BY DEPT. OF NAVY, "COASTERS HARBOR ISLAND AND NAVAL HOSPITAL EXISTING CONDITIONS MAP", DATED: 9/98, NETC DWG NO.: 31058-307, CODE ID NO.: B0091. SCALE: 1"-200'.

## NARRAGANSETT BAY

OFFTA LOCATION MAP

## OLD FIRE FIGHTING TRAINING AREA

**NAVSTA NEWPORT – NEWPORT, RHODE ISLAND**

DRAWN BY: D.W. MACDOUGALL REV.: 0

CHECKED BY: D. BAXTER DATE: JANUARY 23, 2004


SCALE: 1" = 400' FILE NO.: DWG\4152\1400\FIG\_2-1.DWG

FIGURE 2-1



TETRA TECH NUS, INC.

N  
E  
S  
W



#### LEGEND

- CATCH BASIN
- Existing Contour
- B-18 SOIL BORING LOCATION WHERE SURFACE AND SUBSURFACE SOIL SAMPLES WERE COLLECTED
- ◆ MW-65 MONITORING WELL LOCATION WHERE SURFACE AND SUBSURFACE SOIL SAMPLES WERE COLLECTED
- STORM SEWER
- TP-10 TEST PIT LOCATION WHERE SUBSURFACE SOIL SAMPLE(S) WERE COLLECTED (B&RE, 6/97)
- TP1C TEST PIT LOCATION WHERE SUBSURFACE SOIL SAMPLE(S) WERE COLLECTED (TRC, 1/94)
- SB400 PROPOSED BORING AND IDENTIFIER





- SUBSURFACE SOIL SAMPLE LOCATION WHERE CRITERIA\* EXCEEDED
- LOCATIONS (INCLUDING TEST PITS & BORINGS) WHERE PETROLEUM WAS OBSERVED ON SUB-SURFACE SOILS
- \* RIDEM RESIDENTIAL DIRECT EXPOSURE CRITERIA EXCEPT FOR ARSENIC (PROPOSED 6.2 MG/KG BACKGROUND LEVEL WAS USED)
- INTERPRETED BASE OF MOUND

#### NOTES AND REFERENCES:

- DRAWING COMPILED FROM A DRAWING ENTITLED "BASE MAP OLD FIRE FIGHTING TRAINING AREA NETC, NEWPORT, RHODE ISLAND, JULY 1997, PROJ. NO. 7578 CTO: 288, BY BROWN & ROOT ENVIRONMENTAL, SOURCE: BASE PLAN BY GUERRIERE & HALNON, INC., DATED NOVEMBER 10, 1997, AND THE ADDITION OF FIELD MEASURED FEATURES, BY LOUIS FEDERICI AND ASSOCIATES 3/16/99, PRESENTED ON A DRAWING ENTITLED "KADY FIELD, TOPOGRAPHIC, SOIL SAMPLE LOCATION, AND SITE SURVEY AT THE OLD FIRE FIGHTING TRAINING AREA, NAVAL STATION NEWPORT IN NEWPORT, RHODE ISLAND FOR TETRA TECH NUS, INC., LOUIS FEDERICI & ASSOCIATES, 3/16/99, DWG NO. 990205-01.
- HORIZONTAL DATUM BASE ON THE RI STATE PLANE COORDINATE SYSTEM NAD 1927. VERTICAL DATUM BASED ON NAVEL BASE MEAN LOW WATER.
- ALL LOCATIONS ARE TO BE CONSIDERED APPROXIMATE.
- PLAN NOT TO BE USED FOR DESIGN.

DRAWN BY: D.W. MACDOUGALL	TITLE: SOIL BORING LOCATIONS
PREPARED BY: D. HARTIGAN	PRE-DESIGN INVESTIGATION, SOIL REMOVAL
CHECKED BY: S. PARKER	OLD FIRE FIGHTING TRAINING AREA
	NAVAL STATION NEWPORT, RHODE ISLAND
SOURCE: BASE PLAN BY SEE NOTES.	
SCALE: 1" = 50'	DATE: JANUARY 23, 2003
PROJECT MANAGER: S. PARKER	PROJ. NO: 4152
PROGRAM MANAGER: J. TREPANOWSKI	DRAWING NO: FIGURE 4-1
	DWG/4152/1401/FIG_4-1.DWG
	FIGURE 4-1
	ACFILE NAME: REV: 0

**TETRA TECH NUS, INC.**  
55 JONSPIN ROAD  
WILMINGTON, MASSACHUSETTS 01887  
(978)658-7899



NC

1. THE DEPTHS AND THICKNESSES DETERMINED FOR THE SUBSURFACE STRATA WERE GENERALIZED FROM AND INTERPOLATED BETWEEN TEST BORINGS. THE STRATIFICATION LINES REPRESENT AN APPROXIMATE BOUNDARY BETWEEN SOIL TYPES; THE TRANSITION MAY BE GRADUAL. INFORMATION ON SUBSURFACE CONDITIONS EXIST ONLY AT THE LOCATION OF THE TEST BORINGS; THEREFORE, IT IS POSSIBLE THAT THE SUBSURFACE CONDITIONS MAY VARY FROM THOSE INDICATED.

SUBSURFACE CONDITIONS MAY VARY FROM

3. HORIZONTAL DATUM IS BASED ON THE RI STATE PLANE COORDINATE SYSTEM NAD 1927. VERTICAL DATUM IS BASED ON NAVAL BASE MELOW WATER (NGVD 1929 MINUS 1.6 FEET).

#### 4. BASE PLAN

ENVIRONMENTAL.

5. GROUND ELEVATIONS WERE BASED ON BORING LOGS PROVIDED BY TRC.

## 6. ELEVATIONS

7. BASED ON THE SEISMIC REFRACTION SURVEY RESULTS, THE ESTIMATED ACCURACY OF DEPTH OF BEDROCK IS +/- 15 PERCENT OR 2 FEET WHICHEVER IS GREATER. THE DEPTHS DETERMINED FOR BEDROCK X ARE DEPTHS OF COMPETENT ROCK; DEEPLY WEATHERED ROCK MAY OCCUR AT SHALLOWER DEPTHS.

8. PRESUMPTION MADE THAT APPROXIMATELY 1-2 FEET OF TOPSOIL (FILL) LIES BETWEEN THE MOUNDS AND ACROSS THE EASTERN PORTION THE SITE, UNLESS OTHERWISE SPECIFIED.

9. BEDROCK ELEVATIONS ARE BASED ON THE  
WERE USED TO SUPPLEMENT THESE DATA. IF

WERE USED TO SUPPLEMENT THESE DATA. THE BEDS  
FOOT OF THE REFUSAL DEPTH. THE BEDS  
DIFFERENT FROM THE ELEVATION INDICATED

DIFFERENT FROM THE ELEVATION INDICATED.

100

FILL — FINE TO MEDIUM SAND, SILT, GRAVEL, AND ROCK FRAGMENTS MIXED WITH VARYING AMOUNTS OF CONSTRUCTION-TYPE DEBRIS INCLUDING: ASPHALT, CONCRETE, METAL, BRICK, WOOD AND GLASS

A 4x10 grid of squares. Blue arrows are placed in the first column at the top two rows and in the fourth column at the middle two rows, all pointing to the right.

SILTY SAND AND GRAVEL - FINE TO MEDIUM SAND, SILT AND GRAVEL, WITH VARYING AMOUNTS OF ROCK FRAGMENTS AND SEASHELL FRAGMENTS

## TOP SOIL

+	+	+	+	+	+
+	+	+	+	+	+
+	+	+	+	+	+

-	-	-	-	-	-
-	-	-	-	-	-




## BEDROCK - CONGLOMERATE WITH QUARTZITE CO.

8.00 SOIL ABOVE THIS LINE TO BE REMOVED  
NUMBER IS ELEVATION AT END OF LINE IN FEET


LEADER

The diagram illustrates a vertical soil boring profile. A vertical line represents the borehole. At the top, the label "SB405" is positioned above an arrow pointing left, labeled "BORING NUMBER". A green square is placed on the vertical line, with an arrow pointing left from it labeled "SOIL SAMPLE COLLECTED". An arrow points downwards along the vertical line, labeled "SOIL BORING". At the bottom, an arrow points right along the vertical line, labeled "END OF BORING".

DRAWN BY: D.W. MACDOUGALL	TITLE: GEOLOGICAL CROSS SECTIONS A-A', B-B' AND C-C' OLD FIRE FIGHTING TRAINING AREA NAVSTA NEWPORT - NEWPORT, RHODE ISLAND		
PREPARED BY: D. HARTIGAN			
CHECKED BY: S. PARKER			
	SOURCE: BASE PLAN BY SEE NOTES		
	SCALE: AS SHOWN	DATE: JANUARY 23, 2003	PROJ. NO: 4152
PROJECT MANAGER: S. PARKER	DRAWING NO: FIGURE 4-2	ACFILE NAME: DWC4152J1401.FIG.4-2.DWC	REV: 0
PROGRAM MANAGER: G. GARDNER			



**GRAPHIC SCALE**  
VERT: 1 INCH = 10 FEET      HORIZ: 1 INCH = 40 FEET  
VERTICAL EXAGGERATION = 4X



**NOTES:**  
1. THE DEPTHS AND THICKNESSES DETERMINED FOR THE SUBSURFACE STRATA WERE GENERALIZED FROM AND INTERPOLATED BETWEEN TEST BORINGS. THE STRATIFICATION LINES REPRESENT AN APPROXIMATE BOUNDARY BETWEEN SOIL TYPES; THE TRANSITION MAY BE GRADUAL. INFORMATION ON SUBSURFACE CONDITIONS EXIST ONLY AT THE LOCATION OF THE TEST BORINGS; THEREFORE, IT IS POSSIBLE THAT THE SUBSURFACE CONDITIONS MAY VARY FROM THOSE INDICATED.

2. WELL SCREEN WIDTHS ARE NOT TO SCALE.

3. HORIZONTAL DATUM IS BASED ON THE RI STATE PLANE COORDINATE SYSTEM NAD 1927. VERTICAL DATUM IS BASED ON NAVAL BASE MEAN LOW WATER (NGVD 1929 MINUS 1.6 FEET).

4. BASE PLAN BY GEURRIERE AND HALNON, INC., JULY 1997, DATED NOVEMBER 10, 1997, PROJ. NO. 7578 CTO 288, BY BROWN AND ROOT ENVIRONMENTAL.

5. GROUND ELEVATIONS WERE BASED ON BORING LOGS PROVIDED BY TRC.

6. ELEVATIONS OF SUBSURFACE CONTACTS WERE GENERALIZED FROM BORING LOGS BY TRC AND TTNUS.

7. BASED ON THE SEISMIC REFRACTION SURVEY RESULTS, THE ESTIMATED ACCURACY OF DEPTH OF BEDROCK IS +/- 15 PERCENT OR 2 FEET, WHICHEVER IS GREATER. THE DEPTHS DETERMINED FOR BEDROCK X ARE DEPTHS OF COMPETENT ROCK; DEEPLY WEATHERED ROCK MAY OCCUR AT SHALLOWED DEPTHS.


8. PRESUMPTION MADE THAT APPROXIMATELY 1-2 FEET OF TOPSOIL (FILL) LIES BETWEEN THE MOUNDS AND ACROSS THE EASTERN PORTION OF THE SITE, UNLESS OTHERWISE SPECIFIED.

9. BEDROCK ELEVATIONS ARE BASED ON THE DEPTH TO BEDROCK OBSERVED IN TEST PITS AND BORINGS. SEISMIC REFRACTION SURVEY RESULTS WERE USED TO SUPPLEMENT THESE DATA. IF A REFUSAL WAS NOTED IN A BORING THE TOP OF BEDROCK WAS ASSUMED TO BE WITHIN ONE FOOT OF THE REFUSAL DEPTH. THE BEDROCK CONTOURS ARE INTERPRETATIONS OF THESE DATA AND THE ACTUAL BEDROCK ELEVATION MAY BE DIFFERENT FROM THE ELEVATION INDICATED.

10. ALL LOCATIONS TO BE CONSIDERED APPROXIMATE.

11. PLAN NOT TO BE USED FOR DESIGN.

8.00  
SOIL ABOVE THIS LINE TO BE REMOVED  
NUMBER IS ELEVATION AT END OF LINE IN FEET



DRAWN BY: D.W. MACDOUGALL  
PREPARED BY: D. HARTIGAN  
CHECKED BY: S. PARKER

**TITLE:** GEOLOGICAL CROSS SECTIONS D-D', E-E' AND F-F'  
**OLD FIRE FIGHTING TRAINING AREA**  
**NAVSTA NEWPORT - NEWPORT, RHODE ISLAND**  
**SOURCE:** BASE PLAN BY SEE NOTES  
**SCALE:** AS SHOWN      **DATE:** JANUARY 26, 2003      **PROJ. NO.:** 4152  
**PROJECT MANAGER:** S. PARKER      **PROGRAM MANAGER:** G. GARDNER  
**DRAWING NO.:** 4-3      **ACFILE NAME:** DWG\4152\1401\FIG\_4-3.DWG      **REV:** 0

**APPENDIX A**  
**SITE PHOTOGRAPHS**



Photograph 1                    OFFTA Site, NAVSTA Newport, RI                    January 2001  
Central Mound viewed from west (prior to construction of temporary parking lot)



Photograph 2                    OFFTA Site, NAVSTA Newport, RI                    January 2001  
Central Mound viewed from southeast



Photograph 3  
Central Mound viewed from northeast

OFFTA Site, NAVSTA Newport, RI

January 2001




Photograph 4

OFFTA Site, NAVSTA Newport, RI

January 2001

Mound No. 2 viewed from east (prior to construction of temporary parking lot)



Photograph 5                    OFFTA Site, NAVSTA Newport, RI                    January 2001  
Mound No. 2 viewed from west; Mound No. 1 is to the right of the frame



Photograph 6                    OFFTA Site, NAVSTA Newport, RI                    January 2001  
OFFTA shoreline viewed from east

**APPENDIX B**  
**FIELD LOGS**

- RI Surface Sample Descriptions
- RI Test Pit Logs
- RI Soil Boring Logs
- PDI Soil Boring Logs

## **RI Surface Sample Descriptions**

### **Surface Sample ID**

**SS-3**

**SS-5**

**SS-25**

**SS-26**

**SS-325**

**SS-326**

**SS-11 (No Description available)**

**B8**

**B9**

**B-10**

**B-11**

**B14**

**B15**

**SITE 09 – OLD FIREFIGHTING TRAINING AREA  
SURFACE SOIL SAMPLE LOG**

SAMPLE NUMBER	DATE	ANALYSES	SOIL DESCRIPTION
SS-01	4/11/90	TCL, TAL, DIOXIN (ARCHIVED)	SILT AND FINE SAND, MEDIUM DENSE, BROWN
SS-02	4/11/90	TCL, TAL, DIOXIN (ARCHIVED)	FINE SAND, SOME SILT, TRACE GRAVEL, DARK BROWN - (SAMPLE SPLIT WITH EPA)
SS-03	4/11/90	TCL, TAL, DIOXIN (ARCHIVED)	FINE SAND AND SILT, TRACE ORGANICS, BROWN
SS-04	4/11/90	TCL, TAL, DIOXIN (ARCHIVED)	FINE SAND, SOME SILT, BROWN
SS-05	4/11/90	TCL, TAL, DIOXIN (ARCHIVED)	FINE SAND, SOME SILT, BROWN
SS-06	4/11/90	TCL, TAL, DIOXIN (ARCHIVED)	0-6" LOOSE PEBBLES AND SHELLS; 6-12" COARSE SAND AND GRAVEL, SOME COBBLES, TRACE ASPHALT, BROWN

**TABLE 2-3**  
**NETC - NEWPORT**  
**U.S. NAVY - NORTHERN DIVISION**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**SURFACE SOIL SAMPLE DESCRIPTIONS**

Page 1 of 2

Sample I.D.	Date Sampled	Time Sampled	Soil Description
-------------	--------------	--------------	------------------

**Surface Soil Samples**

FF-SS12	11/3/93	0850	Brown F-M SAND & ORGANICS, little gravel & rock fragments, dry, no odor, 0" to 9".
FF-SS13	11/3/93	0915	Brown F SAND & ORGANICS, some M sand, trace gravel & rock fragments, dry, no odor, 0" to 10".
FF-SS14	11/3/93	0930	Brown F SAND & ORGANICS, little silt, dry, no odor, 0" to 10".
FF-SS15	11/3/93	1005	Brown F SAND & ORGANICS, trace rock fragments, dry, no odor, 0" to 10".
FF-SS16	11/3/93	1035	Tan F SAND & ORGANICS, 0" to 3". Brown F SAND, little silt & organics, dry, no odor, 0" to 10".
FF-SS17	11/3/93	1100	Brown F SAND & ORGANICS, little silt & rock fragments, dry, no odor, 0" to 11".
FF-SS18	11/3/93	1120	Brown F SAND, some organics, little silt & rock fragments, 0" to 7".
FF-SS19	11/3/93	1200	Brown FILL, F sand & organics, little silt & gravel, dry, no odor, 0" to 12".
FF-SS20	11/3/93	1215	Brown FILL, F sand & rock fragments, little organics & silt, trace brick & asphalt, dry, no odor, 0" to 10".
FF-SS21	11/4/93	0805	Brown FILL, F-M sand & organics, some rock fragments, trace gravel & glass, dry, no odor, 0" to 9".
FF-SS22	11/4/93	0830	Brown FILL, F sand & organics, some rock fragments, trace M sand & silt, dry, no odor, 0" to 10".
FF-SS23	11/4/93	0850	Brown F SAND & ORGANICS, little silt, trace gravel & rock fragments, dry, no odor, 0" to 10".
FF-SS24	11/4/93	0905	Brown F SAND & ORGANICS, little silt & rock fragments, dry, no odor, 0" to 9".
FF-SS25	11/4/93	0925	Brown FILL, F sand & organics, some silt, little rock fragments, dry, no odor, 0" to 9".
FF-SS26	11/4/93	0950	Brown FILL, F sand & organics, trace M sand & gravel, dry, no odor, 0" to 9".
FF-SS27	11/4/93	1220	Brown F SAND & ORGANICS, trace gravel & rock fragments, dry, no odor, 0" to 12".
FF-SS28	11/4/93	1020	Brown F SAND & ORGANICS, trace rock fragments, dry, no odor, 0" to 8".
FF-SS29	11/4/93	1040	Brown F SAND & ORGANICS, some rock fragments, trace M sand, dry, no odor, 0" to 10".
FF-SS30	11/4/93	1125	Brown F SAND & ORGANICS, some silt, dry, no odor, 0" to 9".
FF-SS31	11/4/93	1200	Brown F SAND & ORGANICS, some rock fragments, trace gravel & M sand, dry, no odor, 0" to 10".

**TABLE 2-3**  
**NETC - NEWPORT**  
**U.S. NAVY - NORTHERN DIVISION**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**SURFACE SOIL SAMPLE DESCRIPTIONS**

Page 2 of 2

Sample I.D.	Date Sampled	Time Sampled	Soil Description
-------------	--------------	--------------	------------------

Soil Boring Surface Soil Samples

FF-B81	11/22/93	0935	Brown FILL, F sand & organics, trace gravel & silt, 0" to 7". Grey FILL, F sand, brick, dry, no odor, 7 to 18"
FF-B91	11/23/93	0840	Brown FILL, F sand & organics, some rock fragments, dry, no odor, 0" to 12".
FF-B101	11/23/93	1420	Brown FILL, F sand & organics, some rock fragments, little asphalt & concrete, dry, no odor, 0" to 12".
FF-B111	11/24/93	0800	Brown FILL, F sand & organics, some rock fragments & gravel, dry, no odor, 0" to 12".
FF-B121	11/24/93	0812	Brown F SAND & SILT, some gravel, dry, no odor, 0" to 12".
FF-B131	11/23/93	1300	Brown FILL, F sand & brick fragments, dry, no odor, 0" to 12".
FF-B141	12/13/93	0910	Brown FILL, F sand & organics, trace rock fragments, dry, no odor, 0" to 12".
FF-B151	12/13/93	1315	Brown FILL, F sand & organics, some rock fragments, trace brick fragments, dry, no odor, 0" to 12".
FF-B161	11/23/93	0930	Brown F SAND & SILT, some organics, M-sand, & gravel, dry, no odor, 0" to 11".
FF-B171	11/24/93	0717	Brown F SAND, some silt & M-C gravel, trace cobbles, dry, no odor, 0" to 12".
FF-B181	11/23/93	0810	Brown F SAND, trace silt, dry, no odor, 0" to 12".

Well Boring Surface Soil Samples

FF-M61	11/30/93	0755	Brown TOPSOIL, 0" to 6". Brown F SAND, some silt, little gravel, trace asphalt, dry, no odor, 6" to 12".
FF-M71	11/29/93	1311	Brown F SAND, little cobbles, trace silt, 0" to 12".
FF-M81	11/30/93	1319	Brown TOPSOIL, 0" to 3". Brown F SAND, little cobbles, trace silt, dry, no odor, 3" to 12".
FF-M91	12/01/93	0715	Brown TOPSOIL, 0" to 6". Brown SILT & ROCK fragments, little F sand, dry, no odor, 6" to 12".
FF-M101	11/29/93	0825	Brown FILL, topsoil, 0" to 6". Brown FILL, F sand & silt, little brick fragments, dry, no odor, 6" to 12".
FF-M111	11/29/93	1020	Brown FILL, F sand & plastic, 0" to 3". FILL, black charred wood, little asphalt & concrete, dry, no odor, 3" to 12".



TETRA TECH NUS, INC.

## SAMPLE LOG SHEET - SOLID PHASE

Site Name: OFFTA Site 09  
Sample ID: OFF - SS-325-0001Tetra Tech, NUS Job No./PMS 5278-1020  
QC Information: NA (if applicable)Sample Method: Collected w/ sharp-shooter shovel (steel) + trowel  
Depth Sampled: 0.5 feet bgs (vac) composite (0-inches - not + SVOC)  
Sample Date & Time: 11/19/98 0853 hours Dup NA hours  
Sampler(s): Coran, McKenna, Parker, Pillion, Jalkut (circle applicable)Data Recorded By: K Jalkut  
SignatureFID  
PID/OVA Monitor Reading: No FID readings ppm

## TYPE OF SAMPLE: (Check all that apply)

- Soil Trip Blank\*  
 Sediment Rinsate Blank\*  
 Lagoon/Pond Field Duplicate collected  
 Grab Grab (vac) Other (Specify): \_\_\_\_\_  
 Composite (metals/SVOC)

Description: (Sand, Clay, Muck, Peat, Dry, Moist, Wet, Etc.) Brown, organic-rich silty soil, very gravelly. No visible stains.

SAMPLE DATA/REMARKS: Physical @ 9 inches (no.75 ft bgs). Attempted several spots - could not get below 9 inches. Composted 0 to 9 inches from sidewalls for metals + SVOCs.

ANALYSIS	BOTTLE LOT NO.	NOTES/SKETCH:
TCL VOCs	3K5g Enviro sampler ✓	* Did not split samples
TCL SVOCs	7/1x1602 um	✓ Edge of central mound - near playground
TAL metals	JAR	* No dioxin analysis
Dioxin	→ NA	
LOTS:		
1602 JAR = 6254010		
Enviro = EN050005		



TETRA TECH NUS, INC.

## SAMPLE LOG SHEET - SOLID PHASE

Site Name: OFFTA Site 09  
Sample ID: OFF-SS-326-0001Tetra Tech, NUS Job No./PMS 5278-1020  
QC Information: NA (if applicable)Sample Method: Collected w/ shovel + trowel  
Depth Sampled: 0.5 feet bgs (voc) Composite 0-12 inches  
Sample Date & Time: 11/19/98 12:15 hours Dup NA hours  
Sampler(s): Conan, McKenna, Parker, Pillion, Jalkut (circle applicable)Data Recorded By: K Jalkut  
Signature

FID PID/DOA Monitor Reading: No FID readings ppm

## TYPE OF SAMPLE: (Check all that apply)

- Soil Trip Blank\*  
 Sediment Rinsate Blank\*  
 Lagoon/Pond Field Duplicate collected  
 Grab Grab voc Other (Specify):  
 Composite (concrete/voc)

Description: (Sand, Clay, Muck, Peat, Dry, Moist, Wet, Etc.) Brown silty sand; few to little gravel. At 1' bgs - soil was transitioning

SAMPLE DATA/REMARKS: Able to advance to 1' bgs. Composted from sidewalls 0-12 inches bgs.  
Collected VOC fraction from middle of sidewall - approx 1cm thick bgs.

ANALYSIS	BOTTLE LOT NO.	NOTES/SKETCH:
TCL VOCs	3x5g Enviro sampler ✓	* no dioxin sample
TCL SVOCs	1x16oz ppm jar ✓	* Did not split sample w/ Gannett-Fleming. G-F collected MS/land at this location
TAL METALS	jar	* Located W-N-W of TT NUS test pit 13
DIOXIN	→ NA	
LOTS:		
16oz jar = 02.5/10/00		
Enviro = Enviro 0005		

## **RI Test Pit Logs**

### **Test Pit ID**

**TP2**

**TP3**

NETC - Newport  
Site 09 - Old Fire Fighting Training Area  
Test Pit Log FF-TP2  
January 11, 1994

Rationale: To characterize the fill material in the western portion of the soil mound.

Date: January 11, 1994

Dimensions: 15' X 4' X 8.5' (L X W X D).

TRC Inspector: Tom McMorrow & John Coykendall

Excavation Subcontractor: Clean Harbors

Sample ID: FF-TP21 collected from oily soils encountered 7 to 8 feet below grade.

FF-TP22 collected from 4.5 feet below grade.

FF-TP23 collected from 2 feet below grade.

DEPTH (FT)	DESCRIPTION
0 - 3'	FILL, brown F-M SAND, some cobbles, little concrete and asphalt, trace wire.
3 - 6'	FILL, brown/grey F SAND and SILT, little rock fragments and cobbles, trace brick.
6 - 7'	FILL, brown C sand and brick, damp.
7 - 8'	Grey/black F-M SAND, some cobbles and rock fragments, black staining with a strong petroleum odor.  Strong petroleum odor with PID readings of 1200 ppm were noted in soils from the 7 to 8 foot layer.

#### CONCLUSIONS

Construction debris encountered from surface to a depth of 7 feet. Strong Petroleum odor and staining encountered in soils at the ground water table (approx. 8 feet).

NETC - Newport  
Site 09 - Old Fire Fighting Training Area  
Test Pit Log FF-TP3  
January 11, 1994

Rationale: To characterize the fill material in the northern portion of the soil mound in the central portion of the site.

Date: January 11, 1994

Dimensions: 15' X 4' X 8.5' (L X W X D).

TRC Inspector: Tom McMorrow & John Coykendall

Excavation Subcontractor: Clean Harbors

Sample ID: FF-TP31 collected from oily soils encountered at a depth of 7 to 8 feet.

FF-TP32 collected from approx. 7 feet below grade.

FF-TP33 collected from approx. 3 feet below grade.

DEPTH (FT)	DESCRIPTION
0 - 4'	FILL, brown F to M SAND and rock fragments, little brick, concrete, and wood, dry, no odor.
4 - 4.5'	FILL, asphalt layer.
4.5 - 7'	FILL, dark brown F-M SAND and rock fragments, brick and metal.
7 - 8'	Light brown sand with rusted metal pieces. Black staining and petroleum odor noted in soils at ground water table (approx 8 feet).

### CONCLUSIONS

Construction debris encountered from surface to depth of 7 feet. Petroleum odor and stained soils noted in soils at ground water table.

**RI Soil Boring Logs**

**Soil Boring/Monitoring Well ID**

**B-8**

**B-9**

**B-10**

**B-11**

**B-14**

**B-15**

**MW-3S**

Test Boring: B-8  
 Site 09 - Old Fire Fighting Training Area  
 NETC - Newport  
 Boring Depth: 23 Feet

Drilling Company: Hardin-Huber, Inc.  
 Drillers: K. Callendar & P. Hendrick  
 TRC Inspector: J. Coykendall & K. Prochorena  
 Test Boring Coordinates:  
 N 156989.51  
 E 546998.41

Date Started: November 22, 1993  
 Date Completed: November 22, 1993  
 Approximate Depth to Water: 11 feet  
 Test Boring Elevation: 11.52 Feet (mhw)

Depth (feet)	Field Measurements			Soil Description	Lithology
	Blow Counts	OVA (ppm)	HNU (ppm)		
0-2	3 24 20 21	ND	ND	0-7" FILL, brown F sand & organics, trace gravel & silt. 7-18" FILL, grey F sand, some rock fragments, little gravel & brick fragments, trace asphalt, dry, no odor.	0.0
2-4	17 50 50/4"	ND	ND	0-8" FILL, brown/grey F sand, some silt & rock fragments, little gravel, trace glass. 8-10" FILL, brick. 10-12" FILL, brown F sand & silt, some gravel, dry, no odor.	
4-6	50/2.5"	NR	NR	FILL, grey shale fragments, dry. Recovery = 1".	
6-8	33 12 11 42	ND	6	FILL, brown/grey F sand & rock fragments, some silt & gravel. Piece of brick in tip, moist, no odor. Recovery = 12".	
8-10	22 28 42 45	ND	7	FILL, brown/grey F-M sand & rock fragments, some gravel, little silt, asphalt, & brick fragments, moist, no odor. Recovery = 16".	
10-12	39 50/5"	NR	NR	FILL, Brick & rock fragments.	11.0
12-14	22 33 50 50/4"	28	20	Grey M-F SAND, some gravel & rock fragments, trace shale fragments, strong petroleum odor & staining in bottom 4" of spoon, wet. Recovery = 12".	
14-16	20 34 50/5"	ND	6	Grey/black ROCK fragments, some M-F sand & gravel, little silt, wet, petroleum odor. Recovery = 6".	
16-18	50/3"	NR	NR	ROCK fragments, wet, slight odor. Recovery = 1".	
18-20	33 50/2"	1	8	Brown/grey F SAND & ROCK fragments, some silt, wet, slight odor. Recovery = 6".	
20-22	48 50/3"	1	2	Brown F SAND & SILT, some rock fragments & gravel, wet, slight odor. Recovery = 6".	
22-23	50/5"	ND	4	Grey ROCK fragments, some F sand & silt, wet, no odor. Recovery = 5". Auger refusal at 23'	23.0

Sample FF-B81-112293 collected from 0-1".  
 Sample FF-B82-112293 collected from 8-10".

Notes: NR = No Reading  
 ND = Not Detected

Test Boring: B-9  
 Site 09 - Old Fire Fighting Training Area  
 NETC - Newport  
 Boring Depth: 13 Feet

Drilling Company: Hardin-Huber, Inc.  
 Drillers: K. Callendar & P. Hendrick  
 TRC Inspector: J. Coykendall & K. Prochorena  
 Test Boring Coordinates:  
 N 156908.45  
 E 546915.05

Date Started: November 23, 1993  
 Date Completed: November 23, 1993  
 Approximate Depth to Water: Unknown  
 Test Boring Elevation: 17.71 Feet (mlw)

Depth (feet)	Field Measurements			Soil Description	Lithology
	Blow Counts	OVA (ppm)	HNu (ppm)		
0-2	4 37 40 28	ND	ND	0-5" FILL, brown F sand & organics, little rock fragments. 6-12" FILL, brown F sand, some rock fragments. 12-14" FILL, rock fragments, some F sand, dry, no odor.	0.0
2-4	47 50/5"	NR	NR	No Recovery	
4-6	50/5"	NR	NR	No Recovery	
6-7	100/5"	NR	NR	No Recovery	
7-9	13 11 9 50/5"	ND	ND	0-2" FILL, rock fragments. 2-10" FILL, brown F sand & silt, some rock fragments & gravel. 10-12" FILL, asphalt chunks, dry, no odor.	
9-11	67 35 29 48	ND	ND	0-2" FILL, brown F-M sand, some rock fragments, trace brick. 2-6" FILL, asphalt fragments, little brown F-M sand. 6-12" FILL, concrete fragments, dry, no odor.	
11-12	100/3"	NR	NR	FILL, concrete fragments, dry, no odor. Recovery = 1"	
12-14	89 100/3"	ND	ND	FILL, concrete fragments, dry, no odor. Recovery = 4". Auger refusal at 13'	13.0

Sample FF-B91-112393 collected from 0-1'.

Notes: NR = No Reading  
 ND = Not Detected

Test Boring: B-10  
Site 09 - Old Fire Fighting Training Area  
NETC - Newport  
Boring Depth: 7 Feet

Drilling Company: Hardin-Huber, Inc.  
Drillers: K. Callendar & P. Hendrick  
TRC Inspector: J. Coykendall & K. Prochorena  
Test Boring Coordinates:  
N 156888.50  
E 546710.64

Date Started: November 23, 1993  
Date Completed: November 23, 1993  
Approximate Depth to Water: unknown  
Test Boring Elevation: 13.66 Feet (mlw)

Depth (feet)	Field Measurements			Soil Description	Lithology
	Blow Counts	OVA (ppm)	HNU (ppm)		
0-2	4 16	ND	ND	0-8" FILL, brown F sand & organics, some rock fragments. 8-22" FILL, brown F sand, some gravel, little asphalt & concrete, dry, no odor.	0.0
	17 15			FILL, brown F sand, some rock fragments & gravel, little concrete	
2-4	21 17	ND	ND	fragments, dry, no odor. Recovery = 14".	
	46 20			No Recovery	
4-6	3 4	NR	NR		
	5 8				
6-8	33 42	ND	ND	0-3" FILL, brown F sand, some rock fragments & gravel. 3-5" FILL, asphalt pieces, little brown F sand. 5-7" FILL, brick pieces, dry, no odor.	7.0
	50/1"			Auger refusal at 7 feet.	

Sample FF-B101-112393 collected from 0-1'.

Notes: NR = No Reading  
ND = Not Detected

Test Boring: B-11  
 Site 09 - Old Fire Fighting Training Area  
 NETC - Newport  
 Boring Depth: 27 Feet

Drilling Company: Hardin-Huber, Inc.  
 Drillers: K. Callendar & P. Hendrick  
 TRC Inspector: J. Coykendall & K. Prochorena  
 Test Boring Coordinates:  
 N 156854.90  
 E 546767.50

Date Started: November 24, 1993  
 Date Completed: November 24, 1993  
 Approximate Depth to Water: 6 Feet  
 Test Boring Elevation: 8.39 Feet (mlw)

Depth (feet)	Field Measurements				Soil Description	Lithology
	Blow Counts	OVA (ppm)	HNU (ppm)			
0-2	3 10 26 28	ND	ND	0-8" FILL, brown F sand & organics, little rock fragments & silt. 8-24" FILL, dk brown F sand, some rock fragments & gravel, dry, no odor.		0.0
2-4	16 23 40 28	ND	ND	0-8" FILL, brown F sand, some silt, trace rock fragments & brick. 8-22" FILL, brown F sand, some silt & rock fragments, little gravel, trace wood, dry, no odor.		
4-6	12 11 8 15	ND	ND	Brown F-M SAND, some gravel & rock fragments, moist, no odor. Recovery = 18". Tip of spoon appears wet.		4.0
6-8	13 27 4 13	1	ND	0-5" Brown F-M SAND, some gravel & rock fragments. 5-8" Grey/black F-M SAND, some shell fragments. 8-20" Brown F SAND, some silt, trace shells, wet, no odor.		
8-10	4 8 21 19	.1	ND	0-11" Brown F SAND, some rock fragments, little silt, trace shells. 11-17" Black/grey TILL, F sand & silt, little rock fragments & gravel, wet, no odor.		
10-12	5 11 13 15	ND	ND	Black/grey TILL, silt, some F sand & rock fragments, little gravel, wet, no odor. Recovery = 15".		
12-14	7 15	ND	ND	0-10" Black/grey TILL, silt, some rock fragments & gravel, little F sand.		
	100/5"			10-12" Brown/grey M-F SAND, some silt & rock fragments, wet, no odor.		
14-16	6 30 12 16	ND	ND	Black/grey TILL, silt, some rock fragments & gravel, trace F sand, wet, no odor. Recovery = 14".		
16-18	9 16 33 37	ND	ND	Black/grey TILL, silt, some rock fragments & gravel, trace F sand, wet, no odor. Recovery = 12".		
18-20	7 9 19 25	ND	ND	Black/grey TILL, silt, some rock fragments & gravel, trace F sand, wet, no odor. Recovery = 8".		
20-22	7 12 19 23	ND	ND	0-6" Black/grey TILL, silt, some rock fragments & gravel, trace F sand.		
22-24	12 13 12 25	ND	ND	6-12" Highly weathered BEDROCK, wet, no odor.	21.0	
25-27	35 40 50/4"	ND	ND	Brown/grey weathered BEDROCK, wet, no odor. Recovery = 12".		
				Brown/grey weathered BEDROCK, wet, no odor. Recovery = 8".	27.0	

Sample FF-B111-112493 collected from 0-1".  
 Sample FF-B112-112493 collected from 4-6".

Note: ND = Not Detected

Test Boring: B-14  
 Site 09 - Old Fire Fighting Training Area  
 NETC - Newport  
 Boring Depth: 28 Feet

Drilling Company: Soil Explorations  
 Drillers: G. Junta & G. Caquette  
 TRC Inspector: J. Coykendall  
 Test Boring Coordinates:  
 N 156893.04  
 E 547371.18

Date Started: December 13, 1993  
 Date Completed: December 13, 1993  
 Approximate Depth to Water: 27 Feet  
 Test Boring Elevation: 30.71 Feet (mlw)

Depth (feet)	Field Measurements				Soil Description	Lithology
	Blow Counts	OVA (ppm)	HNU (ppm)			
0-2	5 5 10 30	ND	ND		0-12" FILL, brown F sand & organics, trace rock fragments. 12-16" FILL, dk brown F-M sand, little rock fragments, trace brick, dry, no odor.	0.0
5-7	7 9 16 30	ND	ND		FILL, brown F-M sand, some gravel & rock fragments, little concrete & asphalt, trace brick fragments, dry, no odor. Recovery = 18".	
7-9	27 30 27 34	ND	ND		FILL, brown/grey F-M sand, some rock fragments & cobbles, little concrete & gravel, trace asphalt & brick fragments, dry, no odor. Recovery = 22".	
9-11	61 120/4"	ND	ND		FILL, brown/grey F-M sand, some rock fragments & cobbles, little concrete & gravel, trace asphalt & brick fragments, dry, no odor. Recovery = 2".	
15-17	9 7 6 6	ND	ND		FILL, grey/black silt, little F sand & rock fragments, trace gravel, moist, no odor. Recovery = 18".	
17-19	9 13 25 10	ND	ND		0-8" FILL, grey/black silt, little F sand & rock fragments, trace gravel. 8-18" FILL, brown F sand, little cobbles, trace wood & brick, moist, no odor.	
20-22	120/4"	NR	NR		FILL, concrete fragments. Recovery = 1".	23.0
25-27	50/1"	NR	NR	No Recovery	Auger to 28 feet and hit auger refusal. Bedrock estimated to be approximately 23 feet below grade. Water in borehole at approximately 27 feet below grade.	28.0
Sample FF-B141-121393 collected from 0-1'. Sample FF-B142-121393 collected from 15-17'.						

Notes: NR = No Reading  
 ND = Not Detected


**Test Boring: B-15**  
**Site 09 - Old Fire Fighting Training Area**  
**NETC - Newport**  
**Boring Depth: 22.5 Feet**

**Drilling Company:** Soil Explorations  
**Drillers:** G. Juinta & G. Caquette  
**TRC Inspector:** J. Cokendall  
**Test Boring Coordinates:**  
N 156895.02  
E 547425.72

Date Started: December 13, 1993  
Date Completed: December 13, 1993  
Approximate Depth to Water: Unknown  
Test Boring Elevation: 27.58 Feet (mlw)

Depth (feet)	Field Measurements				Soil Description	Lithology
	Blow Counts	OVA (ppm)	HNu (ppm)			
0-2	14 7	14 6	ND	ND	0-4" FILL, brown F sand & organics, little rock fragments. 4-12" FILL, brown F-M sand, some rock fragments, trace brick fragments, dry, no odor.	0.0
2-4	11 9	9 11	ND	ND	FILL, brown F-M sand, some rock fragments & cobbles, little gravel, trace concrete, asphalt & brick, dry, no odor. Recovery = 18".	
4-6	11 100/3"	9	ND	ND	FILL, brown F-M sand & rock fragments, some cobbles & gravel, trace brick & concrete, dry, no odor. Recovery = 12".	
8-10	20 67	65 62	ND	ND	FILL, brown/grey M-F sand & gravel, some rock fragments & cobbles, little concrete & asphalt, trace brick & glass, dry, no odor. Recovery = 14".	
10-12	13 34 100/4"	19	ND	ND	FILL, grey F-M sand, some rock fragments & cobbles, little concrete & asphalt, trace brick, dry, slight petroleum odor. Recovery = 18".	
15-17	9 18	12 26	ND	ND	FILL, brown F sand & silt, some gravel & cobbles, little rock fragments & concrete, trace brick, moist, no odor. Recovery = 12".	
17-19	100/4"		NR	NR	No recovery - piece of wood & chunk of asphalt in tip of spoon	
20-21	25 100/1"		NR	NR	No Recovery	20.0
					Augered to refusal at 22.5 feet - did not reach water table. Bedrock estimated to be approximately 20 feet below grade.	22.5
					Sample FF-B151-121393 collected from 0-1". Sample FF-B152-121393 collected from 10-12". Sample FF-B153-121393 collected from 15-17".	

BORING NO.: MW-3 CONTRACTOR: CDS DATE STARTED: 4/24/90  
 PROJECT NO.: 6760-N81 DRILLERS: GAYLORD/QUINN DATE COMPLETED: 4/24/90  
 SECTION: U.S. NAVY-NETC TRC INSPECTOR: GLEZEN/MCMORROW WATER TABLE LEVEL: 6 FT.  
 LOCATION: NEWPORT, RI DRILLING METHOD: 4 1/4" HOLLOW STEM AUGERS LOCATION: N 10.418  
 SITE: 09-FIREFIGHTER GROUND ELEVATION: 9.83 E 4.546  
 BORING DEPTH: 14 FT. CASING ELEVATION: 9.61



END OF BORING - 14 FT.

STRONG PETROLEUM ODOR FROM 4-12 FT.  
VISIBLE OILY STAINING FROM 4-8 FT.

SAMPLE FF-MW31-424 TAKEN FROM 6-8 FT.  
SAMPLE FF-MW32-424 TAKEN FROM 12-14 FT.

**PDI Soil Boring Logs**

**Soil Boring/Monitoring Well ID**

**SB400**

**SB403**

**SB405**

**SB406**

**SB407**

**SB410**

**SB411**

**SB412**

**SB413B**

**SB415**

**SB416**

**SB417**

**SB418**

**SB419**

**SB422**

**SB433**

BORING LOG FOR: CTO 833 - OFFTA - SITE 09  
 PROJECT NO.: 4152-0552  
 LOGGED BY: J.DANIELI / J. LAMBERT  
 DRILLED BY (Company/Driller): AMERICAN DRILLING / CARL BIERHOLM  
 GRID. SURFACE ELEVATION: 7.3' (MLW)

TRANSCRIBED BY: MES

BORING NO.: SB-400  
 START DATE: 12/01/03  
 COMPLETION DATE: 12/01/03  
 MON. WELL NO.: --  
 CHECKED BY: JL

DEPTH (FEET)	BLOWS PER 6"	SAMP REC. / SAMP LENG.	SAMPLING TIME & SAMPLE NO. (QA/QC STATUS)	DEPTH MAT'L CHG./WELL PROFL	SOIL DENSITY/ CONSIS. or ROCK HARD.	CLR	MATERIAL CLASSIFICATION	USCS or ROCK BRKN	REMARKS (moisture condition; odors; geological classification; rock weathering; etc.)	FIELD SCREENING DATA METHOD = [FID, (PPM)]	
0	3				Medium Dense	Gray-Brown	0.0-0.4' = fine to coarse sand, some silt, trace gravel	SW	Dry	PID = 0.0	
	5	0.6									
	6	2.0'	1300 OFF-SB-400-0002	Fill	Light Brown		0.4-1.6' = Silty fine to coarse SAND, some gravel (rounded)	SM		FID = 0.0	
2	9				Very Dense		Silty fine to coarse SAND, trace gravel		Dry Note: caught on a piece of riprap - will move over	PID = 0.0	
	15									FID = 0.0	
	100/2"										
4		0.4'	No sample				Auger from 0-4' - no samples collected				
		0.5'									
0			No sample								
2			No sample								
4			No sample								
17			No sample		Very Dense	Tan	0.0-0.3' = Fine sand 0.3-0.9' = Fine to coarse SAND, some silt, some gravel 0.9-1.2' = Cobble	SP SW	Moist Brick fragments, trace coal, slag fragments	PID = 6.8	
19		1.2'									
33		2.0'								FID = 9.4	
6	120/3"										
	50						0.0-0.4' = Cobble 0.4-1.1' = Fine to coarse sand, some silt, some gravel bottom 0.5' very dense	--			
	44										
	60/3"	1.1'	No sample								
8	60/3"	1.5'									
	60/2"	0.0'	1340 OFF-SB-400-0810								
10		2.0'					No recovery				

TYPE OF DRILLING RIG:	CME - Track mounted	Tetra Tech NUS, Inc.
METHOD OF ADVANCING BORING:	Hollow stem auger	
METHOD OF SOIL SAMPLING:	3" split spoon driven by 300 lb. hammer dropped 18"	
METHOD OF ROCK CORING:	N/A	
GROUNDWATER LEVELS:		
OTHER OBSERVATIONS:	FIRST ATTEMPT = 4' refusal, second attempt = 12' refusal, third attempt = 12' refusal	BORING NO.: SB-400 PAGE: 1 OF 2

BORING LOG FOR: CTO 833 - OFFTA - SITE 09  
 PROJECT NO.: 4152-0552  
 LOGGED BY: J.DANIELI / J. LAMBERT  
 DRILLED BY (Company/Driller): AMERICAN DRILLING / CARL BIERHOLM  
 GRD. SURFACE ELEVATION: 7.3' (MLW)

BORING NO.: SB-400  
 START DATE: 12/01/03  
 COMPLETION DATE: 12/01/03  
 MON. WELL NO.: --  
 ELEVATION FROM: \_\_\_\_\_  
 CHECKED BY: JL

DEPTH (FEET)	BLOWS PER 6"	SAMP REC. / SAMP LENG.	SAMPLING TIME & SAMPLE NO. (QA/QC STATUS)	DEPTH MAT'L CHG/ WELL PROFL	SOIL DENSITY/ CONSIS. or ROCK HARD.	CLR	MATERIAL CLASSIFICATION	USCS or ROCK BRKN	REMARKS (moisture condition; odors; geological classification; rock weathering; etc.)	FIELD SCREENING DATA METHOD = [FID, (PPM)]
10	65/0"		No sample		Very Dense		No recovery - slough only (natural materials in slough)		Augers have been moving well, last 4' driller believes we are pushing a cobble	
					Very Dense					
12			No sample		Very Dense					
					Very Dense					
0			No sample		Very Dense		Auger to 2' - no samples collected from 0-2'			
2	70/2"	0.2' 0.2'	No sample		Very Dense		Silty fine to coarse sand, some gravel will keep 0-2' sample from first attempt	SM	Dry	
4					Very Dense					
6					Very Dense					
8		1.0'	No sample		Very Dense	Light Brown	Silty fine to coarse sand, some gravel	SM		
10	4 70/2"	0.5' 1.0'	No sample		Very Dense		No recovery, material all slough, angular fragments, no manmade material			
12	70/1"			EOB (refusal)					Spoon and auger refusal - borehole complete	

TYPE OF DRILLING RIG:	Track mounted	Tetra Tech NUS, Inc.
METHOD OF ADVANCING BORING:	Hollow stem auger	
METHOD OF SOIL SAMPLING:	3" split spoon driven by 300 lb. hammer dropped 18"	
METHOD OF ROCK CORING:	N/A	
GROUNDWATER LEVELS:		
OTHER OBSERVATIONS:		BORING NO.: SB-400
		PAGE: 2 OF 2



BORING LOG FOR:

CTO 833 - OFFTA - SITE 09

PROJECT NO.:

4152-0552

LOGGED BY:

J. LAMBERT

DRILLED BY (Company/Driller):

AMERICAN DRILLING / RODNEY DEAN

GRD. SURFACE ELEVATION:

9.4' (MLW)

BORING NO.:

SB-403

START DATE: 11/24/03

COMPLETION DATE: 11/25/03

MON. WELL NO.: --

CHECKED BY: JL

TRANSCRIBED BY: MES

ELEVATION FROM: \_\_\_\_\_

DEPTH (FEET)	BLOWS PER 6"	SAMP REC. / SAMP LENG.	SAMPLING TIME & SAMPLE NO. (QA/QC STATUS)	DEPTH MAT'L CHG/ WELL PROFL'	SOIL DENSITY/ CONSIS. or ROCK HARD.	CLR	MATERIAL CLASSIFICATION	USCS or ROCK BRKN	REMARKS (moisture condition; odors; geological classification; rock weathering; etc.)	FIELD SCREENING DATA METHOD = [FID, (PPM)]
0							Auger to 2' bgs - no sample collected			
2										
	5									
	10									
	8	1.5	2	1600 (11/24/03) OFF-SB-403-0204	Medium Dense	Brown	0-0.6' = SILT, some fine sand, trace angular gravel	ML	Moist (Angular gravel)	PID = 188
	10									
	6									
	10	1.2	2	No sample		Dark brown Orange brown	0.6-0.9' = similar to above, some black staining 0.9-1.5' = SILT, some fine sand, some gravel			FID = 0.0
	14									
	16									
	6									
	7	0.8	2	1615 (11/24/03) OFF-SB-403-0608		Gray-orange Red-black	0-0.4' = SILT, some angular gravel 0.4-0.7' = Friable fill material - SLAG?	Fill		
	8									
	9									
	4									
	7									
	5									
	2	0.6	2	No sample		Red-black	0.7-0.8' = GLASS layer 0.8-1.2' = SLAG (gravel - fine sand (?))			FID = 79.1
	7									
	8									
	4									
	7									
	5									
	2									
	7									
	8	1.0	2	1630 (11/24/03) OFF-SB-403-1012		Dark Gray	Fine SAND, trace shell fragments	SP		
	4									
	3									
	2									
	1	0.0	2	No sample		Very Loose	No recovery (slough)	--		PID = 35.6
	2									
	9									
	4									
	8	0.6	2	1645 (11/24/03) OFF-SB-403-1416	Medium Dense	Dark Gray	0-0.4' = Fine SAND, trace shell fragments	SP		PID = 14.0
	8									
	8						0.4-0.6' = Sandy (fine sand) SILT	ML		FID = 24.3

TYPE OF DRILLING RIG: CME 75

METHOD OF ADVANCING BORING: Hollow stem auger

METHOD OF SOIL SAMPLING: 3" split spoon driven by 300 lb. hammer dropped 18"

METHOD OF ROCK CORING: N/A

GROUNDWATER LEVELS:

OTHER OBSERVATIONS:

Tetra Tech NUS, Inc.



BORING NO.: SB-403

PAGE: 1 OF 2

BORING LOG FOR:  
PROJECT NO.:  
LOGGED BY:  
DRILLED BY (Company/Driller):  
GRD. SURFACE ELEVATION:

CTO 833 – OFFTA – SITE 09  
4152-0552  
J. LAMBERT  
AMERICAN DRILLING / RODNEY DEAN  
9.4' (MLW)

TRANSCRIBED BY: MES

ELEVATION FROM: \_\_\_\_\_

BORING NO.: SB-403  
START DATE: 11/24/03  
COMPLETION DATE: 11/25/03  
MON. WELL NO.: –  
CHECKED BY: JL

DEPTH (FEET)	BLOWS PER 6"	SAMP REC. / SAMP LENG.	SAMPLING TIME & SAMPLE NO. (QA/QC STATUS)	DEPTH MAT'L CHG./ WELL PROFL	SOIL DENSITY/ CONSI. or ROCK HARD.	CLR	MATERIAL CLASSIFICATION	USCS or ROCK BRKN	REMARKS (moisture condition; odors; geological classification; rock weathering; etc.)	FIELD SCREENING DATA METHOD = [FID, (PPM)]
16			No sample	EOB	Dense	Gray	Fine sandy SILT, some angular gravel, possible till	SM	Wet	PID = 1.8
	8									
	9		0735 (11/25/03) OFF-SB-403-1820	20'						FID = 0.0
	10						Fine sandy SILT, some gravel, trace coarse sand, possible till		Wet	PID = 0.0
	9									
	7									PID = 7.3
	12									
	14									
	14									

TYPE OF DRILLING RIG:	CME 75	Tetra Tech NUS, Inc.
METHOD OF ADVANCING BORING:	Hollow stem auger	
METHOD OF SOIL SAMPLING:	3" split spoon driven by 300 lb. hammer dropped 18"	
METHOD OF ROCK CORING:	N/A	
GROUNDWATER LEVELS:		PAGE: 2 OF 2
OTHER OBSERVATIONS:	BORING NO.: SB-403	



BORING LOG FOR:

## CTO 833 - OFFTA - SITE 09

PROJECT NO.:

4152-0552

LOGGED BY:

J. LAMBERT

DRILLED BY (Company/Driller):

AMERICAN DRILLING / RODNEY DEAN

GRD. SURFACE ELEVATION:

7.0' (MLW)

TRANSCRIBED BY: MES

BORING NO.: SB-405  
 START DATE: 11/18/03  
 COMPLETION DATE: 11/18/03  
 MON. WELL NO.: --  
 CHECKED BY: JL

DEPTH (FEET)	BLOWS PER 6"	SAMP REC. / SAMP LENG.	SAMPLING TIME & SAMPLE NO. (QA/QC STATUS)	DEPTH MAT'L CHG/ WELL PROFL	SOIL DENSITY/ CONSIS. or ROCK HARD.	CLR	MATERIAL CLASSIFICATION	USCS or ROCK BRKN	REMARKS (moisture condition; odors; geological classification; rock weathering; etc.)	FIELD SCREENING DATA METHOD = [FID, (PPM)]
0							Auger to 2' - no samples collected from 0-2'			
2										
	19									
	15									
	15									
4	17									
	20									
	21									
	20									
6	10									
	3									
	10									
	6									
8	5									
	6									
	6									
10	5									
	6									
	10									
	7									
12	5									
	11									
	19									
	24									
	120/4"									
14										
	17									
	53									
	120/5"									
16										

TYPE OF DRILLING RIG:

CME - Track mounted

METHOD OF ADVANCING BORING:

Hollow stem augers

METHOD OF SOIL SAMPLING:

3" Split spoons driven with 300 lb. hammer dropped 18"

METHOD OF ROCK CORING:

N/A

GROUNDWATER LEVELS:

~ 10' bgs

OTHER OBSERVATIONS:

Tetra Tech NUS, Inc.



BORING NO.: SB-405

PAGE: 1 OF 2

BORING LOG FOR: CTO 833 – OFFTA – SITE 09  
 PROJECT NO.: 4152-0552  
 LOGGED BY: J. LAMBERT  
 DRILLED BY (Company/Driller): AMERICAN DRILLING / RODNEY DEAN  
 GRD. SURFACE ELEVATION: 7.0' (MLW)

BORING NO.: SB-405  
 START DATE: 11/18/03  
 COMPLETION DATE: 11/18/03  
 MON. WELL NO.: --  
 CHECKED BY: JL

DEPTH (FEET)	BLOWS PER 6"	SAMP REC. / SAMP LENG.	SAMPLING TIME & SAMPLE NO. (QA/QC STATUS)	DEPTH MAT'L CHG./ WELL PROF'L	SOIL DENSITY/ CONSIS. or ROCK HARD.	CLR	MATERIAL CLASSIFICATION	USCS or ROCK BRKN	REMARKS (moisture condition; odors; geological classification; rock weathering; etc.)	FIELD SCREENING DATA METHOD = [FID, (PPM)]
16'	120/4"	0.0	No sample	18'	Very Dense		Split spoon refusal; steady grind on augers (auger refusal) – believed to be at or close to bedrock			
		2.0								
18'				EOB						

TYPE OF DRILLING RIG: CME - 75  
 METHOD OF ADVANCING BORING: Hollow stem auger  
 METHOD OF SOIL SAMPLING: 3" Split spoons driven with 300 lb. hammer dropped 18"  
 METHOD OF ROCK CORING: N/A  
 GROUNDWATER LEVELS: ~ 10' bgs  
 OTHER OBSERVATIONS:

Tetra Tech NUS, Inc.



BORING NO.: SB-405

PAGE: 2 OF 2

BORING LOG FOR:

CTO 833 - OFFTA - SITE 09

PROJECT NO.:

4152-0552

LOGGED BY:

J.DANIELI

DRILLED BY (Company/Driller):

AMERICAN DRILLING / CARL BEIRHOLM

GRD. SURFACE ELEVATION:

11.4' (MLW)

TRANSCRIBED BY: MES

BORING NO.: SB-406

12/03/03

START DATE: 12/03/03

COMPLETION DATE: --

MON. WELL NO.: --

CHECKED BY: DH

ELEVATION FROM: \_\_\_\_\_

DEPTH (FEET)	BLOWS PER 6"	SAMP REC. / SAMP LENG.	SAMPLING TIME & SAMPLE NO. (QA/QC STATUS)	DEPTH MAT'L CHG./ WELL PROFL	SOIL DENSITY/ CONSI. or ROCK HARD.	CLR'	MATERIAL CLASSIFICATION	USCS or ROCK BRKN	REMARKS (moisture condition; odors; geological classification; rock weathering; etc.)	FIELD SCREENING DATA METHOD = [FID, (PPM)]
0				FILL	Dense Loose	Brown	Fine silty SAND with roots, topsoil 1.0-0.2' 0.2-0.6' = fine to coarse SAND, trace silt 0.6-0.8' = piece of boulder, some rounded gravels	SM	Dry	FID = 20.6
	4	0.8 / 2.0'	1455 OFF-SB-406-0002							PID = 0.0
	5									
2	6		No sample		Loose Dense (Compact)	White Olive Gray	0.0-0.2' = pieces of cobble, concrete? 0.2-1.2' = SILT with trace sand and sub-angular gravel, pieces of Brick and asphalt	ML	Dry	FID = 0.0
	13									
	25									
	60/2"									
4									Dry	
	20	1.1 / 2.0'	No sample							FID = 0.0
	12									
	12									
6	8									
	60/4"	0.3 / 0.3'	1530 OFF-SB-406-0608		Loose	Dark Gray	Silty SAND with some gravel, pieces of cobble / concrete?	SM	Dry	FID = 0.0
8			No sample							
	20									
	12									
	17	1.0 / 2.0'			Loose	Dark Gray	Piece of concrete (0.3-0.5)		Dry	FID = 3.8
10	13									
	6									
	7	0.7 / 2.0'	1550 (& grain size) OFF-SB-406-1012							
	7									
12	9		No sample							
	7									
	8	1.0 / 2.0'			Dense	Dark Brown	0.0-0.8' = fine to medium SAND, well sorted 0.8-1.0' = SILT with sand	SP	Wet	FID = 0.0
	6									
14	12									
	6									
	8	1.4 / 2.0'	1610 (Dup 1615) OFF-SB-406-1416							
	7									
16	5				Dense	Dark Gray	SILT, trace rounded gravels and sand	ML	Wet	FID = 0.8

TYPE OF DRILLING RIG: Track mounted - CME

METHOD OF ADVANCING BORING: Hollow stem auger

METHOD OF SOIL SAMPLING: 3" split spoon - 2' long - 300 lb. hammer - 18" drop

METHOD OF ROCK CORING: N/A

GROUNDWATER LEVELS: ~ 9' bgs

OTHER OBSERVATIONS:

BORING NO.: SB-406

Tetra Tech NUS, Inc.



PAGE: 1 OF 2

BORING LOG FOR:  
PROJECT NO.:  
LOGGED BY:  
DRILLED BY (Company/Driller):  
GRD. SURFACE ELEVATION:

CTO 833 – OFFTA – SITE 09  
4152-0552  
J.DANIELI  
AMERICAN DRILLING / CARL BEIRHOLM  
11.4' (MLW)

TRANSCRIBED BY: MES  
ELEVATION FROM: \_\_\_\_\_

BORING NO.: SB-406  
START DATE: 12/03/03  
COMPLETION DATE: 12/03/03  
MON. WELL NO.: --  
CHECKED BY: DH

DEPTH (FEET)	BLOWS PER 6"	SAMP REC. / SAMP LENG.	SAMPLING TIME & SAMPLE NO. (QA/QC STATUS)	DEPTH MAT'L CHG./ WELL PROF'L	SOIL DENSITY/ CONSIS. or ROCK HARD.	CLR	MATERIAL CLASSIFICATION	USCS or ROCK BRKN	REMARKS (moisture condition; odors; geological classification; rock weathering; etc.)	FIELD SCREENING DATA METHOD = [FID, (PPM)]
16	9				Dense	Dark Gray	0.0-0.7' = silty GRAVEL with sand, till	GM	Wet	FID = 0.0
	22	1.3	No sample		Dense	Brown	0.7-1.3' = silty GRAVEL, trace sand, till	GM	Soupy	PID = 3.7
18	56				Dense	Brown	Silty sandy GRAVEL, till	GM		
	51	2.0'					19.5' auger refusal Pieces of rock (phyllite) in nose?			PID = 2.6
	21						EOB @ 19.5' bgs			
	20	0.9	1625 OFF-SB-406-1820	1.0'						
	60/1"									
20	No Recovery	No Penetration	No sample							
	60/0"									
22										
	24									

TYPE OF DRILLING RIG:	Track mounted - CME	Tetra Tech NUS, Inc.
METHOD OF ADVANCING BORING:	Hollow stem auger	
METHOD OF SOIL SAMPLING:	3" split spoon - 2' long - 300 lb. hammer - 18" drop	
METHOD OF ROCK CORING:	N/A	
GROUNDWATER LEVELS:	- 9' bgs	
OTHER OBSERVATIONS:	BORING NO.: SB-406	PAGE: 2 OF 2

BORING LOG FOR: CTO 833 - OFFTA - SITE 09  
 PROJECT NO.: 4152-0552  
 LOGGED BY: J. DANIELI  
 DRILLED BY (Company/Driller): AMERICAN DRILLING / CARL BEIRHOLM  
 GRD. SURFACE ELEVATION: 12.9' (MLW)

TRANSCRIBED BY: MES

ELEVATION FROM:

BORING NO.: SB-407  
 START DATE: 12/01/03  
 COMPLETION DATE: 12/01/03  
 MON. WELL NO.: --  
 CHECKED BY: DH

DEPTH (FEET)	BLOWS PER 6"	SAMP REC. / SAMP LENG.	SAMPLING TIME & SAMPLE NO. (QA/QC STATUS)	DEPTH MAT'L CHG./ WELL PROFL	SOIL DENSITY/ CONSIS. or ROCK HARD.	CLR	MATERIAL CLASSIFICATION	USCS or ROCK BRKN	REMARKS (moisture condition; odors; geological classification; rock weathering; etc.)	FIELD SCREENING DATA METHOD = [FID, (PPM)]	
0	29	1.6' / 2.0'	1020 Dup 1030 OFF-SB-407-0002	Fill	Topsoil Dense	Brown	Topsoil with roots 0-6'		Dry	FID = 0.0	
	42				Loose		SAND and GRAVEL with pieces of brick, fill	SW/GW		PID = 0.0	
	6	1.3' / 2.0'	1040 MS/MSD OFF-SB-407-0204						Dry	FID = 0.0	
	10				Dense	Dark Brown	Sandy and gravelly SILT	ML		PID = 0.0	
	10	1.5' / 2.0'	No sample				Large pieces of concrete 0.5' long, pieces of brick and asphalt		Dry	FID = 0.0	
	12									PID = 0.0	
	16	0.6' / 2.0'	No sample			Light Brown	Pieces of cobble at nose of spoon Sandy SILT – trace gravel	ML	Dry	FID = 0.0	
	17									PID = 0.0	
	13	1.0' / 2.0'	1103 OFF-SB-407-0810						Dry	FID = 0.0	
	16				Loose	White/Pink	Broken up cobble – 0.5' long			PID = 0.0	
8	9	0.9' / 2.0'	No sample			Dark Brown	Silty SAND and GRAVEL	SW/GM			
	13										
	10	1.0' / 2.0'	1103 OFF-SB-407-0810		Loose	Dark Brown					
	16										
	16	0.9' / 2.0'	No sample								
	19				Loose	Brown	Fine to medium SAND, trace silt and gravel	SM	Wet	FID = 0.0	
10	5	0.9' / 2.0'	No sample			Dark Brown	Sandy silt with layers of brown peat and roots	ML		PID = 0.0	
	5										
	11	0.9' / 2.0'	1120 OFF-SB-407-1214		Dense	Olive Gray	Silty SAND with gravel, soupy, saturated with oil	SM	Wet Sheen noted	FID = 29.2	
	17									PID = 19.1	
	20	0.9' / 2.0'	1120 OFF-SB-407-1214		Loose	Olive Gray	Soupy, saturated with oil, SILT with sand and gravel	ML	Wet Sheen noted	FID = 1.1	
	11									PID = 0.1	
12	17	0.9' / 2.0'	No sample		Dense	Olive Gray					
	9										
	13	2.0' / 2.0'	No sample								
	11										
14	7	2.0' / 2.0'	No sample								
	8										

TYPE OF DRILLING RIG:

Track mounted CME

METHOD OF ADVANCING BORING:

Hollow stem auger

METHOD OF SOIL SAMPLING:

3" split spoon – 2' length, 18" drop with 300 lb. hammer

METHOD OF ROCK CORING:

N/A

GROUNDWATER LEVELS:

~ 10' bgs (from top of mound)

OTHER OBSERVATIONS:

BORING NO.: SB-407

PAGE: 1 OF 2



Tetra Tech NUS, Inc.

BORING LOG FOR: CTO 833 - OFFTA - SITE 09  
 PROJECT NO.: 4152-0552  
 LOGGED BY: J. DANIELI  
 DRILLED BY (Company/Driller): AMERICAN DRILLING / CARL BEIRHOLM  
 GRD. SURFACE ELEVATION: 12.9' (MLW)

TRANSCRIBED BY: MES

BORING NO.: SB-407  
 START DATE: 12/01/03  
 COMPLETION DATE: 12/01/03  
 MON. WELL NO.: --  
 ELEVATION FROM: CHECKED BY: DH

DEPTH (FEET)	BLOWS PER 6"	SAMP REC. / SAMP LENG.	SAMPLING TIME & SAMPLE NO. (QA/QC STATUS)	DEPTH MAT'L CHG./ WELL PROFL	SOIL DENSITY/ CONSI. or ROCK HARD.	CLR	MATERIAL CLASSIFICATION	USCS or ROCK BRKN	REMARKS (moisture condition; odors; geological classification; rock weathering; etc.)	FIELD SCREENING DATA METHOD = [FID, (PPM)]
16										
	38									
	28									
18	33	1.0' / 2.0'	1140 (grain size Collected) OFF-SB-407-1618		Loose	Dark Gray	Soupy, broken rock, weathered, phyllite?			Wet - sheen saturated with oil, weathered rock
	20				Dense	Olive Gray	0.5' long - mixture, SILT with sand and gravel - till?	ML		FID = 4.7
	4	0.9' / 2.0'	No sample		Dense	Olive Gray	SILT with sand and gravel - till?	ML	Orange staining Wet	PID = 3.8
	5					Gray	Pieces of weathered rx - orange staining			FID = 6.9
20	5					Gray	Piece of wire-copper SILT with gravel and trace sand			
	6					Gray	Orange staining - rx - phyllite?			
	11	1.4' / 2.0'	1215 Dup							
	5		1220 OFF-SB-407-2022							
22	5									
	9									
	47									
	120'2"	0.7' / 1.5'	No sample							
24										
	120'2"	0.2' / 1.0'	No sample Weathered rx Low recovery			Gray	Soupy			
26							Weathered broken rx - phyllite?	Broken rock		PID = 0.0
							EOB @ 24' 2"			FID = 0.6

TYPE OF DRILLING RIG:	Track mounted rig - CME	Tetra Tech NUS, Inc.
METHOD OF ADVANCING BORING:	Hollow stem auger	
METHOD OF SOIL SAMPLING:	3" split spoon - 2' length, 18" drop with 300 lb. hammer	
METHOD OF ROCK CORING:	N/A	
GROUNDWATER LEVELS:	~ 10' bgs (from top of mound)	
OTHER OBSERVATIONS:		BORING NO.: SB-407
		PAGE: 2 OF 2

BORING LOG FOR: CTO 833 - OFFTA - SITE 09  
 PROJECT NO.: 4152-0552  
 LOGGED BY: J. LAMBERT  
 DRILLED BY (Company/Driller): AMERICAN DRILLING / RODNEY DEAN  
 GRD. SURFACE ELEVATION: 9.4'

TRANSCRIBED BY: MES  
 ELEVATION FROM: NGVD 1929 (MLW)

BORING NO.: SB-410  
 START DATE: 11/20/03  
 COMPLETION DATE: 11/21/03  
 MON. WELL NO.: --  
 CHECKED BY: DH

DEPTH (FEET)	BLOWS PER 6"	SAMP REC. / SAMP LENG.	SAMPLING TIME & SAMPLE NO. (QA/QC STATUS)	DEPTH MAT'L CHG./ WELL PROFL	SOIL DENSITY/ CONSIS. or ROCK HARD.	CLR	MATERIAL CLASSIFICATION	USCS or ROCK BRKN	REMARKS (moisture condition; odors; geological classification; rock weathering; etc.)	FIELD SCREENING DATA METHOD = [FID, (PPM)]
0							Hollow stem auger to 2' - no sample collected		Dry	
2										
10										
20	1.0	2	1540 (11/20/03) OFF-SB-410-0204	Dense	Light Brown		Fine to coarse SAND, trace gravel (angular - rounded)	SW	Dry	PID = 0.0
11							0.0-0.2' = Stained material, similar to above			FID = 1.5
14							0.2-0.4' = Dry friable manmade material - no reaction to acid			
7				Medium Dense	Red Tan				Petroleum odor	
8	0.8	2	No sample				0.4-0.8' = Stained, gravelly SILT, some sand	ML	Moist	PID = 127
10							Similar to above - very strong petroleum odor, free product			FID = 122.5
5				Black						
8				Loose						
2	1.2	4	1600 (11/20/03) OFF-SB-410-0608							
3										
3							Slough material to above, sheen on water in spoon			
2				Black						
2	0	4.2	No sample							
2										
10				Medium Dense			0.0-0.4' = same as above	SW		
3							0.4-1.0' = fine to coarse SAND, trace gravel (angular - subangular)			
6	1.1	4.2	MS/MSD 1615 (11/20/03) OFF-SB-410-1012				1.0-1.1' = coarse SAND	SP		
8										
12										
10				Dark Gray			Fine to coarse SAND and SILT, trace fine gravel	SM	Very slight odor	
9										
13	1.7	4.2	No sample							
19										
18										
5										
10	1.1	4.2	0725 (11/21/03) OFF-SB-410-1416							
11										
12		2.0					Fine silty SAND, trace coarse sand, trace fine gravel (rounded)			

TYPE OF DRILLING RIG:	CME - 75	Tetra Tech NUS, Inc.
METHOD OF ADVANCING BORING:	Hollow stem auger 4.25"	
METHOD OF SOIL SAMPLING:	3" split spoon driven with 300 lb. hammer dropped 18"	
METHOD OF ROCK CORING:	N/A	
GROUNDWATER LEVELS:		
OTHER OBSERVATIONS:		BORING NO.: SB-410
		PAGE: 1 OF 2

BORING LOG FOR: CTO 833 - OFFTA - SITE 09  
 PROJECT NO.: 4152-0552  
 LOGGED BY: J. LAMBERT  
 DRILLED BY (Company/Driller): AMERICAN DRILLING / RODNEY DEAN  
 GRD. SURFACE ELEVATION: 9.4'

TRANSCRIBED BY: MES  
 ELEVATION FROM: NGVD 1929 (MLW)

BORING NO.: SB-410  
 START DATE: 11/20/03  
 COMPLETION DATE: 11/21/03  
 MON. WELL NO.: --  
 CHECKED BY: DH

DEPTH (FEET)	BLOWS PER 6"	SAMP REC. / SAMP LENG.	SAMPLING TIME & SAMPLE NO. (QA/QC STATUS)	DEPTH MAT'L CHG/ WELL PROF'L	SOIL DENSITY/ CONSIS. or ROCK HARD.	CLR	MATERIAL CLASSIFICATION	USCS or ROCK BRKN	REMARKS (moisture condition; odors; geological classification; rock weathering; etc.)	FIELD SCREENING DATA METHOD = [FID, (PPM)]
16	5 5 8 8 5 12 17 31	1.2 / 2 1.2 / 2	No sample 0750 OFF-SB-410-1820	20' EOB	Medium Dense Dark Gray		Silty fine SAND, trace coarse sand, trace fine gravel (rounded)	SM	Wet	PID = 4.5
18							Similar to above			FID = 4.0
20						↓		↓		PID = 0.0
						↓				FID = 3.2

TYPE OF DRILLING RIG:	CME 75	Tetra Tech NUS, Inc.
METHOD OF ADVANCING BORING:	Hollow stem auger 4.25" ID	
METHOD OF SOIL SAMPLING:	3" split spoon driven with 300 lb hammer dropped 18"	
METHOD OF ROCK CORING:	N/A	
GROUNDWATER LEVELS:		
OTHER OBSERVATIONS:		
	BORING NO.: SB-410	PAGE: 2 OF 2

BORING LOG FOR: CTO 833 - OFFTA - SITE 09  
 PROJECT NO.: 4152-0552  
 LOGGED BY: J. DANIELI  
 DRILLED BY (Company/Driller): AMERICAN DRILLING / CARL BEIRHOLM  
 GRD. SURFACE ELEVATION: 31.0'

TRANSCRIBED BY: MES  
 ELEVATION FROM: NGVD 1929 (MLW)

BORING NO.: SB-411  
 START DATE: 11/24/03  
 COMPLETION DATE: 11/25/03  
 MON. WELL NO.: --  
 CHECKED BY: DH

DEPTH (FEET)	BLOWS PER 6"	SAMP REC. / SAMP LENG.	SAMPLING TIME & SAMPLE NO. (QA/QC STATUS)	DEPTH MAT'L CHG./ WELL PROF'L	SOIL DENSITY/ CONSIS. or ROCK HARD.	CLR	MATERIAL CLASSIFICATION	USCS or ROCK BRKN	REMARKS (moisture condition; odors; geological classification; rock weathering; etc.)	FIELD SCREENING DATA METHOD = [FID, (PPM)]
0										
			No sample							
			No split spoon auger to 2' bgs							
2	7	1.4	1440 OFF-SB-411-0204	2.0'	Brown		0-0.6' = Topsoil with grass and roots 0.6-2.0' = SAND and GRAVEL	GW/ SW	2-4' used 140 lb Hammer Dry	FID = 0.0
	9				Brown		- Fill -			
	8				Dark Brown		SAND and GRAVEL - some silt Pieces of asphalt	GW/ SW	Dry	FID = 0.0
4	12	1.5	No sample	2.0'			- Fill -			
	10				Dense	Gray	Silty sand with gravel Pieces of brick	SM	Moist	FID = 72.8
	16						- Fill -			
	19									
6	35	0.5	1520 OFF-SB-411-0608	1.0'						
	18									
	130/5"									
8	8	0.4	No sample	2.0'			Large piece of gravel 0.2' diameter at base of split spoon		Moist	FID = 94.1
	12						- Fill -			
	22				Dense	Gray	SAND and GRAVEL with silt	GW/ SW	Moist	FID = 0.0
10	45	1.1	1535 OFF-SB-411-1012	2.0'			0.2- Piece of gravel - boulder? Concrete? 11.5-11.7 - Fill			
	30						- Fill -			
	15				Dense	Gray/ Black	Silty SAND and GRAVEL - pieces of brick, pieces of asphalt	GW/ SW		FID = 574
	10									
12	9	1.4	No sample	2.0'			13.9-14.1 - Piece of asphalt, fill			
	13						- Fill -			
	11				Dense	Gray/ Black				
	11									
14	14	1.3		2.0'	Dense	Gray/ Black	Sandy SILT with pieces of asphalt, piece of green plate, rock phyllite? Compact, fill	ML	Moist	FID = 201
	12									
	11									
16	10	1.00	1600 OFF-SB-411-1416	2.0'						FID = 0.0

TYPE OF DRILLING RIG: Track mounted CME  
 METHOD OF ADVANCING BORING: Hollow stem auger - 140 lb hammer  
 METHOD OF SOIL SAMPLING: 3" split spoon S.S. - 2' long  
 METHOD OF ROCK CORING: N/A  
 GROUNDWATER LEVELS: Not clear  
 OTHER OBSERVATIONS: Use 140 lb. hammer w/ 30" stroke - missing pin for 300 lb hammer, BZ = 0.0 ppm, in hole at ~ 16' stem from hole  
 Reading 1500 ppm - down to 0.0 ppm

Tetra Tech NUS, Inc.  
  
 BORING NO.: SB-411  
 PAGE: 1 OF 2

BORING LOG FOR: CTO 833 - OFFTA - SITE 09  
 PROJECT NO.: 4152-0552  
 LOGGED BY: J. DANIELI  
 DRILLED BY (Company/Driller): AMERICAN DRILLING / CARL BEIRHOLM  
 GRD. SURFACE ELEVATION: 31.0'

BORING NO.: SB-411  
 START DATE: 11/24/03  
 COMPLETION DATE: 11/25/03  
 MON. WELL NO.: --  
 ELEVATION FROM: NGVD 1929 (MLW)  
 CHECKED BY: DH

TRANSCRIBED BY: MES

DEPTH (FEET)	BLOWS PER 6"	SAMP REC. / SAMP LENG.	SAMPLING TIME & SAMPLE NO. (QA/QC STATUS)	DEPTH MAT'L CHG/ WELL PROF'L	SOIL DENSITY/ CONSIS. or ROCK HARD.	CLR	MATERIAL CLASSIFICATION	USCS or ROCK BRKN	REMARKS (moisture condition; odors; geological classification; rock weathering; etc.)	FIELD SCREENING DATA METHOD = [FID, (PPM)]
16'	130 FOR 6"	0.2 0.5'	NO SAMPLE	Natural Materials	Dense	Gray	Sandy SILT, piece of boulder at base of split spoon	ML	Moist	FID = 489 PPM
18'	130 FOR 4"	0.33'	NO RECOVERY NO SAMPLE				Fill			--
20'	39	1.1	1650				No recovery (18-20')			--
22'	42 39 130 1/4"	1.8'	OFF-SB-411-2022		Fill	Gray	Sandy SILT with asphalt fill	ML	Moist	FID = 0.0 PPM
24'	130/5"	0.4	0735 OFF-SB-411-2224		Brown		21.5 - SAND and GRAVEL (rounded)	GW/ SP	Dry	--
26'	27	0.4'			Loose		Fine to medium SAND with gravel, pieces of boulder/cobble (rounded edges)	SP	Dry	FID = 0.0 PPM
28'	130/4"	0.3	NO SAMPLE		Olive Gray				Dry	FID = 0.0 PPM
		0.3'			Loose			SP		
		0.1	0830 OFF-SB-411-2628		Dense/ Compact	Dark Gray	Silty SAND with gravel (rounded)	SM		
	130/2"	0.16'			Loose	Light Gray	Fine to medium SAND with gravel - rx? Concrete? Pulverized rx?			
		0.1	NO SAMPLE						Auger refusal @ 27.5' - send split spoon down	
		0.16'								
									Only drives down and then 2" and 0.1' recovered	

TYPE OF DRILLING RIG:	TRACK MOUNTED - CME
METHOD OF ADVANCING BORING:	HOLLOW STEM AUGER - 140 LB. HAMMER
METHOD OF SOIL SAMPLING:	3" SPLIT SPOON, 2' LONG
METHOD OF ROCK CORING:	NA
GROUNDWATER LEVELS:	NOT CLEAR
OTHER OBSERVATIONS:	USE 140 LB. HAMMER W/ 30" STROKE - MISSING PIN FOR 300 LB. HAMMER

BORING NO.: SB-411

Tetra Tech NUS, Inc.



PAGE: 2 OF 2

BORING LOG FOR:

CTO 833 – OFFTA – SITE 09

PROJECT NO.:

4152-0552

LOGGED BY:

J. DANIELI

DRILLED BY (Company/Driller):

AMERICAN DRILLING / CARL BEIRHOLM

GRD. SURFACE ELEVATION:

24.5'

TRANSCRIBED BY: MES

BORING NO.:

SB-412

START DATE:

11/25/03

COMPLETION DATE:

11/25/03

MON. WELL NO.:

—

CHECKED BY:

DH

ELEVATION FROM: NGVD 1929 (MLW)

DEPTH (FEET)	BLOWS PER 6"	SAMP REC. / SAMP LENG.	SAMPLING TIME & SAMPLE NO. (QA/QC STATUS)	DEPTH MAT'L CHG./ WELL PROFL	SOIL DENSITY/ CONSI. or ROCK HARD.	CLR	MATERIAL CLASSIFICATION	USCS or ROCK BRKN	REMARKS (moisture condition; odors; geological classification; rock weathering; etc.)	FIELD SCREENING DATA METHOD = (FID, (PPM))
0										
2			No sample No split spoon Auger to 2' bgs							
10										
56										
65										
4	1050 OFF-SB-412-0204 1055 Dup	0.55 2.0		Topsoll	Dense	Brown	Silty SAND with roots Topsoll	SM	Moist	FID = 25 PID = 123
12										
31										
36										
6	1120 OFF-SB-412-0608	1.5 2.0	No sample	Fill	Loose	Dark Brown	Fill, SAND and GRAVEL with boulder piece (0.5' in length) Pieces of red brick	SW/ GW	Dry	FID = 7.2 PID = 0.0
48										
31										
130/5.5"										
8										
13										
13										
16										
10	1145 OFF-SB-412-1012	1.3 2.0	No sample	Fill	Loose	Olive Gray	SAND with gravel - fill - pieces of brick	SW	Dry	FID = 8.3 PID = 0.0
6										
5										
7										
7										
12										
8										
4										
7										
12										
14										
37										
30										
130/3"										
16	1230 OFF-SB-412-1416	0.2 0.25	Natural Material		Loose	Olive Gray	Fine to medium SAND with gravel, trace silt, pieces of boulder - dark gray platy rock	SP	Dry	FID = 137.0 PID = 50.3

TYPE OF DRILLING RIG:

Track rig CME

METHOD OF ADVANCING BORING:

Hollow stem auger

METHOD OF SOIL SAMPLING:

3" split spoon – 2' in length – 300 lb. hammer – 18" drop

METHOD OF ROCK CORING:

N/A

GROUNDWATER LEVELS:

Not clear

OTHER OBSERVATIONS:

Tetra Tech NUS, Inc.



BORING NO.: SB-412

PAGE: 1 OF 2

BORING LOG FOR: CTO 833 – OFFTA – SITE 09  
 PROJECT NO.: 4152-0552  
 LOGGED BY: J. DANIELI  
 DRILLED BY (Company/Driller): AMERICAN DRILLING / CARL BEIRHOLM  
 GRD. SURFACE ELEVATION: 24.5'

BORING NO.: SB-412  
 START DATE: 11/25/03  
 COMPLETION DATE: 11/25/03  
 MON. WELL NO.: --  
 ELEVATION FROM: NGVD 1929 (MLW)  
 CHECKED BY: DH

DEPTH (FEET)	BLOWS PER 6"	SAMP REC. / SAMP LENG.	SAMPLING TIME & SAMPLE NO. (QA/QC STATUS)	DEPTH MAT'L CHG./ WELL PROF'L	SOIL DENSITY/ CONSIS. or ROCK HARD.	CLR	MATERIAL CLASSIFICATION	USCS or ROCK BRKN	REMARKS (moisture condition; odors; geological classification; rock weathering; etc.)	FIELD SCREENING DATA METHOD = [FID, (PPM)]
16	33 133/3"	0.2	No sample	Loose	Gray	Pieces of boulder - rounded Traces of fine SAND	SW	Dry	PID = 63 FID = 132.6	
		0.5								
18	130/4"	No Recovery	No sample			No recovery				
		0.30								
20	130/3"	No Recovery	No sample			No recovery				
		0.25								
22						Auger refused at 20' bgs, stop augering - can't go any further - may come back with drive and wash				
						EOB @ 20.25' BGS				

TYPE OF DRILLING RIG:	Track mounted rig – CME	Tetra Tech NUS, Inc.
METHOD OF ADVANCING BORING:	Hollow stem auger	
METHOD OF SOIL SAMPLING:	3" split spoon, 2' long, 300 lb hammer, 18" drop	
METHOD OF ROCK CORING:	N/A	
GROUNDWATER LEVELS:	Not clear	
OTHER OBSERVATIONS:		BORING NO.: SB-412
		PAGE: 2 OF 2



BORING LOG FOR:  
PROJECT NO.:  
LOGGED BY:  
DRILLED BY (Company/Driller):  
GRD. SURFACE ELEVATION:

CTO 833 - OFFTA - SITE 09  
4152-0552  
J. DANIELI  
AMERICAN DRILLING / CARL BEIRHOLM  
10.6'

TRANSCRIBED BY: MES

ELEVATION FROM: NGVD 1929 (MLW)

BORING NO.: SB-413B  
START DATE: 12/04/03  
COMPLETION DATE: 12/04/03  
MON. WELL NO.: --  
CHECKED BY: DH

DEPTH (FEET)	BLOWS PER 6"	SAMP REC. / SAMP LENG.	SAMPLING TIME & SAMPLE NO. (QA/QC STATUS)	DEPTH MAT'L CHG./ WELL PROFL	SOIL DENSITY/ CONSIS. or ROCK HARD.	CLR	MATERIAL CLASSIFICATION	USCS or ROCK BRKN	REMARKS (moisture condition; odors; geological classification; rock weathering; etc.)	FIELD SCREENING DATA METHOD = [FID, (PPM)]
0			No sample				Auger to 4' bgs, no sample			
2										
4										
	70/1"	0.1	No sample							FID = 7.1
6	70/0"	0.1'	No Recovery	No sample	Dense	Brown	In nose - SILT with sand (0-0.1')	ML		PID = 0.0
			No Penetration				Auger refusal 5.5' bgs No recovery - pieces of broken rock			
8							Switch over to drive and wash, will roller bit in 3' the take spoon			
8.5							Roller bit down 3' for total depth of 8.5' bgs Send spoon down → roller bit steady pieces of rx in wash water			
9.5	65/1"	0.1	No sample		Gray		Pulverized rx			
							EOB @ 8.5' BGS			

TYPE OF DRILLING RIG:	Track mounted CME	Tetra Tech NUS, Inc.
METHOD OF ADVANCING BORING:	Hollow stem auger and drive and wash	
METHOD OF SOIL SAMPLING:	3" split spoon -300 lb. hammer with 18" drop	
METHOD OF ROCK CORING:	N/A	
GROUNDWATER LEVELS:	Not evident	
OTHER OBSERVATIONS:		BORING NO.: SB-413B
		PAGE: 1 OF 1

BORING LOG FOR: CTO 833 – OFFTA – SITE 09  
 PROJECT NO.: 4152-0552  
 LOGGED BY: J. LAMBERT  
 DRILLED BY (Company/Driller): AMERICAN DRILLING / RODNEY DEAN  
 GRD. SURFACE ELEVATION: 13.3'

TRANSCRIBED BY: MES

ELEVATION FROM: NGVD 1929

BORING NO.: SB-415  
 START DATE: 11/18/03  
 COMPLETION DATE: 11/19/03  
 MON. WELL NO.: --  
 CHECKED BY: DH

DEPTH (FEET)	BLOWS PER 6"	SAMP REC. / SAMP LENG.	SAMPLING TIME & SAMPLE NO. (QA/QC STATUS)	DEPTH MAT'L CHG./ WELL PROFL	SOIL DENSITY/ CONSIS. or ROCK HARD.	CLR	MATERIAL CLASSIFICATION	USCS or ROCK BRKN	REMARKS (moisture condition; odors; geological classification; rock weathering; etc.)	FIELD SCREENING DATA METHOD = [FID, (PPM)]
0	2		1530 (11/18) OFF-SB-415-0002		Medium Dense	Dark Brown	0-0.7' organic sandy SILT (fine sand)	OL	Asphalt, brick, concrete fragments in sample	PID = 0.0
	5	1.5 / 2.0'	1535 (11/18) OFF-SB-415-DUP03	Fill			0.7-1.5' - silty fine to coarse SAND	SM		
2	7						No recovery - will retrieve sample from 2 <sup>nd</sup> borehole			
	14									
	4									
	6									
	8									
4	15									
	11									
	13									
	22									
6	20									
	14									
	15									
	10									
8	15									
	19									
	13									
	8									
10	11									
	14									
	15									
	10									
8	15									
	19									
	13									
	8									
10	11									
	14									
	15									
	10									
	20									
	20									
12	120/4"		1600 (11/18) OFF-SB-415-1012 Grain size				Cobble at 10' (likely reason for 8-10' poor recovery) fine to coarse SAND and GRAVEL		Wet	PID = 0.0
2										
	10									
	26									
	36									
4	20	1.0 / 2.0'	0825 (11/19) OFF-SB-415-0204 *	EOB	Very Dense	Light Gray	0-0.5' concrete fragments	--	Concrete layer not sampled (only sampled soil)	FID = 0.0
					Dense	Dark Brown	0.5-1.0' - fine to coarse SAND, some gravel, trace silt	SW		

TYPE OF DRILLING RIG:	CME 75	Tetra Tech NUS, Inc.
METHOD OF ADVANCING BORING:	Hollow stem auger	
METHOD OF SOIL SAMPLING:	3" split spoon driven with 300 lb hammer dropped 18"	
METHOD OF ROCK CORING:	N/A	
GROUNDWATER LEVELS:		
OTHER OBSERVATIONS:	* Second boring advanced for 2-4' recovery and sample only	BORING NO.: SB-415
		PAGE: 1 OF 1



BORING LOG FOR:  
PROJECT NO.:  
LOGGED BY:  
DRILLED BY (Company/Driller):  
GRD. SURFACE ELEVATION:

CTO 833 - OFFTA - SITE 09

4152-0552

J. LAMBERT

AMERICAN DRILLING / RODNEY DEAN

11.5'

TRANSCRIBED BY: MES

BORING NO.: SB-416  
START DATE: 11/19/03  
COMPLETION DATE: 11/19/03  
MON. WELL NO.: -  
CHECKED BY: DH

ELEVATION FROM: NGVD 1929 (MLW)

DEPTH (FEET)	BLOWS PER 6"	SAMP REC. / SAMP LENG.	SAMPLING TIME & SAMPLE NO. (QA/QC STATUS)	DEPTH MAT'L CHG./ WELL PROF'L	SOIL DENSITY/ CONSIS. or ROCK HARD.	CLR	MATERIAL CLASSIFICATION	USCS or ROCK BRKN	REMARKS (moisture condition; odors; geological classification; rock weathering; etc.)	FIELD SCREENING DATA METHOD = [FID, (PPM)]
0	5		MS/MSD		Medium Dense	Dark Brown	0.0-0.4' = Grass and roots 0.4-1.8' = silty fine to coarse sand, some coarse rounded gravel	SM	PID/FID = 0.0 on sample Damp	PID = 0.6
	10	1.8 / 2.0'	0850 OFF-SB-416-0002	FILL						
2	15									
	15									
4	6	1.1 / 2.0'	No sample		Very Dense	Brown Red	0.0-0.2 = silty fine to coarse sand, some gravel 0.2-0.6 = brick fragments	--	Damp	PID = 0.9
	9									
	70									
6	34									
	7	0.8 / 2.0'	0910 OFF-SB-416-0406		White Brown		0.6-0.8 = concrete 0.8-1.1 = silty fine sand, trace gravel	--		
	11									
	8									
8	6	1.2 / 2.0'	No sample		Medium Dense	Light Brown	Fine to coarse sand, some gravel (angular to subrounded)	SW	Damp Small pieces of slag and concrete	PID = 0.0
	6									
	8									
	9									
8	9	1.2 / 2.0'	No sample				0.0-0.7 = sandy silt (fine to medium sand)	ML	0.3' - non-native gravel	PID = 0.0
	10									
	14	1.1 / 2.0'	0925 OFF-SB-416-0810			Black	0.7-0.9' = Possible burn zone (slag and charcoal) 0.9-1.2' = Silty fine to coarse sand, some gravel	--		
	11									
10	8							SM		
	4	1.1 / 2.0'	No sample							
	9									
	17									
12	14	1.5 / 2.0'	No sample							
	14									
	40	1.7 / 2.0'	0940 OFF-SB-416-1214							
14	41									
	42									
	6	1.2 / 2.0'	No sample		Very Dense		Gravelly silt, some fine to coarse sand, gravel is angular to subrounded	ML	PID = 1.0 ppm at 10.5' in the sample	PID = 0.8
	12									
	27									
16	32						0.0-0.8' = gravelly, sandy silt (sand - medium to coarse sand, trace fine sand) - very dense	SP		
							*			
						Red				

TYPE OF DRILLING RIG:

CME 75

METHOD OF ADVANCING BORING:

Hollow stem auger

METHOD OF SOIL SAMPLING:

3" split spoon driven with a 300 lb. hammer dropped 18"

METHOD OF ROCK CORING:

N/A

GROUNDWATER LEVELS:

\* - 0.8-1.2' = similar to above, less silt

BORING NO.: SB-416

Tetra Tech NUS, Inc.



PAGE: 1 OF 2

BORING LOG FOR:  
PROJECT NO.:  
LOGGED BY:  
DRILLED BY (Company/Driller):  
GRD. SURFACE ELEVATION:

CTO 833 - OFFTA - SITE 09  
4152-0552  
J. LAMBERT  
AMERICAN DRILLING / RODNEY DEAN  
11.5'

TRANSCRIBED BY: MES  
ELEVATION FROM: NGVD 1929 (MLW)

BORING NO.: SB-416  
START DATE: 11/19/03  
COMPLETION: DATE: 11/19/03  
MON. WELL NO.: --  
CHECKED BY: DH

DEPTH (FEET)	BLOWS PER 6"	SAMP REC. / SAMP. LENG.	SAMPLING TIME & SAMPLE NO. (QA/QC STATUS)	DEPTH MAT'L CHG./ WELL PROF'L	SOIL DENSITY/ CONSIS. or ROCK HARD.	CLR	MATERIAL CLASSIFICATION	USCS or ROCK BRKN	REMARKS (moisture condition; odors; geological classification; rock weathering; etc.)	FIELD SCREENING DATA METHOD = [FID, (PPM)]
16	37	1.3	1020 OFF-SB-416-1618	Till	Very Dense	Light Brown	0-0.6' - light brown, gravelly silt, some medium to coarse sand	ML		PID = 1.5
	120	2.0'			Red Brown		0.6-1.3' - gravelly sandy silt, possible till (gravel = fine to coarse angular to subangular)			FID = 3.0
18	120/0"						Partially consolidated gravelly silt, some medium to coarse sand (III)			PID = 0.6
	45	1.0	1042 OFF-SB-416-1820							FID = 11.4
	45	1.3'								
20	120/3"									
	120/2"	0.0	No sample				No recovery - cobble in the nose of the spoon - broken face			
22		2.0'		EOB Spoon Refusal						

TYPE OF DRILLING RIG:

CME 75

METHOD OF ADVANCING BORING:

Hollow stem auger

METHOD OF SOIL SAMPLING:

3" split spoon driven with 300 lb. hammer, dropped 18"

METHOD OF ROCK CORING:

N/A

GROUNDWATER LEVELS:

OTHER OBSERVATIONS:

Tetra Tech NUS, Inc.



BORING NO.: SB-416

PAGE: 2 OF 2

BORING LOG FOR: CTO 833 - OFFTA - SITE 09  
 PROJECT NO.: 4152-0552  
 LOGGED BY: J. LAMBERT  
 DRILLED BY (Company/Driller): AMERICAN DRILLING / RODNEY DEAN  
 GRD. SURFACE ELEVATION: 8.5'

TRANSCRIBED BY: MES  
 ELEVATION FROM: NGVD 1929 (MLW)

BORING NO.: SB-417  
 START DATE: 11/19/03  
 COMPLETION DATE: 11/19/03  
 MON. WELL NO.: --  
 CHECKED BY: DH

DEPTH (FEET)	BLOWS PER 6"	SAMP REC. / SAMP LENG.	SAMPLING TIME & SAMPLE NO. (QA/QC STATUS)	DEPTH MAT'L CHG./ WELL PROFL	SOIL DENSITY/ CONSIS. or ROCK HARD.	CLR	MATERIAL CLASSIFICATION	USCS or ROCK BRKN	REMARKS (moisture condition; odors; geological classification; rock weathering; etc.)	FIELD SCREENING DATA METHOD = [FID, (PPM)]
0										
							Auger to 2' - no sample collected from 0-2'			
2										
	8									
	11									
	0.0	/ 2.0'	No sample		Medium Dense		No recovery			
	7									
4	9									
	8			1340	Loose	Brown	Silty sand (fine to coarse sand)	SM	Moist Wet - bottom 0.5'	PID = 122
	4			OFF-SB-417-0406			Oxidized above 0.5', petroleum staining and odor			FID = 10.9
	4				Medium Dense	Black	Oil stained fine to coarse SAND 0.4' = white gray material surrounding a hard white center -	SW	PID = 10.3 ppm in sample	PID = 7.0
6	5			1400						
	7			OFF-SB-417-0608			Possibly grout, inorganic or tile, At 0.6' = Off-white material, possible grout			
	6			1410						
	7			OFF-SB-DUP04			0.0-0.5' - oil stained material, shell in spoon			
8	5									
	8				Black					
	8		No sample				0.5-0.9' - fine sand, some olive green mottling	SP		
	8									
10	8						Similar to above, fine sand		Wet	PID = 1.0
	8									
	7			1415						
	7			OFF-SB-417-1012			0.0-0.4' = fine sand, trace silt in lower portions			
12	8									
	12				Dense		0.0-0.8' = dropstone with varves bent around it			
	11		No sample							
	23									
14	21									
	18									
	19									
	1.2	/ 2.0'	1430					SM		
	18			OFF-SB-417-1416			Silty fine sand, some gravel, pockets of heavily oxidized (dark red) material			
16	20									

TYPE OF DRILLING RIG: CME 75 - track mounted  
 METHOD OF ADVANCING BORING: Hollow stem auger  
 METHOD OF SOIL SAMPLING: 3" split spoon driven with 300 lb hammer dropped 18"  
 METHOD OF ROCK CORING: N/A  
 GROUNDWATER LEVELS:  
 OTHER OBSERVATIONS:

BORING NO.: SB-417

Tetra Tech NUS, Inc.



PAGE: 1 OF 2

BORING LOG FOR:  
PROJECT NO.:  
LOGGED BY:  
DRILLED BY (Company/Driller):  
GRD. SURFACE ELEVATION:

CTO 833 – OFFTA – SITE 09  
4152-0552  
J. LAMBERT  
AMERICAN DRILLING / RODNEY DEAN  
8.5'

BORING NO.:  
START DATE:  
COMPLETION DATE:  
MON. WELL NO.:  
ELEVATION FROM: NGVD 1929 (MLW)

SB-417  
11/19/03  
11/19/03  
--  
CHECKED BY:  
DH

DEPTH (FEET)	BLOWS PER 6"	SAMP REC. / SAMP LENG.	SAMPLING TIME & SAMPLE NO. (QA/QC STATUS)	DEPTH MAT'L CHG./ WELL PROF'L	SOIL DENSITY/ CONSIS. or ROCK HARD.	CLR	MATERIAL CLASSIFICATION	USCS or ROCK BRKN	REMARKS (moisture condition; odors; geological classification; rock weathering; etc.)	FIELD SCREENING DATA METHOD = (FID, (PPM))
16				1.3 / 2.0' No sample	Dark Gray	Till	Gravelly silt, some sand, extremely dense Possibly weathered conglomerate or till, layers and nodules of heavily oxidized material, mottled (light brown, gray and red) 0.0-0.4' = similar to above			PID = 1.0
	13									
	19									
18	22			1.0 / 2.0' 1455 OFF-SB-417-1820	Light Brown		0.4-1.0' = compacted gravelly sand, some silt - possible conglomerate			FID = 0.0
	22									
	28									
	78									PID = 2.2
20	72									FID = 0.0
	82									
				EOB						

TYPE OF DRILLING RIG:	CME 75	Tetra Tech NUS, Inc.
METHOD OF ADVANCING BORING:	Hollow stem auger	
METHOD OF SOIL SAMPLING:	3" split spoon driven with a 300 lb. hammer dropped 18"	
METHOD OF ROCK CORING:	N/A	
GROUNDWATER LEVELS:		
OTHER OBSERVATIONS:		BORING NO.: SB-417
		PAGE: 2 OF 2

BORING LOG FOR:  
PROJECT NO.: 4152-0552  
LOGGED BY: J. LAMBERT  
DRILLED BY (Company/Driller): AMERICAN DRILLING / CARL BEIRHOLM  
GRD. SURFACE ELEVATION: 10.0'

## CTO 833 - OFFTA - SITE 09

TRANSCRIBED BY: MES

ELEVATION FROM: NGVD 1929 (MLW)

BORING NO.: SB-418  
START DATE: 12/03/03  
COMPLETION DATE: 12/03/03  
MON. WELL NO.: --  
CHECKED BY: DH

DEPTH (FEET)	BLOWS PER 6"	SAMP REC. / SAMP LENG.	SAMPLING TIME & SAMPLE NO. (QA/QC STATUS)	DEPTH MAT'L CHG./ WELL PROFL	SOIL DENSITY/ CONSIS. or ROCK HARD.	CLR	MATERIAL CLASSIFICATION	USCS or ROCK BRKN	REMARKS (moisture condition; odors; geological classification; rock weathering; etc.)	FIELD SCREENING DATA METHOD = [FID, (PPM)]
0	7			Topsoil	Loose	Brown	0.0-0.5 = Fine to medium SAND with silt - topsoil		Dry	FID = 2.1
	12									
2	18									
	17									
	12									
	24									
4	30									
	46									
	5									
	5									
6	6									
	3									
	5									
	7									
8	6									
	6									
	10									
	10									
10	12									
	13									
	5									
	5									
12	7									
	9									
	7									
14	9									
	8									
	7									
	9									
14	8									
	7									
	12									
16	12									
	15									

TYPE OF DRILLING RIG:	Track mounted - CME	Tetra Tech NUS, Inc.
METHOD OF ADVANCING BORING:	Hollow stem auger	
METHOD OF SOIL SAMPLING:	3" split spoon - 2' long - 300 lb. hammer, 18" drop	
METHOD OF ROCK CORING:	N/A	
GROUNDWATER LEVELS:	~ OR = 8' bgs	
OTHER OBSERVATIONS:		BORING NO.: SB-418 PAGE: 1 OF 2

BORING LOG FOR:	CTO 833 – OFFTA – SITE 09
PROJECT NO.:	4152-0552
LOGGED BY:	J. LAMBERT
DRILLED BY (Company/Driller):	AMERICAN DRILLING / CARL BEIRHOLM
GRD. SURFACE ELEVATION:	10.0'

TRANSCRIBED BY: MES

ELEVATION FROM: NGVD 1929 (MLW)

BORING NO.:	SB-418
START DATE:	12/03/03
COMPLETION: DATE:	12/03/03
MON. WELL NO.:	--
CHECKED BY:	DH

TYPE OF DRILLING RIG:	Track mounted CME	Tetra Tech NUS, Inc.
METHOD OF ADVANCING BORING:	Hollow stem auger	
METHOD OF SOIL SAMPLING:	3" split spoon - 2' length - 300 lb. hammer with 18" drop	
METHOD OF ROCK CORING:	N/A	
GROUNDWATER LEVELS:	- OR = 8' bgs	
OTHER OBSERVATIONS:		BORING NO.: SB-418
		PAGE: 2 OF 2

BORING LOG FOR: CTO 833 – OFFTA – SITE 09  
 PROJECT NO.: 4152-0552  
 LOGGED BY: J. LAMBERT  
 DRILLED BY (Company/Driller): AMERICAN DRILLING / RODNEY DEAN  
 GRD. SURFACE ELEVATION: 8.4'

TRANSCRIBED BY: MES  
 ELEVATION FROM: NGVD 1929 (MLW)

BORING NO.: SB-419  
 START DATE: 11/18/03  
 COMPLETION DATE: 11/18/03  
 MON. WELL NO.: --  
 CHECKED BY: DH

DEPTH (FEET)	BLOWS PER 6"	SAMP REC. / SAMP LENG.	SAMPLING TIME & SAMPLE NO. (QA/QC STATUS)	DEPTH MAT'L CHG./ WELL PROF'L	SOIL DENSITY/ CONSIS. or ROCK HARD.	CLR	MATERIAL CLASSIFICATION	USCS or ROCK BRKN	REMARKS (moisture condition; odors; geological classification; rock weathering; etc.)	FIELD SCREENING DATA METHOD = [FID, (PPM)]
0				FILL			Auger to 2' – no samples taken from 0-2' BGS			
2										
7										
10	2.0' / 2.0'	0745 OFF-SB-419-0204	No sample	Medium Dense	Gray/ Orange		0-1.0' = Oixidized silty fine to coarse SAND, some gravel	SW	Moist Petroleum odor Brick fragments	PID = 59.9
17										
15							1.0'-2.0' – Similar to above, slightly stained	SW		FID = 44.6
4							Silty fine to coarse SAND	SM	Moist	
16	1.8' / 2.0'									PID = 277
18							PID = 128 ppm in sample			FID = 289
6	1.5' / 2.0'	0800 OFF-SB-419-0608		Very Dense			Crumbly silty fine to coarse SAND in sample PID = 310 ppm in sample	↓	Petroleum odor	PID = 294
26										FID = 174
46										
55										
85										
10	1.2' / 2.0'	0810 OFF-SB-DUP01	No sample				0-0.8' = Crumbly fine to coares SAND, some gravel	SM	Wet Sheen on water in spoon	PID = 23.3
40										FID = 34.9
25							0.8-1.2' = Silty fine to coarse SAND	↓		
20										
10	1.0' / 2.0'	0820 OFF-SB-419-1012		Red- Gray			0-0.6' = Silty fine to coarse SAND, some clay, trace gravel		Spoon refusal at 11.5' - light petroleum odor	PID = 27.7
35							0.6-1.0' = Saprolitic rock (more dense)			FID = 20.9
12	120/5"			EOB			Saprolitic rock - possible conglomerate with oxidized coarse sand sized pieces		Petroleum odor	
120/4"				12.5' Spoon Refusal						PID = 52.6
14										FID = 40.0

TYPE OF DRILLING RIG:	CME 75	Tetra Tech NUS, Inc.
METHOD OF ADVANCING BORING:	4.25" ID hollow stem auger	
METHOD OF SOIL SAMPLING:	3" split spoon driven with 300 lb. hammer and dropped 18"	
METHOD OF ROCK CORING:	N/A	
GROUNDWATER LEVELs:		
OTHER OBSERVATIONS:	Augers started pulling up water and saturated soils @ 10'. Only manmade material to 4' - the rest is most likely native	BORING NO.: SB-419 PAGE: 1 OF 1

PROJECT NO.:  
LOGGED BY:  
DRILLED BY (Company/Driller):  
GRD. SURFACE ELEVATION:

CTO 833 - OFFTA - SITE 09  
4152-0002  
J. DANIELI  
AMERICAN DRILLING / CARL AND JIMMY BEIRHOLM  
11.8'

TRANSCRIBED BY: MES  
ELEVATION FROM: NGVD 1929 (MLW)

BORING NO.: SB-422  
START DATE: 12/03/03  
COMPLETION DATE: 12/03/03  
MON. WELL NO.:  
CHECKED BY: DH

DEPTH (FEET)	BLOWS PER 6"	SAMP REC. / SAMP LENG.	SAMPLING TIME & SAMPLE NO. (QA/QC STATUS)	DEPTH MAT'L CHG./ WELL PROFL	SOIL DENSITY/ CONSIS. or ROCK HARD.	CLR	MATERIAL CLASSIFICATION	USCS or ROCK BRKN	REMARKS (moisture condition; odors; geological classification; rock weathering; etc.)	FIE SCREE DA1 METHK [FID, (P
0							Auger to 2' bgs			
2							No sample			
4	4	2.0' / 2.0'	0745 OFF-SB-422-0204	Loose	Brown		Fine to coarse SAND with gravel, some orange staining	SW	Dry	PID = 0.0
4	4									FID = 0.0
4	9									
6	9									
6	11									
6	9									
8	7	1.4' / 2.0'	No sample	Loose	Brown Gray		0-0.3' = Pieces of cobble	SP	Dry	PID = 18.0
8	8			Dense	Dark brown		0.3-0.7' = Fine to medium SAND, well sorted	ML		FID = 18.6
8	7						0.8-1.4' = Sandy SILT with pieces of boulder			
10	13	1.3' / 2.0'	0805 OFF-SB-422-0406	Loose	Gray		0-0.7' = Fine to coarse SAND with gravel	SW	Dry	PID = 6.4
10	12			Dense	Dark gray Black		0.7-1.3' = SILT, trace clay, pieces of cobble	ML	Orange staining	FID = 334
10	12									
10	13						0.1-0.5' = SILT with sand, trace gravels			
12	6	1.3' / 2.0'	No sample	Dense	Gray		0.5-1.3' = Sandy SILT with orange staining	ML	Wet	PID = 6.0
12	8									FID = 3.2
12	7									
12	8									
14	6									
14	9	0.9' / 2.0'	No sample							
14	9									
14	15									
16	6									
16	11	1.5' / 2.0'	MS/MSD 0840 OFF-SB-422-1416	Dense	Gray		Silty fine SAND (0-0.5')	SM	Wet	PID = 0.3
16	12			Very Dense	Dark gray/ Black		0.5-1.5' = SILT with trace clay and gravels - till?	ML		FID = 0.0
16	16									

TYPE OF DRILLING RIG:

Track mounted CME

METHOD OF ADVANCING BORING:

Hollow stem auger

METHOD OF SOIL SAMPLING:

3" Split spoon, 2' long, 300 lb. hammer, 18" drop

METHOD OF ROCK CORING:

N/A

GROUNDWATER LEVELS:

~ 8' bgs

OTHER OBSERVATIONS:

BORING NO.: SB-422

Tetra Tech NUS, Inc.



PAGE: 1 OF 2



BORING LOG FOR: CTO 833 – OFFTA – SITE 09  
 PROJECT NO.: 4152-0552  
 LOGGED BY: J. DANIELI  
 DRILLED BY (Company/Driller): AMERICAN DRILLING / CARL BEIRHOLM  
 GRD. SURFACE ELEVATION: 17.3'

TRANSCRIBED BY: MES  
 ELEVATION FROM: NGVD 1929 (MLW)

BORING NO.: SB-433  
 START DATE: 11/26/03  
 COMPLETION: DATE: 11/26/03  
 MON. WELL NO.: —  
 CHECKED BY: DH

DEPTH (FEET)	BLOWS PER 6"	SAMP REC. / SAMP LENG.	SAMPLING TIME & SAMPLE NO. (QA/QC STATUS)	DEPTH MAT'L CHG/ WELL PROFL	SOIL DENSITY/ CONSIS. or ROCK HARD.	CLR	MATERIAL CLASSIFICATION	USCS or ROCK BRKN	REMARKS (moisture condition; odors; geological classification; rock weathering; etc.)	FIELD SCREENING DATA METHOD = [FID, (PPM)]
0							No split spoon – auger to 2' bgs			
			No sample							
2										
9									Dry	
8									PID = 0.0	
5									FID = 0.0	
4										
6										
8										
5										
3										
3										
8										
5										
3										
6										
10										
5										
6										
12										
2										
2										
12										
3										
27										
59										
14										
24										
130/3"										
0.8'										
2.0'										
16			No sample (14.0'-14.25')				Auger refusal at 14.5'			

TYPE OF DRILLING RIG:	Track mounted CME	Tetra Tech NUS, Inc.
METHOD OF ADVANCING BORING:	Hollow stem auger	
METHOD OF SOIL SAMPLING:	3" split spoon, 2' long, 300 lb. hammer, 18" drop	
METHOD OF ROCK CORING:	N/A	
GROUNDWATER LEVELS:	~ 5.5' BGS	
OTHER OBSERVATIONS:		BORING NO.: SB-433
		PAGE: 1 OF 2

BORING LOG FOR: CTO 833 - OFFTA - SITE 09  
 PROJECT NO.: 4152-0552  
 LOGGED BY: J. DANIELI  
 DRILLED BY (Company/Driller): AMERICAN DRILLING / CARL BEIRHOLM  
 GRD. SURFACE ELEVATION: 17.3'

TRANSCRIBED BY: MES  
 ELEVATION FROM: NGVD 1929 (MLW)

BORING NO.: SB-433  
 START DATE: 11/26/03  
 COMPLETION DATE: 11/26/03  
 MON. WELL NO.: --  
 CHECKED BY: DH

DEPTH (FEET)	BLOWS PER 6"	SAMP REC. / SAMP LENG.	SAMPLING TIME & SAMPLE NO. (OA/OC STATUS)	DEPTH MAT'L CHG./ WELL PROFL	SOIL DENSITY/ CONSIS. or ROCK HARD.	CLR	MATERIAL CLASSIFICATION	USCS or ROCK BRKN	REMARKS (moisture condition; odors; geological classification; rock weathering; etc.)	FIELD SCREENING DATA METHOD = [FID, (PPM)]
16	130/1"	0.15' / 0.16'	No sample Spoon only 14.5'-14.9'				0.15' in length Piece of concrete - move auger to 14.5' - try to send spoon down		(Recover 0.15' - Concrete)	FID = --
18							Move south - 5' to auger to 16' & taken 16-18' spoon			PID = --
16	14	0.9 / 2.0'	1050 OFF-SB-433-1618	Dense	Brown		Silty fine to medium SAND with gravel	SW	Wet (Second hole)	PID = 0.4
18	11								Wet	FID = 0.0
18	9									PID = 1.0
	11									FID = 0.0
	14									PID = 5.4
	19									
20	17									
	4	2.0'	1140 OFF-SB-433-2022							
	4		1145 Dup09							
22	8	2.0'					SILT - less sand and gravel Sandy SILT with gravels (20 - 21.5)	ML		
22	17									
	90									
	53	1.5' / 2.0'	No sample	Dense	Brown		SILT with trace sand and gravels (21.5 - 22.0')	ML	Wet	FID = 0.0
24	79									
24	29						SILT, weathered rock Orange staining, pieces of gravel, till - soupy	ML		PID = 1.6
	26	1.5' / 2.0'	1215 OFF-SB-433-2426							
	31		1220 Dup10							
26	38						Soupy - silty, sandy - GRAVEL with weathered rock, orange staining, till	GM	Wet	FID = 0.0
	130/4"	0.9' / 2.0'	No sample				Trace clay Auger refusal @ 27.5' bgs	GC GM		FID = 0.0
28										
	130/1"	0.8' / 0.8'	1240 OFF-SB-433-2830	Light Brown			Soupy, silty, sandy GRAVEL with weathered rock, orange staining - till	GM		PID = 0.0
30				Loose	Brown		Sample from 27.5' plus 1" - 27.7"			
							EOB @ 27.7" - did not reach competent bedrock but till overlies bedrock in area and just shy of 20' requirement stated in Work			

Plan - 20' from base of mound that is 8' high

TYPE OF DRILLING RIG:	Track mounted CME	Tetra Tech NUS, Inc.
METHOD OF ADVANCING BORING:	Hollow stem auger	
METHOD OF SOIL SAMPLING:	3" split spoon, 2' long, 300 lb. hammer, 18" drop	
METHOD OF ROCK CORING:	~ 5.5' bgs	
GROUNDWATER LEVELS:	N/A	
OTHER OBSERVATIONS:		BORING NO.: SB-433
		PAGE: 2 OF 2

**APPENDIX C**  
**SURVEY DATA**

# LOUIS FEDERICI and ASSOCIATES

365 Smith Street, Providence, RI 02908 Tel: 401-331-1570 Fax: 401-331-1583  
land surveyors, biologists, planners

Tabulation of field located soil samples for Tetra Tech NUS, Inc.  
at the Old Fire Fighting Training Area, Naval Station Newport, in Newport, RI

LFA PROJECT NUMBER = 990205

Date Surveyed: 1/2/2004

The values below are based on the following datums:

Horizontal = NAD 1927; Vertical = NGVD 1929 (MLW).

LFA PT NO.	TETRA TECH I.D.	NORTHING	EASTING	ORIGINAL GRADE
2000	SB-421	156808.8	547298.1	10.8
2001	SB-420	156797.6	547158.0	10.0
2002	SB-419	156842.2	547045.4	8.4
2003	SB-408	156940.5	547056.3	8.0
2004	SB-409	156924.9	547155.3	9.1
2005	SB-410	156914.9	547253.2	9.4
2006	SB-402	157010.9	547266.9	8.4
2007	SB-432	156869.0	547198.4	8.8
2008	SB-401	157029.8	547170.7	7.9
2009	SB-400	157035.6	547083.8	7.3
2010	SB-428	157054.9	547304.0	8.0
2011	SB-403	156956.3	547387.7	9.4
2012	SB-429	157023.5	547365.1	8.8
2013	SB-404	156982.7	547465.7	8.9
2014	SB-430	156918.5	547570.9	9.8
2015	SB-427	157072.7	547203.9	8.3
2182	SB-415	156886.6	546658.1	13.3
2187	SB-416	156875.4	546740.5	11.5
2231	SB-426	156745.4	547737.1	11.8
2233	SB-425	156761.1	547633.3	12.1
2234	SB-424	156787.4	547566.9	12.0
2235	SB-413	156872.0	547552.2	10.8
2238	SB-412	156853.2	547454.9	12.5
2239	SB-411	156890.1	547375.0	31.0
2240	SB-434	156819.2	547484.7	11.5
2245	SB-423	156768.4	547426.2	11.9
2247	SB-422	156807.4	547325.4	11.8
2248	SB-414	156855.1	547647.8	10.7
2249	SB-431	156809.4	547712.1	11.1
2277	SB-433	156900.7	546881.8	17.3
2278	SB-406	156851.9	546862.3	11.4
2279	SB-407	156959.5	546952.7	12.9
2280	SB-418	156871.9	546934.3	10.0
2281	SB-417	156864.9	546846.1	8.5
2292	SB-405	156961.0	546759.8	7.0

RI Rge. Number 1646

**APPENDIX D**  
**ANALYTICAL RESULTS**

- RI Soil Sample Analytical Results
- PDI Soil Sample Analytical Results

## **RI Soil Sample Analytical Results**

### Sample ID

#### **Surface Soil Samples**

SS-03  
SS-05  
SS-11  
SS25-110493  
SS26-110493  
B81-112293  
B91-112393  
B101-112393  
B141-121393  
B151-121393  
SS-325-0001  
SS-326-0001

#### **Subsurface Soil Samples**

TP23  
TP33  
TP32  
TP31  
B142-121393  
B152-121393  
B153-121393

SITE 09 - OLD FIRE FIGHTER TRAINING AREA  
 CONSTITUENTS DETECTED IN SURFACE SOIL SAMPLES  
 PAGE 1 OF 2

SAMPLE IDENTIFICATION:	SS-01	SS-02	SS-03	SS-04	SS-05	SS-06	FB-041290	TB-041290
<b>**** VOLATILE ORGANICS (PPB) ***</b>								
METHYLENE CHLORIDE.....	10 U*	14 U*	24 U*	11 U*	13 U*	12 U*	7 B	6 B
ACETONE.....	12 U**	10 U**	10 U**	10 U**	10 U**	12 U*	5 J	11
CARBON DISULFIDE.....								
CHLOROFORM.....								
2-BUTANONE.....			2 J					
TETRACHLOROETHENE.....								
TOLUENE.....								
ETHYLBENZENE.....								
XYLENE.....								
<b>TOTAL VOLATILE ORGANICS....</b>	<b>0</b>	<b>2</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>12</b>	<b>19</b>
<b>** BASE NEUTRAL / ACIDS (PPB) **</b>								
PHENOL.....							N/A	
BENZOIC ACID.....								
NAPHTHALENE.....e							480 J	
2-METHYLNAPHTHALENE.....e								
ACENAPHTHYLENE.....e							940 J	
ACENAPHTHENE.....e							650 J	
DIBENZOFURAN.....							1200 J	
FLUORENE.....e								
PHENANTHRENE.....e	83 J	350 J		250 J	100 J		1200	
ANTHRACENE.....e							1500 J	
DI-N-BUTYLPHthalATE.....								
FLUORANTHENE.....e	97 J	250 J	44 J	290 J	180 J		8000	
PYRENE.....e	160 J	480		300 J	190 J		5700 J*	
BUTYLBENZYLPHthalATE.....								
BENZO(a)ANTHRACENE.....ee				130 J	76 J		8300	
CHRYSENE.....ee				110 J	78 J		2800	
BIS(2-ETHYLHEXYL)PHthalATE.....590 *		450 U**		340 U*				
BENZO(b)FLUORANTHENE.....ee				120 J	65 J		2800	
BENZO(k)FLUORANTHENE.....ee				110 J			3100	
BENZO(a)PYRENE.....ee				120 J	61 J		2700	
INDENO(1,2,3-cd)PYRENE.....ee								
DIBENZO(a,h)ANTHRACENE.....ee								
BENZO(g,h,i)PERYLENE.....e							N/A	
<b>TOTAL BNA'S....</b>	<b>930</b>	<b>1751</b>	<b>44</b>	<b>1430</b>	<b>750</b>	<b>40370</b>	<b>0</b>	
<b>TOTAL PAH'S....</b>	<b>340</b>	<b>1751</b>	<b>44</b>	<b>1430</b>	<b>750</b>	<b>39720</b>	<b>0</b>	
<b>TOTAL CARCINOGENIC PAH'S...</b>	<b>0</b>	<b>671</b>	<b>0</b>	<b>590</b>	<b>280</b>	<b>14700</b>	<b>0</b>	

NOTE: \* - INDICATES THAT THE QUALIFIER HAS CHANGED ACCORDING TO DATA VALIDATION.

\*\*- INDICATES THAT THE CONTAMINANT VALUE HAS CHANGED ACCORDING TO DATA VALIDATION.

e - INDICATES THAT THE COMPOUND IS A POLYNUCLEAR AROMATIC HYDROCARBON (PAH).

ee - INDICATES THAT THE COMPOUND IS A CARCINOGENIC POLYNUCLEAR AROMATIC HYDROCARBON.

N/A - INDICATES THAT THE COMPOUNDS WERE NOT ANALYZED FOR.

SITE 09 - OLD FIRE FIGHTER TRAINING AREA  
CONSTITUENTS DETECTED IN SURFACE SOIL SAMPLES  
PAGE 2 OF 2

SAMPLE IDENTIFICATION:	SS-01	SS-02	SS-03	SS-04	SS-05	SS-06	FB-041290	TB-041290
<b>**** PESTICIDES/PCB'S (PPB) ****</b>								
4,4'-DDE.....	7.3 J	7.2 J	8.1 J	2.9 J	3.7 J			N/A
4,4'-DDT.....	6.3 J	6.8 U*	6.3 J	6.8 J	3.7 J	2.3 J		
AROCOLOR-1254.....	80 J							N/A
<b>***** INORGANICS (PPM) *****</b>								
SILVER.....		0.68 J*						N/A
ALUMINUM.....	8800	6080	8730	5070	10500	10600		
ARSENIC.....	6.2	5.1 J*	5.5	2	5.8	8.9		
BARIUM.....	25.8	18.7	21.8	21.7	28.3	8		
BERYLLIUM.....	0.47		0.41		0.48	0.39		
CALCIUM.....	1100	673	540	21000	1480	1670	0.19 B1	
CADMIUM.....				0.94				
COBALT.....	7.5	5.7	7.1	4.7	9.3	20		
CHROMIUM.....	15.9	6.8	18.8	8.8	16.7	16.4		
COPPER.....	27.1	11.2	16.8	15.4	23	44.3		
IRON.....	17400	10100	14500	10300	17800	35600		
MERCURY.....				0.17				
POTASSIUM.....	261	229	247	442	503	424		
MAGNESIUM.....	1480	917	1530	7340	1820	5010		
MANGANESE.....	249	174	185	174	251	750		
SODIUM.....	60.8 U*	49	47.6 U*	93.6 U*	91.9 U*	907	0.198	
NICKEL.....	12.3	5.4	10.9	7	12.8	25.6		
LEAD.....	52.5	19	21		28.1	77.8		
ANTIMONY.....						5.6		
SELENIUM.....	0.53						0.0022	
VANADIUM.....	24.5	9.8	19.5	19.3	27.4	36.3		
ZINC.....	80.1	26.2	32.4	34.5	70.4	142	0.0111	
CYANIDE.....							N/A	

NOTE: \* - INDICATES THAT THE QUALIFIER HAS CHANGED ACCORDING TO DATA VALIDATION.

N/A - INDICATES THAT THE COMPOUNDS WERE NOT ANALYZED FOR.

TABLE 1

SITE 09 - OLD FIRE FIGHTING TRAINING AREA  
CONSTITUENTS DETECTED IN SURFACE SOIL SAMPLES

SAMPLE IDENTIFICATION:	SS-07 (1)	SS-08 (2)	SS-12	SS-09	SS-10	SS-11	FB-1219
<b>***** INORGANICS (PPM) *****</b>							
SILVER.....							
ALUMINUM.....	4160	3430	2420	6120	6350	6570	
ARSENIC.....	3.5	2.2 B	2 B	5.6	4	4.4	
BARIUM.....	17 B	19.4 B	14 B	22.7 B	28.4 B	21.9 B	
BERYLLIUM.....			0.32 B	0.31 B	0.43 B	0.5 B	
CALCIUM.....	1090 B	859 B	628 B	1090 B	1220 B	1100 B	
CADMIUM.....							
COBALT.....	2.7 B	2.4 B	1.8 B	4.2 B	4 B	4.5 B	
CHROMIUM.....	8.7	5.8	4.3	10.3	10	8.5	
COPPER.....	8.4	9.8	6.9	9.7	13.4	11.4	
IRON.....	6760	6160	4470	9670	9470	10100	
MERCURY.....		0.08 B	0.07 B	0.07 B	0.09 B		
POTASSIUM.....	273 B	433 B	373 B	290 B	411 B		
MAGNESIUM.....	783 B	932 B	717 B	886 B	1010 B	945 B	
MANGANESE.....	143	166	117	169	197	201	
SODIUM.....							
NICKEL.....				8.6 B	6.2 B	5.1 B	
LEAD.....	22.2	27.5	26	32.4	38.7	20.6	
ANTIMONY.....							
SELENIUM.....							
THALLIUM.....							
VANADIUM.....	6.2 B	5.3 B	4.6 B	9.1 B	9.8 B	10.1 B	5.5 B
ZINC.....	36.1	38.1	26.6	34.9	46.3	35.3	

Note: (1) SS-07 was collected from the same location as SS-02.

(2) SS-12 is a duplicate sample of SS-8.

B = Indicates that the reported value is less than the CRDL

**TABLE L1.C**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**SURFACE SOIL SAMPLES**  
**SUMMARY OF PESTICIDE/PCB COMPOUNDS**

Page 4 of 12

Sample Location=	FF-SS24-110493			FF-SS25-110493			FF-SS26-110493			FF-SS27-110493			
Sample Designation=	031390-0004-SA			031390-0005-SA			031390-0006-SA			031390-0007-SA			
Sample Collection Date=	04 NOV 93			04 NOV 93			04 NOV 93			04 NOV 93			
Compound	Units	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Qual	Reporting Limit
alpha-BHC	ug/kg	ND	U	2.1	ND	U	1.8	ND	U	2.0	ND	R	2.1
beta-BHC	ug/kg	ND	U	2.1	ND	U	1.8	ND	U	2.0	ND	R	2.1
delta-BHC	ug/kg	ND	U	2.1	ND	U	1.8	ND	U	2.0	ND	R	2.1
gamma-BHC (Lindane)	ug/kg	0.37	J	2.1	0.096	J	1.8	ND	UJ*	2.0	ND	R	2.1
Heptachlor	ug/kg	ND	U	2.1	ND	U	1.8	ND	U	2.0	ND	R	2.1
Aldrin	ug/kg	ND	U	2.1	ND	U	1.8	ND	U	2.0	ND	R	2.1
Heptachlor epoxide	ug/kg	ND	U	2.1	ND	U	1.8	0.58	J	2.0	ND	R	2.1
Endosulfan I	ug/kg	ND	U	2.1	ND	U	1.8	ND	U	2.0	ND	R	2.1
Dieldrin	ug/kg	0.91	NJ	4.1	0.66	J	3.5	ND	UJ*	6.2	ND	R	4.1
4,4'-DDE	ug/kg	12		4.1	10		3.5	5.1	J	3.9	ND	R	4.1
Endrin	ug/kg	3.6	J	4.1	2.2	NJ	3.5	ND	U	3.9	ND	R	4.1
Endosulfan II	ug/kg	ND	U	4.1	ND	U	3.5	ND	U	3.9	ND	R	4.1
4,4'-DDD	ug/kg	2.3	J	4.1	5.5		3.5	ND	U	3.9	ND	R	4.1
Endosulfan sulfate	ug/kg	ND	U	4.1	ND	U	3.5	ND	U	3.9	ND	R	4.1
4,4'-DDT	ug/kg	14		4.1	17		3.5	9.4	J	3.9	ND	R	4.1
Methoxychlor	ug/kg	ND	U*	21	3.8	J	18	ND	U	20	ND	R	21
Endrin ketone	ug/kg	ND	U	4.1	ND	U	3.5	ND	U	3.9	ND	R	4.1
Endrin aldehyde	ug/kg	6.9	J	4.1	5.1	J	3.5	9.4		3.9	ND	R	4.1
alpha-Chlordane	ug/kg	ND	U	2.1	ND	U	1.8	0.62	J	2.0	ND	R	2.1
gamma-Chlordane	ug/kg	ND	U	2.1	ND	U	1.8	ND	U	2.0	ND	R	2.1
Toxaphene	ug/kg	ND	U	210	ND	U	180	ND	U	200	ND	R	210
Aroclor 1016	ug/kg	ND	U	41	ND	U	35	ND	U	39	ND	R	41
Aroclor 1221	ug/kg	ND	U	84	ND	U	71	ND	U	79	ND	R	84
Aroclor 1232	ug/kg	ND	U	41	ND	U	35	ND	U	39	ND	R	41
Aroclor 1242	ug/kg	ND	U	41	ND	U	35	ND	U	39	ND	R	41
Aroclor 1248	ug/kg	ND	U	41	ND	U	35	ND	U	39	ND	R	41
Aroclor 1254	ug/kg	ND	U	41	ND	U	35	ND	U	39	ND	R	41
Aroclor 1260	ug/kg	ND	U	41	ND	U	35	ND	U	39	ND	R	41

NOTE: \*\* indicates a value which was changed to 'ND' following data validation

**TABLE L1.B**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**SURFACE SOIL SAMPLES**  
**SUMMARY OF SEMIVOLATILE ORGANIC COMPOUNDS**

Sample Location	FF-SS24-110493 031390-0004-SA 04 NOV 93			FF-SS25-110493 031390-0005-SA 04 NOV 93			FF-SS26-110493 031390-0006-SA 04 NOV 93			Page 5 of 15		
Compound	Units	Sample Value	Reporting Limit	Sample Value	Reporting Limit	Sample Value	Reporting Limit	Sample Value	Qual	Reporting Limit		
Acenaphthene	ug/kg	ND	U	420	ND	U	350	ND	U	390		
Acenaphthylene	ug/kg	ND	U	420	ND	U	350	ND	U	390		
Anthracene	ug/kg	ND	U	420	ND	U	350	ND	U	390		
9H-Carbazole	ug/kg	ND	U	420	ND	U	350	ND	U	390		
Benzo(a)anthracene	ug/kg	ND	U	420	ND	U	350	ND	U	390		
Benzo(a)pyrene	ug/kg	ND	U	420	ND	U	350	ND	U	390		
Benzo(b)fluoranthene	ug/kg	46	U	420	36	U	350	ND	U	390		
Benzo(g,h,i)perylene	ug/kg	ND	U	420	ND	U	350	ND	U	390		
Benzo(k)fluoranthene	ug/kg	ND	U	420	ND	U	350	ND	U	390		
4-Bromophenyl phenyl ether	ug/kg	ND	U	420	ND	U	350	ND	U	390		
Butyl benzyl phthalate	ug/kg	ND	U	420	ND	U	350	ND	U	390		
4-Chloroaniline	ug/kg	ND	U	420	ND	U	350	ND	U	390		
bis(2-Chloroethoxy)-methane	ug/kg	ND	U	420	ND	U	350	ND	U	390		
bis(2-Chloroethyl) ether	ug/kg	ND	U	420	ND	U	350	ND	U	390		
bis(2-Chloroisopropyl) ether	ug/kg	ND	U	420	ND	U	350	ND	U	390		
4-Chloro-3-methylphenol	ug/kg	ND	U	420	ND	U	350	ND	U	390		
2-Chloronaphthalene	ug/kg	ND	U	420	ND	U	350	ND	U	390		
2-Chlorophenol	ug/kg	ND	U	420	ND	U	350	ND	U	390		
4-Chlorophenyl phenyl ether	ug/kg	ND	U	420	ND	U	350	ND	U	390		
Chrysene	ug/kg	ND	U	420	ND	U	350	ND	U	390		
Di-n-butyl phthalate	ug/kg	ND	U	420	ND	U	350	ND	U	390		
Dibenz(a,h)anthracene	ug/kg	ND	U	420	ND	U	350	ND	U	390		
Dibenzo furan	ug/kg	ND	U	420	ND	U	350	ND	U	390		
1,2-Dichlorobenzene	ug/kg	ND	U	420	ND	U	350	ND	U	390		
1,3-Dichlorobenzene	ug/kg	ND	U	420	ND	U	350	ND	U	390		
1,4-Dichlorobenzene	ug/kg	ND	U	420	ND	U	350	ND	U	390		
1'-Dichlorobenzidine	ug/kg	ND	U	420	ND	U	350	ND	U	390		
1-Dichlorophenol	ug/kg	ND	U	420	ND	U	350	ND	U	390		
Diethyl phthalate	ug/kg	ND	U	420	ND	U	350	ND	U	390		
2,4-Dimethylphenol	ug/kg	ND	U	420	ND	U	350	ND	U	390		
Dimethyl phthalate	ug/kg	ND	U	420	ND	U	350	ND	U	390		
4,6-Dinitro-2-methylphenol	ug/kg	ND	U	1000	ND	U	850	ND	U	940		
2,4-Dinitrophenol	ug/kg	ND	U	1000	ND	U	850	ND	U	940		
2,4-Dinitrotoluene	ug/kg	ND	U	420	ND	U	350	ND	U	390		
2,6-Dinitrotoluene	ug/kg	ND	U	420	ND	U	350	ND	U	390		
Di-n-octyl phthalate	ug/kg	ND	U	420	ND	U	350	ND	U	390		
bis(2-Ethylhexyl) phthalate	ug/kg	ND	U	420	ND	U	350	ND	U	390		
Fluoranthene	ug/kg	46	U	420	38	U	350	ND	U	390		
Fluorene	ug/kg	ND	U	420	ND	U	350	ND	U	390		
Hexachlorobenzene	ug/kg	ND	U	420	ND	U	350	ND	U	390		
Hexachlorobutadiene	ug/kg	ND	U	420	ND	U	350	ND	U	390		
Hexachlorocyclo-pentadiene	ug/kg	ND	U	420	ND	U	350	ND	U	390		
Hexachloroethane	ug/kg	ND	U	420	ND	U	350	ND	U	390		
Indeno(1,2,3-cd)pyrene	ug/kg	ND	U	420	ND	U	350	ND	U	390		
Isophorone	ug/kg	ND	U	420	ND	U	350	ND	U	390		
2-Methylnaphthalene	ug/kg	ND	U	420	ND	U	350	ND	U	390		
2-Methylphenol	ug/kg	ND	U	420	ND	U	350	ND	U	390		
4-Methylphenol	ug/kg	ND	U	420	ND	U	350	ND	U	390		
Naphthalene	ug/kg	ND	U	420	ND	U	350	ND	U	390		
2-Nitroaniline	ug/kg	ND	U	1000	ND	U	850	ND	U	940		
3-Nitroaniline	ug/kg	ND	U	1000	ND	U	850	ND	U	940		
4-Nitroaniline	ug/kg	ND	U	1000	ND	U	850	ND	U	940		
Nitrobenzene	ug/kg	ND	U	420	ND	U	350	ND	U	390		
2-Nitrophenol	ug/kg	ND	U	420	ND	U	350	ND	U	390		
4-Nitrophenol	ug/kg	ND	U	1000	ND	U	850	ND	U	940		
N-Nitrosodiphenylamine	ug/kg	ND	U	420	ND	U	350	ND	U	390		
N-Nitroso-di-n-propylamine	ug/kg	ND	U	420	ND	U	350	ND	U	390		
Pentachlorophenol	ug/kg	ND	U	1000	ND	U	850	ND	U	940		
Phenanthrene	ug/kg	ND	U	420	ND	U	350	ND	U	390		
Phenol	ug/kg	ND	U	420	ND	U	350	ND	U	390		
Pyrene	ug/kg	46	U	420	40	U	350	49	J	390		
1,2,4-Trichlorobenzene	ug/kg	ND	U	420	ND	U	350	ND	U	390		
2,4,5-Trichlorophenol	ug/kg	ND	U	1000	ND	U	850	ND	U	940		
2,4,6-Trichlorophenol	ug/kg	ND	U	420	ND	U	350	ND	U	390		
a) PAHs		140			114			49				
a) Carcinogenic PAHs		46			36			0				
Total SVOCs		140			114			49				

NOTE: "J" indicates a value which was changed to "ND" following data validation.

**TABLE L1.D**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**SURFACE SOIL SAMPLES**  
**SUMMARY OF INORGANIC ANALYTES**

Page 4 of 12

Sample Location=		FF-SS24-110493				FF-SS25-110493				FF-SS26-110493				FF-SS27-110493			
Sample Designation=	031390-0004-SA	Sample Value	Qual	Reporting Limit	Sample Value	Qual	Reporting Limit	Sample Value	Qual	Reporting Limit	Sample Value	Qual	Reporting Limit	Sample Value	Qual	Reporting Limit	
Sample Collection Date=	04 NOV 93				04 NOV 93			04 NOV 93			04 NOV 93			04 NOV 93			
Aluminum	mg/kg	9360		NA	9890		NA	9090		NA	7650		NA	6.2	UJ	NA	
Antimony	mg/kg	6.3		UJ	5.4		UJ	5.9		UJ	NA		NA	4.3	J	NA	
Arsenic	mg/kg	5.2		J	NA		NA	5.2		J	NA		NA	20.9	B	NA	
Barium	mg/kg	24		B	NA		NA	22.8		B	NA		NA	0.31	B	NA	
Beryllium	mg/kg	0.36		B	NA		NA	0.33		B	NA		NA	0.75	U	NA	
Cadmium	mg/kg	0.75		U	NA		NA	0.71		U	NA		NA	19	J	NA	
Calcium	mg/kg	907		J	NA		NA	604		J	NA		NA	14.9	J	NA	
Chromium	mg/kg	16.7		NA	10.5		NA	12.1		NA	NA		NA	1460	J	NA	
Cobalt	mg/kg	5.5		B	NA		NA	5.6		B	NA		NA	173	U	NA	
Copper	mg/kg	9.8		NA	14.2		NA	8.8		NA	NA		NA	300	U	NA	
Iron	mg/kg	13300		NA	14200		NA	14300		NA	11800		NA	0.5	UW	NA	
Lead	mg/kg	16.5		J	NA		NA	16.1		J	NA		NA	0.5	U	NA	
Magnesium	mg/kg	1720		NA	1720		NA	1790		NA	NA		NA	1.8	U	NA	
Manganese	mg/kg	191		NA	205		NA	210		NA	NA		NA	41/5	NA	NA	
Mercury	mg/kg	0.06		U	NA		NA	0.06		U	NA		NA	0.62	NA	NA	
Nickel	mg/kg	11.5		NA	12.8		NA	12		NA	NA		NA	1.63	U	NA	
Potassium	mg/kg	351		B	NA		NA	286		B	NA		NA	0.5	U	NA	
Selenium	mg/kg	0.5		U	NA		NA	0.47		U	NA		NA	1.13	U	NA	
Silver	mg/kg	1		U	NA		NA	0.94		U	NA		NA	1	U	NA	
Sodium	mg/kg	302		U	NA		NA	283		U	NA		NA	0.5	UW	NA	
Thallium	mg/kg	0.5		U	NA		NA	0.47		U	NA		NA	0.62	U	NA	
Vanadium	mg/kg	16.9		NA	16		NA	15.3		NA	NA		NA	1.8	NA	NA	
Zinc	mg/kg	40.6		NA	38.2		NA	37.2		NA	NA		NA	41/5	NA	NA	
Cyanide, Total	mg/kg	NA		NA	NA		NA	NA		NA	NA		NA	0.62	U	NA	

**SURFACE SOIL VOLATILE ORGANIC ANALYSIS (UG/KG)**  
**OLD FIREFIGHTER TRAINING AREA**  
**REMEDIATION INVESTIGATION REPORT**  
**NAVSTA NEWPORT, NEWPORT, RHODE ISLAND**

Sample Number	OFF-SS-323-0001	OFF-SS-324-0001	OFF-SS-325-0001	OFF-SS-326-0001	OFF-SS-327-0001	OFF-SS-328-0001-MAX	OFF-SS-329-0001
Date Sampled	11/19/98	11/19/98	11/19/98	11/19/98	11/19/98	11/20/98	11/20/98
QC Identifier	None	None	None	None	None	Field Dup. OFF-SS-328-0001	None
Interval (ft)	0.0-1.0	0.0-1.0	0.0-1.0	0.0-1.0	0.0-1.0	0.0-1.0	0.0-1.0
1,1,1-TRICHLOROETHANE	4 U	5 U	8 U	5 U	5 U	5 U	5 U
1,1,2,2-TETRACHLOROETHANE	4 U	5 U	8 U	5 U	5 U	5 U	5 U
1,1,2-TRICHLOROETHANE	4 U	5 U	8 U	5 U	5 U	5 U	5 U
1,1-DICHLOROETHANE	4 U	5 U	8 U	5 U	5 U	5 U	5 U
1,1-DICHLOROETHENE	4 U	5 U	8 U	5 U	5 U	5 U	5 U
1,2-DICHLOROETHANE	4 U	5 U	8 U	5 U	5 U	5 U	5 U
1,2-DICHLOROETHENE (TOTAL)	4 U	5 U	8 U	5 U	5 U	5 U	5 U
2-DICHLOROPROPANE	4 U	5 U	8 U	5 U	5 U	5 U	5 U
2-BUTANONE	9 U	9 J	28 U	11 U	7 J	11 U	11 U
2-HEXANONE	9 U	9 U	17 U	11 U	10 U	10 U	11 U
4-METHYL-2-PENTANONE	9 U	9 U	17 U	11 U	10 U	10 U	11 U
ACETONE	150 J	130 J	320 J	80 U	77 J	110	100 J
BENZENE	4 U	5 U	8 U	5 U	5 U	5 U	5 U
BROMODICHLOROMETHANE	4 U	5 U	8 U	5 U	5 U	5 U	5 U
BROMOFORM	4 U	5 U	8 U	5 U	5 U	5 U	5 U
BROMOMETHANE	4 U	5 U	8 U	5 U	5 U	5 U	5 U
CARBON DISULFIDE	4 U	5 U	8 U	5 U	5 U	5 U	5 U
CARBON TETRACHLORIDE	4 U	5 U	8 U	5 U	5 U	5 U	5 U
CHLOROBENZENE	4 U	5 U	8 U	5 U	5 U	5 U	5 U
CHLOROETHANE	4 U	5 U	8 U	5 U	5 U	5 U	5 U
CHLOROFORM	4 U	5 U	8 U	5 U	5 U	5 U	5 U
CHLOROMETHANE	4 U	5 U	8 U	5 U	5 U	5 U	5 U
CIS-1,3-DICHLOROPROPENE	4 U	5 U	8 U	5 U	5 U	5 U	5 U
DIBROMOCHLOROMETHANE	4 U	5 U	8 U	5 U	5 U	5 U	5 U
ETHYLBENZENE	4 U	5 U	8 U	5 U	5 U	5 U	5 U
METHYLENE CHLORIDE	2 J	4 J	3 J	2 J	3 J	2	3 J
STYRENE	4 U	5 U	8 U	5 U	5 U	5 U	5 U
TETRACHLOROETHENE	4 U	5 U	8 U	5 U	5 U	5 U	5 U
TOLUENE	4 U	5 U	8 U	5 U	5 U	5 U	5 U
TOTAL XYLEMES	4 U	5 U	8 U	5 U	5 U	5 U	5 U
TRANS-1,3-DICHLOROPROPENE	4 U	5 U	8 U	5 U	5 U	5 U	5 U
TRICHLOROETHENE	4 U	5 U	8 U	5 U	5 U	5 U	5 U
VINYL CHLORIDE	4 U	5 U	8 U	5 U	5 U	5 U	5 U

U - Not detected; UJ - Detection limit approximate; J - Quantitation approximate; EB/TB - Equipment/Trip Blank contamination;  
NA - Not Analyzed; \* - From dilution analysis; R - Rejected; EMPC - Est. Max. Poss. Conc.

**SURFACE SOIL SEMIVOLATILE ORGANIC ANALYSIS (UG/KG)**  
**OLD FIREFIGHTER TRAINING AREA**  
**REMEDIAL INVESTIGATION REPORT**  
**NAVSTA NEWPORT, NEWPORT, RHODE ISLAND**

Sample Number	OFF-SS-322-0001	OFF-SS-323-0001	OFF-SS-324-0001	OFF-SS-325-0001	OFF-SS-326-0001	OFF-SS-327-0001	OFF-SS-328-0001-MAX
Date Sampled	11/19/98	11/19/98	11/19/98	11/19/98	11/19/98	11/19/98	11/20/98
QC Identifier	None	None	None	None	None	None	Field Dup. OFF-SS-328-0001
Interval (ft)	0.0-1.0	0.0-1.0	0.0-1.0	0.0-1.0	0.0-1.0	0.0-1.0	0.0-1.0
1,2,4-TRICHLOROBENZENE	350 U	360 U	1600 U	670 U	400 U	1900 U	390 U
1,2-DICHLOROBENZENE	350 U	360 U	1600 U	670 U	400 U	1900 U	390 U
1,3-DICHLOROBENZENE	350 U	360 U	1600 U	670 U	400 U	1900 U	390 U
1,4-DICHLOROBENZENE	350 U	360 U	1600 U	670 U	400 U	1900 U	390 U
2,2-OXYBIS(1-CHLOROPROPANE)	350 UJ	360 UJ	1600 UJ	670 U	400 UJ	1900 UJ	390 U
2,4,5-TRICHLOROPHENOL	890 U	900 U	4600 UJ	1700 U	1000 U	4700 UJ	980 U
2,4,6-TRICHLOROPHENOL	350 U	360 U	1600 U	670 U	400 U	1900 U	390 U
2,4-DICHLOROPHENOL	350 U	360 U	1600 U	670 U	400 U	1900 U	390 U
2,4-DIMETHYLPHENOL	350 U	360 U	1600 U	670 U	400 U	1900 U	390 U
2,4-DINITROPHENOL	890 U	900 U	4600 UJ	1700 UJ	1000 UJ	4700 UJ	980 U
2,4-DINITROTOLUENE	350 U	360 U	1600 U	670 U	400 U	1900 U	390 U
2,6-DINITROTOLUENE	350 U	360 U	1600 U	670 U	400 U	1900 U	390 U
2-CHLORONAPHTHALENE	350 U	360 U	1600 U	670 U	400 U	1900 U	390 U
2-CHLOROPHENOL	350 U	360 U	1600 U	670 U	400 U	1900 U	390 U
2-METHYLNAPHTHALENE	350 U	360 U	1600 U	670 U	400 U	1900 U	390 U
2-METHYLPHENOL	350 U	360 U	1600 U	670 U	400 U	1900 U	390 U
2-NITROANILINE	890 U	900 U	4600 U	1700 UJ	1000 U	4700 U	980 U
2-NITROPHENOL	350 U	360 U	1600 U	670 U	400 U	1900 U	390 U
3,3'-DICHLOROBENZIDINE	350 U	360 U	1600 UJ	670 UJ	400 UJ	1900 UJ	390 U
3-NITROANILINE	890 U	900 U	4600 U	1700 U	1000 U	4700 U	980 U
4,6-DINITRO-2-METHYLPHENOL	890 U	900 U	4600 U	1700 UJ	1000 UJ	4700 U	980 U
4-BROMOPHENYL-PHENYLETHER	350 U	360 U	1600 U	670 U	400 U	1900 U	390 U
4-CHLORO-3-METHYLPHENOL	350 U	360 U	1600 U	670 U	140 J	1900 U	390 U
4-CHLOROANILINE	350 U	360 U	1600 U	670 U	400 U	1900 U	390 U
4-CHLOROPHENYL-PHENYLETHER	350 U	360 U	1600 U	670 U	400 U	1900 U	390 U
4-METHYLPHENOL	350 U	360 U	1600 U	670 U	400 U	1900 U	390 U
4-NITROANILINE	890 U	900 U	4600 UJ	1700 UJ	1000 UJ	4700 UJ	980 U
4-NITROPHENOL	890 U	900 U	4600 UJ	1700 UJ	1000 U	4700 UJ	980 U
ACENAPHTHENE	350 U	360 U	1600 UJ	670 U	400 U	240 J	390 U
ACENAPHTHYLENE	350 U	360 U	1600 U	670 U	400 U	1900 U	390 U
ANTHRACENE	350 U	360 U	1600 U	95 J	400 U	1800 J	390 U
BENZO(A)ANTHRACENE	350 U	360 U	1600 U	300 J	400 U	2500	390 U
BENZO(A)PYRENE	350 U	360 U	1600 U	300 J	400 U	1900	390 U
BENZO(B)FLUORANTHENE	350 U	360 U	210 J	400 J	400 U	2400	45 J
BENZO(G,H,I)PERYLENE	350 U	360 U	1600 U	150 J	400 U	1200 J	390 U

U - Not detected; UJ - Detection limit approximate; J - Quantitation approximate; EB/TB - Equipment/Trip Blank contamination;  
NA - Not Analyzed; \* - From dilution analysis; R - Rejected; EMPC - Est. Max. Poss. Conc.

SURFACE SOIL SEMIVOLATILE ORGANIC ANALYSIS (UG/KG)  
 OLD FIREFIGHTER TRAINING AREA  
 REMEDIAL INVESTIGATION REPORT  
 NAVSTA NEWPORT, NEWPORT, RHODE ISLAND

Sample Number	OFF-SS-322-0001	OFF-SS-323-0001	OFF-SS-324-0001	OFF-SS-325-0001	OFF-SS-326-0001	OFF-SS-327-0001	OFF-SS-328-0001-MAX
Date Sampled	11/19/98	11/19/98	11/19/98	11/19/98	11/19/98	11/19/98	11/20/98
QC Identifier	None	None	None	None	None	None	
Interval (ft)	0.0-1.0	0.0-1.0	0.0-1.0	0.0-1.0	0.0-1.0	0.0-1.0	0.0-1.0
BENZO(K)FLUORANTHENE	350 U	360 U	1800 U	170 J	400 U	930 J	390 U
BIS(2-CHLOROETHOXY)METHANE	350 U	360 U	1800 U	670 U	400 U	1900 U	390 U
BIS(2-CHLOROETHYL)ETHER	350 U	360 U	1800 U	670 U	400 U	1900 U	390 U
BIS(2-ETHYLHEXYL)PHTHALATE	350 U	360 U	1800 U	670 U	400 U	1900 U	390 U
BUTYLBENZYLPHthalate	350 U	360 U	1800 U	670 U	400 U	1900 U	390 U
CARBAZOLE	350 U	360 U	1800 U	670 U	400 U	1900 U	390 U
CHRYSENE	350 U	360 U	1800 U	270 J	400 U	2300	41
DI-N-BUTYLPHthalate	53 J	50 U	1800 U	94 J	400 U	1900 U	390 U
DI-N-OCTYLPHthalate	350 U	360 U	1800 U	670 UJ	400 U	1900 UJ	390 U
DIBENZO(A,H)ANTHRACENE	350 U	360 U	1800 U	670 U	400 U	230 J	390 U
DIBENZOFURAN	350 U	360 U	1800 U	670 U	400 U	220 J	390 U
DIETHYLPHthalate	350 U	360 U	1800 U	670 U	400 U	1900 U	390 U
DIMETHYLPHthalate	350 U	360 U	1800 U	670 U	400 U	1900 U	390 U
FLUORANTHENE	350 U	360 U	210 J	660 J	400 U	5500	78
FLUORENE	350 U	360 U	1800 U	670 U	400 U	370 J	390 U
HEXACHLOROBENZENE	350 U	360 U	1800 U	670 UJ	400 UJ	1900 U	390 U
HEXACHLOROBUTADIENE	350 U	360 U	1800 U	670 U	400 U	1900 U	390 U
HEXACHLOROCYCLOPENTADIENE	350 U	360 U	1800 U	670 U	400 U	1900 U	390 U
HEXACHLOROETHANE	350 U	360 U	1800 U	670 U	400 U	1900 U	390 U
INDENO(1,2,3-CD)PYRENE	350 U	360 U	1800 U	160 J	400 U	1900 J	390 U
ISOPHORONE	350 U	360 U	1800 U	670 U	400 U	1900 U	390 U
N-NITROSO-DI-N-PROPYLAMINE	350 U	360 U	1800 U	670 U	400 U	1900 U	390 U
N-NITROSO-DIPHENYLAMINE	350 U	360 U	1800 U	670 U	400 U	1900 U	390 U
NAPHTHALENE	350 U	360 U	1800 U	670 U	400 U	1900 U	390 U
NITROBENZENE	350 U	360 U	1800 U	670 U	400 U	1900 U	390 U
PENTACHLOROPHENOL	890 U	900 U	4600 UJ	1700 UJ	1000 U	4700 UJ	980 U
PHENANTHRENE	350 U	360 U	1800 U	440 J	400 U	4700	47
PHENOL	350 U	360 U	1800 U	670 U	400 U	1900 U	390 U
PYRENE	41 J	360 U	270	690	400 U	4700	72

U - Not detected; UJ - Detection limit approximate; J - Quantitation approximate; EB/TB - Equipment/Trip Blank contamination;  
 NA - Not Analyzed; \* - From dilution analysis; R - Rejected; EMPC - Est. Max. Poss. Conc.

SURFACE SOIL TAL METAL ANALYSIS (MG/KG)  
 OLD FIREFIGHTER TRAINING AREA  
 REMEDIAL INVESTIGATION REPORT  
 NAVSTA NEWPORT, NEWPORT, RHODE ISLAND

Sample Number	OFF-SS-325-0001	OFF-SS-326-0001	OFF-SS-327-0001	OFF-SS-328-0001-MAX	OFF-SS-329-0001	OFF-SS-330-0001	OFF-SS-331-0001	OFF-SS-332-0001
Date Sampled	11/19/98	11/19/98	11/19/98	11/20/98	11/20/98	11/18/98	11/18/98	11/20/98
QC Identifier	None	None	None	Field Dup. OFF-SS-328-0001	None	None	None	None
Interval (ft)	0.0-1.0	0.0-1.0	0.0-1.0	0.0-1.0	0.0-1.0	0.0-1.0	0.0-1.0	0.0-1.0
ALUMINUM	10700	10900	11000	11000	11400	J	11400	10400
ANTIMONY	1.1	U	0.58	U	0.58	J	0.57	UJ
ARSENIC	10.4		10.1	7.7	10.3		8.7	J
BARIUM	24.7		24.7	27.7		27.7		25.9
BERYLLIUM	0.35	J	0.47	0.32	U	0.38	0.39	J
CADMIUM	0.1	U	0.09	U	0.08	U	0.09	U
CALCIUM	707		1210	2610	J	1070	U	5970
CHROMIUM	11.1		11	12.2		9.8	10.9	13.7
COBALT	8.6		6.8	7		8.5	9.4	5.8
COPPER	16.8		8.8	J	13.6		13.5	14.3
IRON	20200		18100	18000		21000	18100	J
LEAD	46.1	J	18.9	J	36.1		26.1	30.3
MAGNESIUM	2420		1910	2420		1910	3780	J
MANGANESE	293		196	282		305	228	J
MERCURY	0.06	U	0.06	U	0.05	U	0.06	U
NICKEL	15.7		13.2	13.1		15.5	U	17.2
POTASSIUM	260	U	274	U	425		234	269
SELENIUM	0.77	U	0.69	U	0.64	U	0.68	U
SILVER	6	U	5.6	U	3.1	J	5.3	4.3
SODIUM	84.9	U	99.1	U	105	J	216	U
THALLIUM	0.58	U	0.51	U	0.48	U	0.51	U
VANADIUM	18.8		19.3		17.3		18.3	
ZINC	61.5		33.8		75.1		50.3	

U - Not detected; UJ - Detection limit approximate; J - Quantitation approximate; EB/TB - Equipment/Trip Blank contamination;  
 NA - Not Analyzed; \* - From dilution analysis; R - Rejected; EMPC - Est. Max. Poss. Conc.

**TABLE L1.A**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**SURFACE SOIL SAMPLES**  
**SUMMARY OF VOLATILE ORGANIC COMPOUNDS**

Page 5 of 12

Sample Location=	FF-SS31-110493 031390-0012-SA 04 NOV 93			FF-B81-112293 031806-0005-SA 22 NOV 93			FF-B91-112393 031806-0008-SA 23 NOV 93			FF-B101-112393 031813-0008-SA 23 NOV 93			
Compound	Units	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit
Chloromethane	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
Bromomethane	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
Vinyl Chloride	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
Chloroethane	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
Methylene chloride	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
Acetone	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
Carbon disulfide	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
1,1-Dichloroethene	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
1,1-Dichloroethane	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
1,2-Dichloroethene (cis/trans)	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
Chloroform	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
1,2-Dichloroethane	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
2-Butanone	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
1,1,1-Trichloroethane	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
Carbon tetrachloride	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
Bromodichloromethane	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
1,2-Dichloropropane	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
cis-1,3-Dichloropropene	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
Trichloroethene	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
Dibromochloromethane	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
1,1,2-Trichloroethane	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
Benzene	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
trans-1,3-Dichloropropene	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
Bromoform	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
4-Methyl-2-Pentanone	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
2-Hexanone	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
1,1,2,2-Tetrachloroethane	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
Tetrachloroethene	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	16		11
Toluene	ug/kg	ND	U	12	ND	UJ	12	2	J	11	ND	U	11
Chlorobenzene	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
Ethylbenzene	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
Styrene	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
Xylenes (total)	ug/kg	ND	U	12	ND	UJ	12	ND	UJ	11	ND	U	11
Total VOCs		0			0			2			16		

NOTE: " " indicates a value which was changed to 'Not Detected' following data validation

**TABLE L1.A**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**SURFACE SOIL SAMPLES**  
**SUMMARY OF VOLATILE ORGANIC COMPOUNDS**

Page 6 of 12

Sample Location=	FF-B111-112493 031813-0001-SA 24 NOV 93				FF-B121-112493 031813-0003-SA 24 NOV 93				FF-B131-112393 031806-0009-SA 23 NOV 93				FF-B141-121393 32184-01-SA 13 DEC 93			
Compound	Units	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Qual	Reporting Limit			
Chloromethane	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	ND	U	12			
Bromomethane	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	12			
Vinyl Chloride	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	3	J	12			
Chloroethane	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	ND	U	12			
Methylene chloride	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	ND	U	12			
Acetone	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	ND	U	12			
Carbon disulfide	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	ND	U	12			
1,1-Dichlorethene	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	ND	U	12			
1,1-Dichloroethane	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	ND	U	12			
1,2-Dichloroethene (cis/trans)	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	17		12			
Chloroform	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	ND	U	12			
1,2-Dichloroethane	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	ND	U	12			
2-Butanone	ug/kg	3	J	11	3	J	11	ND	UJ	11	1	J	12			
1,1,1-Trichloroethane	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	ND	U	12			
Carbon tetrachloride	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	ND	U	12			
Bromodichloromethane	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	ND	U	12			
1,2-Dichloropropane	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	ND	U	12			
cis-1,3-Dichloropropene	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	ND	U	12			
Trichloroethene	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	ND	U	12			
Dibromochloromethane	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	ND	U	12			
1,1,2-Trichloroethane	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	ND	U	12			
Benzene	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	ND	U	12			
trans-1,3-Dichloropropene	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	ND	U	12			
Bromoform	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	ND	U	12			
4-Methyl-2-Pentanone	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	ND	U	12			
2-Hexanone	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	ND	U	12			
1,1,2-Tetrachloroethane	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	ND	U	12			
Tetrachloroethene	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	ND	U	12			
Toluene	ug/kg	ND	U	11	2	J	11	ND	UJ	11	ND	U	12			
Chlorobenzene	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	ND	U	12			
Ethylbenzene	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	ND	U	12			
Styrene	ug/kg	ND	U	11	ND	U	11	ND	UJ	11	ND	U	12			
Xylenes (total)	ug/kg	ND	U	11	ND	U	11	ND	UJ	N	ND	U	12			
Total VOCs		3			5			0			21					

NOTE: \*\* indicates a value which was changed to 'Not Detected' following data validation

**TABLE L1.A**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**SURFACE SOIL SAMPLES**  
**SUMMARY OF VOLATILE ORGANIC COMPOUNDS**

Page 7 of 12

Sample Location=	FF-B151-121393	Sample Location=	FF-B161-112393	Sample Location=	FF-B164-112393 (Dup of B161)	Sample Location=	FF-B171-112493						
Sample Designation=	32184-03-SA	Sample Designation=	031806-0011-SA	Sample Designation=	031806-0014-SA	Sample Designation=	031813-0005-SA						
Sample Collection Date=	13 DEC 93	Sample Collection Date=	23 NOV 93	Sample Collection Date=	23 NOV 93	Sample Collection Date=	24 NOV 93						
Compound	Units	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit
Chloromethane	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
Bromomethane	ug/kg	ND	UJ	11	ND	UJ	11	ND	UJ	11	ND	U	11
Vinyl Chloride	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
Chloroethane	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
Methylene chloride	ug/kg	1	J	11	ND	UJ	11	ND	UJ	11	ND	U	11
Acetone	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
Carbon disulfide	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
1,1-Dichloroethene	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
1,1-Dichloroethane	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
1,2-Dichloroethene (cis/trans)	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
Chloroform	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
1,2-Dichloroethane	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
2-Butanone	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
1,1,1-Trichloroethane	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
Carbon tetrachloride	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
Bromodichloromethane	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
1,2-Dichloropropane	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
cis-1,3-Dichloropropene	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
Trichloroethene	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
Dibromochloromethane	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
1,1,2-Trichloroethane	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
Benzene	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
trans-1,3-Dichloropropene	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
Bromoform	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
4-Methyl-2-Pentanone	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
2-Hexanone	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
1,1,2,2-Tetrachloroethane	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
Tetrachloroethene	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
Toluene	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
Chlorobenzene	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
Ethylbenzene	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
Styrene	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	ND	U	11
Xylenes (total)	ug/kg	ND	U	11	ND	UJ	11	ND	UJ	11	1	J	11
Total VOCs		1		0	0		0	0		1			

NOTE: \*\* indicates a value which was changed to 'Not Detected' following data validation

**TABLE L1.B**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**SURFACE SOIL SAMPLES**  
**SUMMARY OF SEMIVOLATILE ORGANIC COMPOUNDS**

Page 10 of 15

Sample Location=	FF-B141-121393 32184-01-SA 13 DEC 93			FF-B151-121393 32184-0003-SA 13 DEC 93			FF-B161-112393 081806-0011-SA 28 NOV 93		
Compound	Units	Sample Value	Reporting Limit	Sample Value	Qual	Reporting Limit	Sample Value	Qual	Reporting Limit
Acenaphthene	ug/kg	ND	U	390		ND	U	370	330
Acenaphthylene	ug/kg	ND	U	390		40	J	370	ND
Anthracene	ug/kg	ND	U	390		170	J	370	U
9H-Carbazole	ug/kg	ND	U	390		ND	U	370	720
Benz(a)anthracene	ug/kg	ND	U	390		440	J	370	240
Benz(a)pyrene	ug/kg	ND	U	390		240	J	370	2400
Benz(b)fluoranthene	ug/kg	ND	U	390		440	J	370	2600
Benzo(g,h,i)perylene	ug/kg	ND	U	390		120	J	370	3900
Benzo(k)fluoranthene	ug/kg	ND	U	390		ND	U	370	1400
4-Bromophenyl phenyl ether	ug/kg	ND	U	390		ND	U	370	ND
Butyl benzyl phthalate	ug/kg	ND	U	390		ND	U	370	ND
4-Chloroaniline	ug/kg	ND	U	390		ND	U	370	ND
bis(2-Chloroethoxy)-methane	ug/kg	ND	U	390		ND	U	370	ND
bis(2-Chloroethyl) ether	ug/kg	ND	U	390		ND	U	370	ND
bis(2-Chloroisopropyl) ether	ug/kg	ND	U	390		ND	U	370	ND
4-Chloro-3-methylphenol	ug/kg	ND	U	390		ND	U	370	ND
2-Chloronaphthalene	ug/kg	ND	U	390		ND	U	370	ND
2-Chlorophenol	ug/kg	ND	U	390		ND	U	370	ND
4-Chlorophenyl phenyl ether	ug/kg	ND	U	390		ND	U	370	ND
Chrysene	ug/kg	ND	U	390		390	J	370	2400
Di-n-butyl phthalate	ug/kg	ND	U	390		ND	U	370	ND
Dibenz(a,h)anthracene	ug/kg	ND	U	390		77	J	370	350
Dibenzofuran	ug/kg	ND	U	390		ND	U	370	ND
1,2-Dichlorobenzene	ug/kg	ND	U	390		ND	U	370	ND
1,3-Dichlorobenzene	ug/kg	ND	U	390		ND	U	370	ND
1,4-Dichlorobenzene	ug/kg	ND	U	390		ND	U	370	ND
3,3'-Dichlorobenzidine	ug/kg	ND	U	390		ND	U	370	ND
2,4-Dichlorophenol	ug/kg	ND	U	390		ND	U	370	ND
Diethyl phthalate	ug/kg	ND	U	390		ND	U	370	ND
2,4-Dimethylphenol	ug/kg	ND	U	390		ND	U	370	ND
Dimethyl phthalate	ug/kg	ND	U	390		ND	U	370	ND
4,6-Dinitro-2-methylphenol	ug/kg	ND	U	950		ND	U	900	ND
2,4-Dinitrophenol	ug/kg	ND	U	950		ND	U	900	ND
2,4-Dinitrotoluene	ug/kg	ND	U	390		ND	U	370	ND
2,6-Dinitrotoluene	ug/kg	ND	U	390		ND	U	370	ND
Di-n-octyl phthalate	ug/kg	ND	U	390		ND	U	370	ND
bis(2-Ethylhexyl) phthalate	ug/kg	ND	U	390		ND	U	370	ND
Fluoranthene	ug/kg	ND	U	390		740	J	370	3200
Fluorene	ug/kg	ND	U	390		ND	U	370	380
Hexachlorobenzene	ug/kg	ND	U	390		43	J	370	ND
Hexachlorobutadiene	ug/kg	ND	U	390		ND	U	370	ND
Hexachlorocyclo-pentadiene	ug/kg	ND	U	390		ND	U	370	ND
Hexachloroethane	ug/kg	ND	U	390		ND	U	370	ND
Indeno(1,2,3-cd)pyrene	ug/kg	ND	U	390		130	J	370	1100
Isophorone	ug/kg	ND	U	390		ND	U	370	ND
2-Methylnaphthalene	ug/kg	ND	U	390		ND	U	370	1400
2-Methylphenol	ug/kg	ND	U	390		ND	U	370	ND
4-Methylphenol	ug/kg	ND	U	390		ND	U	370	ND
Naphthalene	ug/kg	ND	U	390		ND	U	370	ND
2-Nitroaniline	ug/kg	ND	U	950		ND	U	900	ND
3-Nitroaniline	ug/kg	ND	U	950		ND	U	900	ND
4-Nitroaniline	ug/kg	ND	U	950		ND	U	900	ND
Nitrobenzene	ug/kg	ND	U	390		ND	U	370	ND
2-Nitrophenol	ug/kg	ND	U	390		ND	U	370	ND
4-Nitrophenol	ug/kg	ND	U	950		ND	U	900	ND
N-Nitrosodiphenylamine	ug/kg	ND	U	390		ND	U	370	ND
N-Nitroso-di-n-propylamine	ug/kg	ND	U	390		ND	U	370	ND
Pentachlorophenol	ug/kg	ND	U	950		ND	U	900	ND
Phenanthrene	ug/kg	ND	U	390		500	J	370	3300
Phenol	ug/kg	ND	U	390		ND	U	370	ND
Pyrene	ug/kg	ND	U	390		800	J	370	4600
1,2,4-Trichlorobenzene	ug/kg	ND	U	390		ND	U	370	ND
2,4,5-Trichlorophenol	ug/kg	ND	U	950		ND	U	900	ND
2,4,6-Trichlorophenol	ug/kg	ND	U	390		ND	U	370	ND
Total PAHs		0				4087			26770
Total Carcinogenic PAHs		0				1837			14050
Total SVOCs		0				4130			27010

NOTE: \*\* indicates a value which was changed to 'ND' following data validation.

**TABLE L1.B**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**SURFACE SOIL SAMPLES**  
**SUMMARY OF SEMIVOLATILE ORGANIC COMPOUNDS**

Sample Location	FF-B91-112293 031806-0005-SA 22 NOV 93			FF-B91-112393 031806-0008-SA 23 NOV 93			FF-B101-112393 031813-0008-SA 23 NOV 93			Page 8 of 15			
Compound	Units	Sample Value	Qual	Reporting Limit	Sample Value	Qual	Reporting Limit	Sample Value	Qual	Reporting Limit	Sample Value	Qual	Reporting Limit
Acenaphthene	ug/kg	92	J	380	62	J	380	ND	U	360			
Acenaphthylene	ug/kg	270	J	380	ND	U	380	ND	U	360			
Anthracene	ug/kg	320	J	380	130	J	380	68	J	360			
9H-Carbazole	ug/kg	61	J	380	68	J	380	ND	U	360			
Benz(a)anthracene	ug/kg	1400		380	350	J	380	240	J	360			
Benz(a)pyrene	ug/kg	1200		380	310	J	380	220	J	360			
Benz(b)fluoranthene	ug/kg	1700		380	540		380	440		360			
Benz(g,h,i)perylene	ug/kg	420		380	140	J	380	59	J	360			
Benz(k)fluoranthene	ug/kg	ND		380	ND	U	380	ND	U	360			
4-Bromophenyl phenyl ether	ug/kg	ND		380	ND	U	380	ND	U	360			
Butyl benzyl phthalate	ug/kg	ND		380	ND	U	380	ND	U	360			
4-Chloroaniline	ug/kg	ND		380	ND	U	380	ND	U	360			
bis(2-Chloroethoxy)-methane	ug/kg	ND		380	ND	U	380	ND	U	360			
bis(2-Chloroethyl) ether	ug/kg	ND		380	ND	U	380	ND	U	360			
bis(2-Chloroisopropyl) ether	ug/kg	ND		380	ND	U	380	ND	U	360			
4-Chloro-3-methylphenol	ug/kg	ND		380	ND	U	380	ND	U	360			
2-Chloronaphthalene	ug/kg	ND		380	ND	U	380	ND	U	360			
2-Chlorophenol	ug/kg	ND		380	ND	U	380	ND	U	360			
4-Chlorophenyl phenyl ether	ug/kg	ND		380	ND	U	380	ND	U	360			
Chrysene	ug/kg	1400		380	380		380	250		360			
Di-n-butyl phthalate	ug/kg	41	J	380	ND	U	380	140	J	360			
Dibenz(a,h)anthracene	ug/kg	270		380	59	J	380	43	J	360			
Dibenzofuran	ug/kg	130		380	46	J	380	ND	U	360			
1,2-Dichlorobenzene	ug/kg	ND		380	ND	U	380	ND	U	360			
1,3-Dichlorobenzene	ug/kg	ND		380	ND	U	380	ND	U	360			
1,4-Dichlorobenzene	ug/kg	ND		380	ND	U	380	ND	U	360			
3,3'-Dichlorobenzidine	ug/kg	ND		380	ND	U	380	ND	U	360			
2,4-Dichlorophenol	ug/kg	ND		380	ND	U	380	ND	U	360			
Diethyl phthalate	ug/kg	80	J	380	ND	U	380	ND	U	360			
2,4-Dimethylphenol	ug/kg	ND		380	ND	U	380	ND	U	360			
Dimethyl phthalate	ug/kg	ND		380	ND	U	380	ND	U	360			
4,6-Dinitro-2-methylphenol	ug/kg	ND		910	ND	U	910	ND	U	880			
2,4-Dinitrophenol	ug/kg	ND		910	ND	U	910	ND	U	880			
2,4-Dinitrotoluene	ug/kg	ND		380	ND	U	380	ND	U	360			
2,6-Dinitrotoluene	ug/kg	ND		380	ND	U	380	ND	U	360			
Di-n-octyl phthalate	ug/kg	ND		380	ND	U	380	ND	U	360			
bis(2-Ethylhexyl) phthalate	ug/kg	ND		380	ND	U	380	59	J	360			
Fluoranthene	ug/kg	2100		380	740		380	430		360			
Fluorene	ug/kg	190		380	75		380	ND	U	360			
Hexachlorobenzene	ug/kg	ND		380	ND	U	380	ND	U	360			
Hexachlorobutadiene	ug/kg	ND		380	ND	U	380	ND	U	360			
Hexachlorocyclo-pentadiene	ug/kg	ND		380	ND	U	380	ND	U	360			
Hexachloroethane	ug/kg	ND		380	ND	U	380	ND	U	360			
Indeno(1,2,3-cd)pyrene	ug/kg	560		380	170		380	100	J	360			
Isophorone	ug/kg	ND		380	ND	U	380	ND	U	360			
2-Methylnaphthalene	ug/kg	ND		380	45	J	380	ND	U	360			
2-Methylphenol	ug/kg	ND		380	ND	U	380	ND	U	360			
4-Methylphenol	ug/kg	ND		380	ND	U	380	ND	U	360			
Naphthalene	ug/kg	ND		380	39		380	ND	U	360			
2-Nitroaniline	ug/kg	ND		910	ND	U	910	ND	U	880			
3-Nitroaniline	ug/kg	ND		910	ND	U	910	ND	U	880			
4-Nitroaniline	ug/kg	ND		910	ND	U	910	ND	U	880			
Nitrobenzene	ug/kg	ND		380	ND	U	380	ND	U	360			
2-Nitrophenol	ug/kg	ND		380	ND	U	380	ND	U	360			
4-Nitrophenol	ug/kg	ND		910	ND	U	910	ND	U	880			
N-Nitrosodiphenylamine	ug/kg	ND		380	ND	U	380	ND	U	360			
N-Nitroso-di-n-propylamine	ug/kg	ND		380	ND	U	380	ND	U	360			
Pentachlorophenol	ug/kg	ND		910	ND	U	910	ND	U	880			
Phenanthrene	ug/kg	1600		380	640		380	210		360			
Phenol	ug/kg	ND	U	380	ND	U	380	ND	U	360			
Pyrene	ug/kg	2300		380	710		380	490		360			
1,2,4-Trichlorobenzene	ug/kg	ND		380	ND	U	380	ND	U	360			
2,4,5-Trichlorophenol	ug/kg	ND		910	ND	U	910	ND	U	880			
2,4,6-Trichlorophenol	ug/kg	ND		380	ND	U	380	ND	U	360			
Total PAHs		13822			4390			2550					
Total Carcinogenic PAHs		6950			1949			1352					
Total SVOCs		14134			4504			2749					

NOTE: " indicates a value which was changed to "ND" following data validation.

**TABLE L1.C**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**SURFACE SOIL SAMPLES**  
**SUMMARY OF PESTICIDE/PCB COMPOUNDS**

Sample Location=	FF-SS31-110493	Sample Designation=	FF-B81-112293	Sample Collection Date=	FF-B91-112393	Sample Designation=	FF-B101-112393
'Sample Designation=	031390-0012-SA	'Sample Collection Date=	031806-0005-SA	'Sample Collection Date=	031806-0008-SA	'Sample Designation=	031813-0008-SA
'Sample Collection Date=	04 NOV 93	'Sample Collection Date=	22 NOV 93	'Sample Collection Date=	23 NOV 93	'Sample Collection Date=	23 NOV 93
Compound	Units	Sample Value	Reporting Qual Limit	Sample Value	Reporting Qual Limit	Sample Value	Reporting Qual Limit
alpha-BHC	ug/kg	ND	UJ	2.0	ND	UJ	1.9
beta-BHC	ug/kg	ND	UJ	2.0	ND	UJ	1.9
delta-BHC	ug/kg	ND	UJ	2.0	ND	UJ	1.9
gamma-BHC (Lindane)	ug/kg	ND	UJ	2.0	ND	UJ	1.9
Heptachlor	ug/kg	ND	UJ	2.0	ND	UJ	1.9
Aldrin	ug/kg	ND	UJ	2.0	ND	UJ	1.9
Heptachlor epoxide	ug/kg	0.17	J	2.0	1.3	J	1.9
Endosulfan I	ug/kg	ND	UJ	2.0	ND	UJ	1.9
Dieldrin	ug/kg	ND	UJ*	4.0	3.5	J	3.8
4,4'-DDE	ug/kg	72	J	4.0	9.2	J	3.8
Endrin	ug/kg	ND	UJ	4.0	7.6	J	3.8
Endosulfan II	ug/kg	ND	UJ	4.0	1.6	J	3.8
4,4'-DDD	ug/kg	3.4	J	4.0	3.8	J	3.8
Endosulfan sulfate	ug/kg	ND	UJ	4.0	ND	UJ	3.8
4,4'-DDT	ug/kg	38	J	4.0	15	J	3.8
Methoxychlor	ug/kg	ND	UJ*	20	ND	UJ	19
Endrin ketone	ug/kg	ND	UJ	4.0	ND	UJ	3.8
Endrin aldehyde	ug/kg	ND	UJ*	4.0	ND	UJ	3.8
alpha-Chlordane	ug/kg	0.17	J	2.0	ND	UJ	1.9
gamma-Chlordane	ug/kg	ND	U	2.0	ND	UJ*	1.9
Toxaphene	ug/kg	ND	U	200	ND	UJ	190
Aroclor 1016	ug/kg	ND	U	40	ND	UJ	38
Aroclor 1221	ug/kg	ND	U	80	ND	UJ	77
Aroclor 1232	ug/kg	ND	U	40	ND	UJ	38
Aroclor 1242	ug/kg	ND	U	40	ND	UJ	38
Aroclor 1248	ug/kg	ND	U	40	ND	UJ	38
Aroclor 1254	ug/kg	ND	U	40	ND	UJ	38
Aroclor 1260	ug/kg	ND	U	40	ND	UJ	38

NOTE: '\*' indicates a value which was changed to 'ND' following data validation

**TABLE L1.C**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**SURFACE SOIL SAMPLES**  
**SUMMARY OF PESTICIDE/PCB COMPOUNDS**

Page 7 of 12

Sample Location=	FF-B111-112493 031813-0001-SA 24 NOV 93			FF-B121-112493 031813-0003-SA 24 NOV 93			FF-B131-112393 031806-0009-SA 23 NOV 93			FF-B141-121393 32184-0001-SA 13 DEC 93			
Compound	Units	Sample Value	Reporting Qual Limit	Sample Value	Reporting Qual Limit	Sample Value	Reporting Qual Limit	Sample Value	Reporting Qual Limit	Sample Value	Reporting Qual Limit		
alpha-BHC	ug/kg	ND	U	2.0	0.048	J	1.9	ND	UJ	3.8	ND	U	2.0
beta-BHC	ug/kg	ND	U	2.0	ND	UJ	1.9	ND	UJ	3.8	ND	U	2.0
delta-BHC	ug/kg	ND	U	2.0	ND	UJ	1.9	ND	UJ	3.8	ND	U	2.0
gamma-BHC (Lindane)	ug/kg	ND	UJ*	3.3	ND	UJ*	5.0	ND	UJ	3.8	0.24	J	2.0
Heptachlor	ug/kg	ND	U	2.0	ND	UJ	1.9	ND	UJ	3.8	0.27	J	2.0
Aldrin	ug/kg	ND	U	2.0	ND	UJ	1.9	ND	UJ	3.8	ND	U	2.0
Heptachlor epoxide	ug/kg	0.24	J	2.0	0.66	J	1.9	1.4	J	3.8	0.34	J	2.0
Endosulfan I	ug/kg	ND	U	2.0	ND	UJ	1.9	0.66	NJ	3.8	ND	U	2.0
Dieldrin	ug/kg	ND	UJ*	3.3	ND	UJ*	7.1	5.6	NJ	7.4	0.88	J	3.9
4,4'-DDE	ug/kg	6.5		3.8	0.41	J	3.7	ND	UJ*	7.4	20	J	3.9
Endrin	ug/kg	3.2	J	3.8	4.8	J	3.7	9.7	NJ	7.4	0.59	NJ	3.9
Endosulfan II	ug/kg	0.98	J	3.8	ND	UJ	3.7	7.3	NJ	7.4	0.72	J	3.9
4,4'-DDD	ug/kg	1.8	J	3.8	ND	UJ	3.7	ND	UJ	7.4	2.6	NJ	3.9
Endosulfan sulfate	ug/kg	ND	U	3.8	ND	UJ*	4.3	ND	UJ	7.4	ND	U	3.9
4,4'-DDT	ug/kg	11		3.8	7.2	J	3.7	ND	UJ	7.4	34	J	3.9
Methoxychlor	ug/kg	ND	U	20	5.4	J	19	ND	UJ*	54	ND	U	20
Endrin ketone	ug/kg	ND	U	3.8	ND	U	3.7	ND	UJ	7.4	ND	U	3.9
Endrin aldehyde	ug/kg	ND	UJ*	12	ND	UJ*	32	ND	UJ	7.4	1.4	NJ	3.9
alpha-Chlordane	ug/kg	0.61	J	2.0	ND	U	1.9	ND	UJ*	5.7	ND	U	2.0
gamma-Chlordane	ug/kg	0.29	J	2.0	ND	U	1.9	ND	UJ*	3.8	ND	U	2.0
Toxaphene	ug/kg	ND	U	200	ND	U	190	ND	UJ	380	ND	U	200
Aroclor 1016	ug/kg	ND	U	38	ND	U	37	ND	UJ	74	ND	U	39
Aroclor 1221	ug/kg	ND	U	78	ND	U	74	ND	UJ	150	ND	U	80
Aroclor 1232	ug/kg	ND	U	38	ND	U	37	ND	UJ	74	ND	U	39
Aroclor 1242	ug/kg	ND	U	38	ND	U	37	ND	UJ	74	ND	U	39
Aroclor 1248	ug/kg	ND	U	38	ND	U	37	ND	UJ	74	ND	U	39
Aroclor 1254	ug/kg	ND	U	38	ND	U	37	ND	UJ	74	ND	U	39
Aroclor 1260	ug/kg	ND	U	38	ND	U	37	ND	UJ	74	ND	U	39

NOTE: "\*" indicates a value which was changed to 'ND' following data validation

**TABLE L1.C**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**SURFACE SOIL SAMPLES**  
**SUMMARY OF PESTICIDE/PCB COMPOUNDS**

Page 8 of 12

Sample Location=	FF-B151-121393			FF-B161-112393			FF-B164-112393 (Dup of B161)			FF-B171-112493		
Sample Designation=	32184-0003-SA			031806-0011-SA			031806-0014-SA			031813-0005-SA		
Sample Collection Date=	13 DEC 93			23 NOV 93			23 NOV 93			24 NOV 93		
Compound	Units	Sample Value	Reporting Qual Limit	Sample Value	Reporting Qual Limit	Sample Value	Reporting Qual Limit	Sample Value	Reporting Qual Limit	Sample Value	Qual	Reporting Limit
alpha-BHC	ug/kg	ND	U 1.9	ND	UJ 9.2	ND	UJ 1.9	ND	U 1.9	ND	U	1.9
beta-BHC	ug/kg	ND	U 1.9	ND	UJ 9.2	ND	UJ 1.9	ND	U 1.9	ND	U	1.9
delta-BHC	ug/kg	ND	U 1.9	ND	UJ 9.2	ND	UJ 1.9	ND	U 1.9	ND	U	1.9
gamma-BHC (Lindane)	ug/kg	0.21	J 1.9	ND	UJ 9.2	ND	UJ 1.9	ND	UJ 1.9	ND	UJ*	4.7
Heptachlor	ug/kg	ND	U 1.9	ND	UJ 9.2	ND	UJ 1.9	ND	U 1.9	ND	U	1.9
Aldrin	ug/kg	ND	U 1.9	ND	UJ* 9.2	ND	UJ 1.9	ND	U 1.9	ND	U	1.9
Heptachlor epoxide	ug/kg	1.1	NJ 1.9	8.1	J 9.2	2	J 1.9	ND	UJ* 4.2	ND	UJ*	4.2
Endosulfan I	ug/kg	ND	U 1.9	9.4	J 9.2	2	J 1.9	ND	U 1.9	ND	U	1.9
Dieldrin	ug/kg	ND	UJ* 8.4	ND	UJ* 100	ND	UJ* 28	ND	U 3.7	ND	U	3.7
4,4'-DDE	ug/kg	3.3	J 3.7	ND	UJ 18	ND	UJ 3.7	1.5	J 3.7	ND	U	3.7
Endrin	ug/kg	13	J 3.7	74	J 18	25	J 3.7	ND	U 3.7	ND	U	3.7
Endosulfan II	ug/kg	3.6	J 3.7	25	NJ 18	6.5	J 3.7	ND	UJ* 3.7	ND	UJ*	3.7
4,4'-DDD	ug/kg	ND	U 3.7	17	J 18	4.7	J 3.7	ND	U 3.7	ND	U	3.7
Endosulfan sulfate	ug/kg	1.7	J 3.7	33	J 18	11	J 3.7	ND	U 3.7	ND	U	3.7
4,4'-DDT	ug/kg	ND	U* 28	ND	UJ 18	9.6	J 3.7	3.6	J 3.7	ND	U	3.7
Methoxychlor	ug/kg	ND	U 19	ND	UJ 9.2	ND	UJ 19	1.4	J 19	ND	U	19
Endrin ketone	ug/kg	ND	U 3.7	ND	UJ 18	ND	UJ 3.7	ND	U 3.7	ND	U	3.7
Endrin aldehyde	ug/kg	6.8	NJ 3.7	ND	UJ 18	ND	UJ 3.7	3.9	NJ 3.7	ND	U	3.7
alpha-Chlordane	ug/kg	ND	U* 1.9	ND	UJ 9.2	ND	UJ 1.9	ND	U 1.9	ND	U	1.9
gamma-Chlordane	ug/kg	ND	U* 1.9	3.5	J 9.2	ND	UJ 1.9	ND	U 1.9	ND	U	1.9
Toxaphene	ug/kg	ND	U 190	ND	UJ 920	ND	UJ 190	ND	U 190	ND	U	190
Aroclor 1016	ug/kg	ND	U 37	ND	UJ 180	ND	UJ 37	ND	U 37	ND	U	37
Aroclor 1221	ug/kg	ND	U 75	ND	UJ 360	ND	UJ 75	ND	U 75	ND	U	76
Aroclor 1232	ug/kg	ND	U 37	ND	UJ 180	ND	UJ 37	ND	U 37	ND	U	37
Aroclor 1242	ug/kg	ND	U 37	ND	UJ 180	ND	UJ 37	ND	U 37	ND	U	37
Aroclor 1248	ug/kg	ND	U 37	ND	UJ 180	ND	UJ 37	ND	U 37	ND	U	37
Aroclor 1254	ug/kg	ND	U 37	ND	UJ 180	ND	UJ 37	ND	U 37	ND	U	37
Aroclor 1260	ug/kg	ND	U 37	ND	UJ 180	ND	UJ 37	ND	U 37	ND	U	37

NOTE: "\*" indicates a value which was changed to 'ND' following data validation

**TABLE L1.D**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**SURFACE SOIL SAMPLES**  
**SUMMARY OF INORGANIC ANALYTES**

Page 6 of 12

Sample Location=		FF-SS31-110493 031390-0012-SA 04 NOV 93				FF-B81-112293 031806-0005-SA 22 NOV 93				FF-B91-112393 031806-0008-SA 23 NOV 93				FF-B101-112393 031813-0008-SA 23 NOV 93			
Analyte	Units	Sample Value	Qual	Reporting Limit	Sample Value	Qual	Reporting Limit	Sample Value	Qual	Reporting Limit	Sample Value	Qual	Reporting Limit	Sample Value	Qual	Reporting Limit	
Aluminum	mg/kg	10000		NA	10300		NA	11200		NA	9910		NA				
Antimony	mg/kg	6	UJ	NA	5.7	UJ	NA	5.6	UJ	NA	5.7	J	NA				
Arsenic	mg/kg	6.2	J	NA	6.3	J	NA	6	J	NA	5	J	NA				
Barium	mg/kg	27.2	B	NA	25.6	B	NA	29.9	B	NA	25.4	B	NA				
Beryllium	mg/kg	0.4	B	NA	0.33	B	NA	0.43	B	NA	0.39	B	NA				
Cadmium	mg/kg	0.72	U	NA	0.71	U	NA	0.7	U	NA	0.69	U	NA				
Calcium	mg/kg	668		NA	644	B	NA	1830		NA	1170		NA				
Chromium	mg/kg	11.6		NA	12.1		NA	13.2		NA	11.5		NA				
Cobalt	mg/kg	5.8	B	NA	6.7	B	NA	9.7	B	NA	6.5	B	NA				
Copper	mg/kg	17.2		NA	11.3		NA	19.8		NA	16.4		NA				
Iron	mg/kg	17300		NA	16500		NA	19800		NA	16800		NA				
Lead	mg/kg	133		NA	35.1	S	NA	68.7		NA	60.4		NA				
Magnesium	mg/kg	1900		NA	1930		NA	2390		NA	2120		NA				
Manganese	mg/kg	211		NA	233	J	NA	331	J	NA	221	J	NA				
Mercury	mg/kg	0.19		NA	0.06	U	NA	0.06	U	NA	0.07	B	NA				
Nickel	mg/kg	14.3		NA	12		NA	15.7		NA	15.4		NA				
Potassium	mg/kg	280	B	NA	446	B	NA	419	B	NA	402	B	NA				
Selenium	mg/kg	0.48	UW	NA	0.47	UW	NA	0.47	U	NA	0.46	U	NA				
Silver	mg/kg	0.96	U	NA	1.2	U	NA	1.2	U	NA	1.1	U	NA				
Sodium	mg/kg	289	U	NA	401	U	NA	396	U	NA	388	U	NA				
Thallium	mg/kg	0.48	U	NA	0.47	UJ	NA	0.47	UJ	NA	0.46	UJ	NA				
Vanadium	mg/kg	29.5		NA	18.3	J	NA	22.5		NA	41.2		NA				
Zinc	mg/kg	82		NA	42.8	UJ	NA	73.4	J	NA	65.1	J	NA				
Cyanide, Total	mg/kg	0.60	U	NA	0.59	U	NA	0.59	UJ	NA	0.57	UJ	NA				

**TABLE L1.D**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**SURFACE SOIL SAMPLES**  
**SUMMARY OF INORGANIC ANALYTES**

Sample Location=		FF-B111-112493 031813-0001-SA 24 NOV 93				FF-B121-112493 031813-0003-SA 24 NOV 93				FF-B131-112393 031806-0009-SA 23 NOV 93				FF-B141-121393 32184-01-SA 13 DEC 93			
Analyte	Units	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	
Aluminum	mg/kg	10500		NA	10500		NA	8380		NA	10700		NA				
Antimony	mg/kg	5.3	UJ	NA	5.3	UJ	NA	5.4	UJ	NA	5.9	UJ	NA				
Arsenic	mg/kg	6.6	J	NA	6.6	J	NA	10	J	NA	8.5						
Barium	mg/kg	25.9	B	NA	25.9	B	NA	32.4	B	NA	27.4	B	NA				
Beryllium	mg/kg	0.28	B	NA	0.28	B	NA	0.37	B	NA	0.35	B	NA				
Cadmium	mg/kg	0.66	U	NA	0.66	U	NA	0.67	U	NA	0.74	U	NA				
Calcium	mg/kg	1400	B	NA	1400		NA	4520		NA	937	B	NA				
Chromium	mg/kg	13.7		NA	13.7		NA	19.3		NA	11.8		NA				
Cobalt	mg/kg	10.8	B	NA	10.8	B	NA	10.6	B	NA	5.8	B	NA				
Copper	mg/kg	33.9		NA	33.9		NA	63.8		NA	9.1		NA				
Iron	mg/kg	23000		NA	23000		NA	31000		NA	15400		NA				
Lead	mg/kg	108		NA	108		NA	125		NA	22.5	S	NA				
Magnesium	mg/kg	3280		NA	3280		NA	3540		NA	1930		NA				
Manganese	mg/kg	439	J	NA	439	J	NA	325	J	NA	215	J	NA				
Mercury	mg/kg	0.080	B	NA	0.08	B	NA	0.14		NA	0.06	U	NA				
Nickel	mg/kg	18.3		NA	18.3		NA	20.8		NA	11.7		NA				
Potassium	mg/kg	382	B	NA	382	B	NA	443	B	NA	279	B	NA				
Selenium	mg/kg	0.47	U	NA	0.47	U	NA	0.58	B	NA	0.49	U	NA				
Silver	mg/kg	1.1	U	NA	1.1	U	NA	1.1	U	NA	1.2	U	NA				
Sodium	mg/kg	372	U	NA	372	U	NA	378	U	NA	415	U	NA				
Thallium	mg/kg	0.44	UJ	NA	0.44	UJ	NA	0.45	UJ	NA	0.49	UJ	NA				
Vanadium	mg/kg	19.0		NA	19		NA	21.9		NA	18.7		NA				
Zinc	mg/kg	104	J	NA	104	J	NA	168	J	NA	38	J	NA				
Cyanide, Total	mg/kg	0.55	UJ	NA	0.55	UJ	NA	0.56	UJ	NA	0.61	U	NA				

Page 7 of 12

**TABLE L1.D**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**SURFACE SOIL SAMPLES**  
**SUMMARY OF INORGANIC ANALYTES**

Page 8 of 12

Sample Location=		FF-B151-121393		FF-B161-112393		FF-B164-112393 (Dup of B161)		FF-B171-112493	
Sample Designation=		32184-0003-SA		031806-0011-SA		031806-0014-SA		031813-0005-SA	
Sample Collection Date=		13 DEC 93		23 NOV 93		23 NOV 93		24 NOV 93	
Analyte	Units	Sample Value	Reporting Qual Limit	Sample Value	Reporting Qual Limit	Sample Value	Reporting Qual Limit	Sample Value	Reporting Qual Limit
Aluminum	mg/kg	9540	NA	7080	NA	9580	NA	6270	NA
Antimony	mg/kg	5.1	UJ	5.2	UJ	6.5	J	5.1	UJ
Arsenic	mg/kg	7	NA	6.9	J	7.3	J	3.4	J
Barium	mg/kg	26.9	B	NA	46.5	NA	10.2	13.3	B
Beryllium	mg/kg	0.36	B	NA	0.22	B	0.4	0.23	B
Cadmium	mg/kg	0.72	B	NA	0.65	U	0.66	0.64	U
Calcium	mg/kg	1640	NA	1550	NA	849	B	732	B
Chromium	mg/kg	12.1	NA	28.4	NA	17.6	NA	7.2	NA
Cobalt	mg/kg	11.1	NA	7.4	B	14.9	NA	7	B
Copper	mg/kg	20.5	NA	87	NA	45.1	NA	11.6	NA
Iron	mg/kg	22700	NA	39200	NA	31400	NA	12700	NA
Lead	mg/kg	77.4	NA	126	NA	83.2	NA	23.6	S
Magnesium	mg/kg	2640	NA	3330	NA	3320	NA	2170	NA
Manganese	mg/kg	506	J	290	J	554	J	404	J
Mercury	mg/kg	0.05	U	NA	0.11	B	0.1	0.05	U
Nickel	mg/kg	19.5	NA	26.8	NA	19.1	NA	11	NA
Potassium	mg/kg	329	B	NA	1160	NA	339	330	B
Selenium	mg/kg	0.43	UW	NA	0.44	U	0.44	0.43	U
Silver	mg/kg	1.1	U	NA	1.1	U	1.1	1.1	U
Sodium	mg/kg	362	U	NA	368	U	372	362	U
Thallium	mg/kg	0.43	UJ	NA	0.44	UJ	0.44	0.43	UJ
Vanadium	mg/kg	19.3	NA	27.3	NA	16.4	NA	9	B
Zinc	mg/kg	89.3	J	NA	207	J	125	39.5	J
Cyanide, Total	mg/kg	0.54	U	NA	0.54	UJ	0.55	0.46	UJ

**TABLE L3.A**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**TEST PIT SOIL SAMPLES**  
**SUMMARY OF VOLATILE ORGANIC COMPOUNDS**

Page 1 of 3

Sample Location=	FF-TP11-011194	Sample Location=	FF-TP12-011194	Sample Location=	FF-TP13-011194	Sample Location=	FF-TP21-011194						
Sample Designation=	9401L245-001	Sample Designation=	9401L245-002	Sample Designation=	9401L245-003	Sample Designation=	9401L245-004						
Sample Collection Date=	11 JAN 94	Sample Collection Date=	11 JAN 94	Sample Collection Date=	11 JAN 94	Sample Collection Date=	11 JAN 94						
Compound	Units	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit
Diesel Scan	mg/kg	ND	U	749	Not Analyzed			Not Analyzed			Not Analyzed		
Chloromethane	ug/kg	ND	U	2400	ND	U	11	ND	U	11	ND	U	1400
Bromomethane	ug/kg	ND	U	2400	ND	U	11	ND	U	11	ND	U	1400
Vinyl Chloride	ug/kg	ND	U	2400	ND	U	11	ND	U	11	ND	U	1400
Chloroethane	ug/kg	ND	U	2400	ND	U	11	ND	U	11	ND	U	1400
Methylene chloride	ug/kg	ND	U*	2400	ND	U*	15	ND	U*	17	ND	U*	1700
Acetone	ug/kg	ND	U*	5100	ND	U*	29	ND	U*	29	ND	U	1400
Carbon disulfide	ug/kg	ND	U	2400	ND	U	11	ND	U	11	ND	U	1400
1,1-Dichloroethene	ug/kg	ND	U	2400	ND	U	11	ND	U	11	ND	U	1400
1,1-Dichloroethane	ug/kg	ND	U	2400	ND	U	11	ND	U	11	ND	U	1400
1,2-Dichloroethene (cis/trans)	ug/kg	ND	U	2400	ND	U	11	ND	U	11	ND	U	1400
Chloroform	ug/kg	ND	U	2400	ND	U	11	ND	U	11	ND	U	1400
1,2-Dichloroethane	ug/kg	ND	U	2400	ND	U	11	ND	U	11	ND	U	1400
2-Butanone	ug/kg	ND	U	2400	ND	U	11	ND	U	11	ND	U	1400
1,1,1-Trichloroethane	ug/kg	ND	U	2400	ND	U	11	ND	U	11	ND	U	1400
Carbon tetrachloride	ug/kg	ND	U	2400	ND	U	11	ND	U	11	ND	U	1400
Bromodichloromethane	ug/kg	ND	U	2400	ND	U	11	ND	U	11	ND	U	1400
1,2-Dichloropropane	ug/kg	ND	U	2400	ND	U	11	ND	U	11	ND	U	1400
cis-1,3-Dichloropropene	ug/kg	ND	U	2400	NO	U	11	NO	U	11	ND	U	1400
Trichloroethene	ug/kg	ND	U	2400	ND	U	11	ND	U	11	ND	U	1400
Dibromochloromethane	ug/kg	ND	U	2400	ND	U	11	ND	U	11	ND	U	1400
1,1,2-Trichloroethane	ug/kg	ND	U	2400	ND	U	11	ND	U	11	ND	U	1400
Benzene	ug/kg	ND	U	2400	ND	U	11	ND	U	11	ND	U	1400
trans-1,3-Dichloropropene	ug/kg	ND	U	2400	ND	U	11	ND	U	11	ND	U	1400
Bromoform	ug/kg	ND	U	2400	ND	U	11	ND	U	11	ND	U	1400
4-Methyl-2-Pentanone	ug/kg	ND	U	2400	ND	U	11	NO	U	11	ND	U	1400
2-Hexanone	ug/kg	ND	U	2400	ND	U	11	NO	U	11	ND	U	1400
1,1,2,2-Tetrachloroethane	ug/kg	ND	U	2400	ND	U	11	ND	U	11	ND	U	1400
Tetrachloroethene	ug/kg	ND	U	2400	ND	U	11	ND	U	11	ND	U	1400
Toluene	ug/kg	ND	U	2400	ND	U	11	2	U	11	ND	U	1400
Chlorobenzene	ug/kg	ND	U	2400	ND	U	11	ND	U	11	ND	U	1400
Ethylbenzene	ug/kg	ND	U	2400	ND	U	11	ND	U	11	ND	U	1400
Styrene	ug/kg	ND	U	2400	ND	U	11	ND	U	11	ND	U	1400
Xylenes (total)	ug/kg	ND	U	2400	ND	U	11	ND	U	11	ND	U	1400
Total VOCs		0			0			2			0		

NOTE: \*\* indicates a value which was changed to 'Not Detected' following data validation

**TABLE L3.A**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**TEST PIT SOIL SAMPLES**  
**SUMMARY OF VOLATILE ORGANIC COMPOUNDS**

Page 2 of 3

Sample Location=	FF-TP22-011194 9401L245-005 11-JAN 94			FF-TP23-011194 9401L245-006 11 JAN 94			FF-TP31-011194 9401L245-007 11 JAN 94			FF-TP32-011194 9401L245-008 11 JAN 94			
Compound	Units	Sample Value	Qual	Reporting Limit	Sample Value	Qual	Reporting Limit	Sample Value	Qual	Reporting Limit	Sample Value	Qual	Reporting Limit
Chloromethane	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
Bromomethane	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
Vinyl Chloride	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
Chloroethane	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
Methylene chloride	ug/kg	ND	U*	13	ND	U*	18	ND	U*	3800	ND	U*	17
Acetone	ug/kg	ND	U*	56	ND	U*	32	ND	U*	3500	ND	U*	29
Carbon disulfide	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
1,1-Dichloroethene	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
1,1-Dichloroethane	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
1,2-Dichloroethene (cis/trans)	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
Chloroform	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
1,2-Dichloroethane	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
2-Butanone	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
1,1,1-Trichloroethane	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
Carbon tetrachloride	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
Bromodichloromethane	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
1,2-Dichloropropane	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
cis-1,3-Dichloropropene	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
Trichloroethene	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
Dibromochloromethane	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
1,1,2-Trichloroethane	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
Benzene	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
trans-1,3-Dichloropropene	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
Bromoform	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
4-Methyl-2-Pentanone	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
2-Hexanone	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
1,1,2,2-Tetrachloroethane	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
Tetrachloroethene	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
Toluene	ug/kg	ND	U	12	ND	U	11	ND	U	1500	1	J	11
Chlorobenzene	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
Ethylbenzene	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
Styrene	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
Xylenes (total)	ug/kg	ND	U	12	ND	U	11	ND	U	1500	ND	U	11
Total VOCs		0			0			0			1		

NOTE: \*\* indicates a value which was changed to 'Not Detected' following data validation

**TABLE L3.A**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**TEST PIT SOIL SAMPLES**  
**SUMMARY OF VOLATILE ORGANIC COMPOUNDS**

Page 3 of 3

Sample Location=	FF-TP33-011194			FB-011194			TB-011294			
Sample Designation=	9401L245-009			9401L245-010			9401L245-011			
Sample Collection Date=	11 JAN 94			11 JAN 94			12 JAN 94			
Compound	Units	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit
Chloromethane	ug/kg	ND	U	11	ND	U	10	ND	U	10
Bromomethane	ug/kg	ND	U	11	ND	U	10	ND	U	10
Vinyl Chloride	ug/kg	ND	U	11	ND	U	10	ND	U	10
Chloroethane	ug/kg	ND	U	11	ND	U	10	ND	U	10
Methylene chloride	ug/kg	ND	U*	18	ND	U*	12	ND	U*	23
Acetone	ug/kg	ND	U*	32	ND	U*	12	ND	U*	10
Carbon disulfide	ug/kg	ND	U	11	ND	U	10	ND	U	10
1,1-Dichloroethene	ug/kg	ND	U	11	ND	U	10	ND	U	10
1,1-Dichloroethane	ug/kg	ND	U	11	ND	U	10	ND	U	10
1,2-Dichloroethene (cis/trans)	ug/kg	ND	U	11	ND	U	10	ND	U	10
Chloroform	ug/kg	ND	U	11	ND	U	10	ND	U	10
1,2-Dichloroethane	ug/kg	ND	U	11	ND	U	10	ND	U	10
2-Butanone	ug/kg	ND	U	11	ND	U	10	ND	U	10
1,1,1-Trichloroethane	ug/kg	ND	U	11	ND	U	10	ND	U	10
Carbon tetrachloride	ug/kg	ND	U	11	ND	U	10	ND	U	10
Bromodichloromethane	ug/kg	ND	U	11	ND	U	10	ND	U	10
1,2-Dichloropropane	ug/kg	ND	U	11	ND	U	10	ND	U	10
cis-1,3-Dichloropropene	ug/kg	ND	U	11	ND	U	10	ND	U	10
Trichloroethene	ug/kg	ND	U	11	ND	U	10	ND	U	10
Dibromochloromethane	ug/kg	ND	U	11	ND	U	10	ND	U	10
1,1,2-Trichloroethane	ug/kg	ND	U	11	ND	U	10	ND	U	10
Benzene	ug/kg	ND	U	11	ND	U	10	ND	U	10
trans-1,3-Dichloropropene	ug/kg	ND	U	11	ND	U	10	ND	U	10
Bromoform	ug/kg	ND	U	11	ND	U	10	ND	U	10
4-Methyl-2-Pentanone	ug/kg	ND	U	11	ND	U	10	ND	U	10
2-Hexanone	ug/kg	ND	U	11	ND	U	10	ND	U	10
1,1,2,2-Tetrachloroethane	ug/kg	ND	U	11	ND	U	10	ND	U	10
Tetrachloroethene	ug/kg	ND	U	11	ND	U	10	ND	U	10
Toluene	ug/kg	ND	U	11	ND	U	10	ND	U	10
Chlorobenzene	ug/kg	ND	U	11	ND	U	10	ND	U	10
Ethylbenzene	ug/kg	ND	U	11	ND	U	10	ND	U	10
Styrene	ug/kg	ND	U	11	ND	U	10	ND	U	10
Xylenes (total)	ug/kg	ND	U	11	ND	U	10	ND	U	10
Total VOCs		0			0			0		

NOTE: "\*" indicates a value which was changed to 'Not Detected' following data validation

**TABLE L3.B**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**TEST PIT SOIL SAMPLES**  
**SUMMARY OF SEMIVOLATILE ORGANIC COMPOUNDS**

Page 2 of 4

Sample Location	FF-TP21-011194 9401L245-004 11 JAN 94					FF-TP22-011194 9401L245-005 11 JAN 94					FF-TP23-011194 9401L245-056 11 JAN 94				
Compound	Units	Sample Value	Qual	Reporting Limit	Sample Value	Qual	Reporting Limit	Sample Value	Qual	Reporting Limit	Sample Value	Qual	Reporting Limit	Sample Value	Qual
Phenol	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
bis(2-Chloroethyl)ether	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
2-Chlorophenol	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
1,3-Dichlorobenzene	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
1,4-Dichlorobenzene	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
1,2-Dichlorobenzene	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
2-Methylphenol	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
2,2'-oxybis(1-Chloropropane)	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
4-Methylphenol	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
N-Nitroso-di-n-propylamine	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
Hexachloroethane	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
Nitrobenzene	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
Isophorone	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
2-Nitrophenol	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
2,4-Dimethylphenol	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
bis(2-Chloroethoxy)methane	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
2,4-Dichlorophenol	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
1,2,4-Trichlorobenzene	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
Naphthalene	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
4-Chloroaniline	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
Hexachlorobutadiene	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
4-Chloro-3-methylphenol	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
2-Methylnaphthalene	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
Hexachlorocyclopentadiene	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
2,4,6-Trichlorophenol	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
2,4,5-Trichlorophenol	ug/kg	ND	U	19000	ND	UJ	940	ND	UJ	900	ND	UJ	900	ND	UJ
2-Chloronaphthalene	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
2-Nitroaniline	ug/kg	ND	U	19000	ND	UJ	940	ND	UJ	900	ND	UJ	900	ND	UJ
Dimethylphthalate	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
Acenaphthylene	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
2,6-Dinitrotoluene	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
3-Nitroaniline	ug/kg	ND	U	19000	ND	UJ	940	ND	UJ	900	ND	UJ	900	ND	UJ
Acenaphthene	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
2,4-Dinitrophenol	ug/kg	ND	U	19000	ND	UJ	940	ND	UJ	900	ND	UJ	900	ND	UJ
4-Nitrophenol	ug/kg	ND	U	19000	ND	UJ	940	ND	UJ	900	ND	UJ	900	ND	UJ
Dibenzofuran	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
2,4-Dinitrotoluene	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
Diethylphthalate	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
4-Chlorophenyl-phenylether	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
Fluorene	ug/kg	1500	J	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
4-Nitroaniline	ug/kg	ND	U	19000	ND	UJ	940	ND	UJ	900	ND	UJ	900	ND	UJ
4,6-Dinitro-2-methylphenol	ug/kg	ND	U	19000	ND	UJ	940	ND	UJ	900	ND	UJ	900	ND	UJ
N-Nitrosodiphenylamine	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
4-Bromophenyl-phenylether	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
Hexachlorobenzene	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
Pentachlorophenol	ug/kg	ND	U	19000	ND	UJ	940	ND	UJ	900	ND	UJ	900	ND	UJ
Phenanthrene	ug/kg	850	J	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
Anthracene	ug/kg	440	J	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
Carbazole	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
Di-n-butylphthalate	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
Fluoranthene	ug/kg	460	J	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
Pyrene	ug/kg	1000	J	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
Butylbenzylphthalate	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
3,3'-Dichlorobenzidine	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
Benz(a)anthracene	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
Chrysene	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
bis(2-Ethylhexyl)phthalate	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
Di-n-octyl phthalate	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
Benz(b)fluoranthene	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
Benz(k)fluoranthene	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
Benz(a)pyrene	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
Indeno(1,2,3-cd)pyrene	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
Dibenzo(a,h)anthracene	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
Benzo(g,h,i)perylene	ug/kg	ND	U	7700	ND	UJ	380	ND	UJ	360	ND	UJ	360	ND	UJ
Total PAHs		4250					0				6160				
Total Carcinogenic PAHs		0					0				3000				
Total SVOCs		4250					0				6160				

NOTE: \* indicates a value which was changed to "ND" following data validation.

**TABLE L3.B**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**TEST PIT SOIL SAMPLES**  
**SUMMARY OF SEMIVOLATILE ORGANIC COMPOUNDS**

Page 3 of 4

Sample Location	FF-TP31-011194			FF-TP32-011194			FF-TP33-011194			
Sample Designation	9401L245-007			9401L245-008			9401L245-009			
Sample Collection Date	11 JAN 94			11 JAN 94			11 JAN 94			
Compound	Units	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit
Phenol	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
bis(2-Chloroethyl)ether	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
2-Chlorophenol	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
1,3-Dichlorobenzene	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
1,4-Dichlorobenzene	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
1,2-Dichlorobenzene	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
2-Methyphenol	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
2,2'-oxybis(1-Chloropropane)	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
4-Methylphenol	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
N-Nitroso-di-n-propylamine	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
Hexachloroethane	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
Nitrobenzene	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
Isophorone	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
2-Nitrophenol	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
2,4-Dimethylphenol	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
bis(2-Chloroethoxy)methane	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
2,4-Dichlorophenol	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
1,2,4-Trichlorobenzene	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
Naphthalene	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
4-Chloroaniline	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
Hexachlorobutadiene	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
4-Chloro-3-methylphenol	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
2-Methylnaphthalene	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
Hexachlorocyclopentadiene	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
2,4,5-Trichlorophenol	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
2,4,5-Trichlorophenol	ug/kg	ND	UJ	17000	ND	UJ	1800	ND	UJ	370
2-Chloronaphthalene	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
2-Nitroaniline	ug/kg	ND	UJ	17000	ND	UJ	1800	ND	UJ	930
Dimethylphthalate	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
Acenaphthylene	ug/kg	ND	UJ	6700	380	J	700	ND	UJ	370
2,6-Dinitrotoluene	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
3-Nitroaniline	ug/kg	ND	UJ	17000	ND	UJ	1800	ND	UJ	930
Acenaphthene	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
2,4-Dinitrophenol	ug/kg	ND	UJ	17000	ND	UJ	1800	ND	UJ	930
4-Nitrophenol	ug/kg	ND	UJ	17000	ND	UJ	1800	ND	UJ	930
Dibenzofuran	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
2,4-Dinitrotoluene	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
Diethylphthalate	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
4-Chlorophenyl-phenylether	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
Fluorene	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
4-Nitroaniline	ug/kg	ND	UJ	17000	ND	UJ	1800	ND	UJ	930
4,6-Dinitro-2-methylphenol	ug/kg	ND	UJ	17000	ND	UJ	1800	ND	UJ	930
N-Nitrosodiphenylamine	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
4-Bromophenyl-phenylether	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
Hexachlorobenzene	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
Pentachlorophenol	ug/kg	ND	UJ	17000	ND	UJ	1800	ND	UJ	930
Phenanthrene	ug/kg	6300	J	6700	1300	J	700	730	J	370
Anthracene	ug/kg	480	J	6700	520	J	700	200	J	370
Carbazole	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
Di-n-butylphthalate	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
Fluoranthene	ug/kg	ND	UJ	6700	3000	J	700	1200	J	370
Pyrene	ug/kg	ND	UJ	6700	3100	J	700	980	J	370
Butylbenzylphthalate	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
3,3'-Dichlorobenzidine	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
Benzo(a)anthracene	ug/kg	500	J	6700	2400	J	700	580	J	370
Chrysene	ug/kg	680	J	6700	2500	J	700	640	J	370
bis(2-Ethylhexyl)phthalate	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
Di-n-octyl phthalate	ug/kg	ND	UJ	6700	ND	UJ	700	ND	UJ	370
Benzo(b)fluoranthene	ug/kg	430	J	6700	2300	J	700	480	J	370
Benzo(k)fluoranthene	ug/kg	850	J	6700	2500	J	700	570	J	370
Benzo(a)pyrene	ug/kg	ND	UJ	6700	2900	J	700	630	J	370
Indeno(1,2,3-cc)pyrene	ug/kg	ND	UJ	6700	1700	J	700	400	J	370
Dibenz(a,h)anthracene	ug/kg	ND	UJ	6700	780	J	700	130	J	370
Benzo(g,h,i)perylene	ug/kg	ND	UJ	6700	1700	J	700	440	J	370
Total PAHs		9250			25080			6980		
Total Carcinogenic PAHs		2470			16780			3870		
Total SVOCs		9250			25080			5980		

NOTE: \* indicates a value which was changed to "ND" following data validation.

**TABLE L3.C**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**TEST PIT SOIL SAMPLES**  
**SUMMARY OF PESTICIDE/PCB COMPOUNDS**

Page 2 of 3

Sample Location=	FF-TP22-011194 9401L245-005 11 JAN 94				FF-TP23-011194 9401L245-006 11 JAN 94				FF-TP31-011194 9401L245-007 11 JAN 94				FF-TP32-011194 9401L245-008 11 JAN 94			
Compound	Units	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit
alpha-BHC	ug/kg	ND	UJ	1.8	ND	U	1.6	ND	UJ	2.0	ND	UJ	3.6			
beta-BHC	ug/kg	ND	UJ	1.8	ND	U	1.6	ND	UJ	2.0	ND	UJ	3.6			
delta-BHC	ug/kg	ND	UJ	1.8	ND	U	1.6	2.4	J	2.0	ND	UJ	3.6			
gamma-BHC (Lindane)	ug/kg	ND	UJ	1.8	ND	U	1.6	ND	UJ	2.0	ND	UJ	3.6			
Heptachlor	ug/kg	ND	UJ	1.8	ND	U	1.6	ND	UJ	2.0	ND	UJ	3.6			
Aldrin	ug/kg	ND	UJ	1.8	ND	U	1.6	ND	UJ	2.0	ND	UJ	3.6			
Heptachlor epoxide	ug/kg	ND	UJ	1.8	ND	U	1.6	ND	UJ	2.0	ND	UJ	3.6			
Endosulfan I	ug/kg	ND	UJ	1.8	ND	U	1.6	ND	UJ	2.0	ND	UJ	3.6			
Dieldrin	ug/kg	ND	UJ	3.6	ND	U	3.2	ND	UJ	3.9	ND	UJ	7.2			
4,4'-DDE	ug/kg	ND	UJ	3.6	ND	U	3.2	ND	UJ	3.9	ND	UJ	7.2			
Endrin	ug/kg	ND	UJ	3.6	ND	U	3.2	ND	UJ	3.9	ND	UJ	7.2			
Endosulfan II	ug/kg	ND	UJ	3.6	5.1	J	3.2	4.7	J	3.9	9.7	J	7.2			
4,4'-DDD	ug/kg	ND	UJ	3.6	ND	U	3.2	ND	UJ	3.9	ND	UJ	7.2			
Endosulfan sulfate	ug/kg	ND	UJ	3.6	ND	U	3.2	ND	UJ	3.9	ND	UJ	7.2			
4,4'-DDT	ug/kg	ND	UJ	3.6	ND	U	3.2	ND	UJ	3.9	ND	UJ	7.2			
Methoxychlor	ug/kg	ND	UJ	18	ND	U	16	ND	UJ	20	ND	UJ	36			
Endrin ketone	ug/kg	ND	UJ	3.6	ND	U	3.2	ND	UJ	3.9	ND	UJ	7.2			
Endrin aldehyde	ug/kg	ND	UJ	3.6	ND	U	3.2	ND	UJ	3.9	ND	UJ	7.2			
alpha-Chlordane	ug/kg	ND	UJ	1.8	ND	U	1.6	ND	UJ	2.0	ND	UJ	3.6			
gamma-Chlordane	ug/kg	ND	UJ	1.8	ND	U	1.6	ND	UJ	2.0	ND	UJ	3.6			
Toxaphene	ug/kg	ND	UJ	180	ND	U	160	ND	UJ	200	ND	UJ	360			
Aroclor 1016	ug/kg	ND	UJ	36	ND	U	32	ND	UJ	39	ND	UJ	72			
Aroclor 1221	ug/kg	ND	UJ	71	ND	U	64	ND	UJ	78	ND	UJ	140			
Aroclor 1232	ug/kg	ND	UJ	36	ND	U	32	ND	UJ	39	ND	UJ	72			
Aroclor 1242	ug/kg	ND	UJ	36	ND	U	32	ND	UJ	39	ND	UJ	72			
Aroclor 1248	ug/kg	ND	UJ	36	ND	U	32	ND	UJ	39	ND	UJ	72			
Aroclor 1254	ug/kg	ND	UJ	36	ND	U	32	ND	UJ	39	ND	UJ	72			
Aroclor 1260	ug/kg	ND	UJ	36	ND	U	32	ND	UJ	39	ND	UJ	72			

NOTE: \*\* indicates a value which was changed to 'ND' following data validation

**TABLE L3.C**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**TEST PIT SOIL SAMPLES**  
**SUMMARY OF PESTICIDE/PCB COMPOUNDS**

Page 3 of 3

Sample Location=	FF-TB33-011194			FB-011194			
Sample Designation=	9401L245-009			9401L245-010			
Sample Collection Date=	11 JAN 94			11 JAN 94			
Compound	Units	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit
alpha-BHC	ug/kg	ND	UJ	1.9	ND	UJ	0.052
beta-BHC	ug/kg	ND	UJ	1.9	ND	UJ	0.052
delta-BHC	ug/kg	ND	UJ	1.9	ND	UJ	0.052
gamma-BHC (Lindane)	ug/kg	ND	UJ	1.9	ND	UJ	0.052
Heptachlor	ug/kg	ND	UJ	1.9	ND	UJ	0.052
Aldrin	ug/kg	ND	UJ	1.9	ND	UJ	0.052
Heptachlor epoxide	ug/kg	ND	UJ	1.9	ND	UJ	0.052
Endosulfan I	ug/kg	ND	UJ	1.9	ND	UJ	0.052
Dieldrin	ug/kg	ND	UJ	3.7	ND	UJ	0.10
4,4'-DDE	ug/kg	ND	UJ	3.7	ND	UJ	0.10
Endrin	ug/kg	ND	UJ	3.7	ND	UJ	0.10
Endosulfan II	ug/kg	5.4	J	3.7	ND	UJ	0.10
4,4'-DDD	ug/kg	ND	UJ	3.7	ND	UJ	0.10
Endosulfan sulfate	ug/kg	ND	UJ	3.7	ND	UJ	0.10
4,4'-DDT	ug/kg	ND	UJ	3.7	ND	UJ	0.10
Methoxychlor	ug/kg	ND	UJ	19	ND	UJ	0.52
Endrin ketone	ug/kg	ND	UJ	3.7	ND	UJ	0.10
Endrin aldehyde	ug/kg	ND	UJ	3.7	ND	UJ	0.10
alpha-Chlordane	ug/kg	ND	UJ	1.9	ND	UJ	0.052
gamma-Chlordane	ug/kg	ND	UJ	1.9	ND	UJ	0.052
Toxaphene	ug/kg	ND	UJ	190	ND	UJ	5.2
Aroclor 1016	ug/kg	ND	UJ	37	ND	UJ	1.0
Aroclor 1221	ug/kg	ND	UJ	74	ND	UJ	2.1
Aroclor 1232	ug/kg	ND	UJ	37	ND	UJ	1.0
Aroclor 1242	ug/kg	ND	UJ	37	ND	UJ	1.0
Aroclor 1248	ug/kg	ND	UJ	37	ND	UJ	1.0
Aroclor 1254	ug/kg	ND	UJ	37	ND	UJ	1.0
Aroclor 1260	ug/kg	ND	UJ	37	ND	UJ	1.0

NOTE: " " indicates a value which was changed to 'ND' following data validation

**TABLE L3.D**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**TEST PIT SOIL SAMPLES**  
**SUMMARY OF INORGANIC ANALYTES**

Page 1 of 3

Sample Location=	FF-TP11-011194			FF-TP12-011194			FF-TP13-011194			FF-TP21-011194			
Sample Designation=	9401L245-001			9401L245-002			9401L245-003			9401L245-004			
Sample Collection Date=	11 JAN 94			11 JAN 94			11 JAN 94			11 JAN 94			
Analyte	Units	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Qual	Reporting Limit
Silver, Total	mg/kg	0.66	J	0.15	ND	UJ	0.091	ND	UJ	0.089	ND	UJ	0.092
Aluminum, Total	mg/kg	10900		5.8	8710		3.5	7970		3.2	5650		3.5
Arsenic, Total	mg/kg	9.5	J	0.77	4.1	J	0.45	2.6	J	0.45	3.7	J	0.46
Barium, Total	mg/kg	329		1.2	46.2	B	0.70	23.6	B	0.65	9.6	B	0.70
Beryllium, Total	mg/kg	1	B	0.39	0.28	B	0.23	0.37	B	0.22	ND	U	0.23
Calcium, Total	mg/kg	4930		7.0	4330		4.2	795	B	3.9	760	B	4.2
Cadmium, Total	mg/kg	11.5		0.31	0.25	J	0.091	ND	UJ	0.089	ND	UJ	0.092
Cobalt, Total	mg/kg	33.8		0.77	8.3	B	0.47	12.2		0.43	8	B	0.46
Chromium, Total	mg/kg	97.9	J	1.2	8.6	J	0.70	11.8	J	0.65	5.8	J	0.70
Copper, Total	mg/kg	544		0.77	23.3		0.47	16.1		0.43	16.9		0.46
Iron, Total	mg/kg	170000		2.3	17200		1.4	23000		1.3	16900		1.4
Mercury, Total	mg/kg	0.26		0.097	0.25		0.059	ND	U	0.056	ND	U	0.045
Potassium, Total	mg/kg	592	B	258	329	B	156	538	B	144	320	B	154
Magnesium, Total	mg/kg	3650		18.2	1840		11.0	2180		10.2	2040		10.9
Manganese, Total	mg/kg	692	J	1.2	255	J	0.70	186	J	0.65	243	J	0.70
Sodium, Total	mg/kg	196	B	10.4	89.2	B	6.3	97.9	B	5.8	87.3	B	6.3
Nickel, Total	mg/kg	145		3.5	13.7		2.1	28.1		1.9	16.3		2.1
Lead, Total	mg/kg	497	J	7.0	475	J	4.2	40.1	J	3.9	10.8	J	4.6
Antimony, Total	mg/kg	ND	U	10.4	ND	U	6.3	ND	U	5.8	ND	U	6.3
Selenium, Total	mg/kg	ND	UJ	0.77	0.59	J	0.45	ND	UJ	0.45	ND	UJ	0.46
Thallium, Total	mg/kg	ND	UJ	0.77	ND	UJ	4.5	ND	UJ	0.45	ND	UJ	0.46
Vanadium, Total	mg/kg	ND	U	1.5	16.5		0.94	7.1	B	0.87	11.1	B	0.93
Zinc, Total	mg/kg	4480		1.2	169		0.70	57.8		0.65	210		0.70
Cyanide, Total	mg/kg	ND	U	1.9	ND	U	1.2	ND	U	1.2	ND	U	1.2

NOTE: "ND" indicates a value which was changed to 'Not Detected' following data validation.

**TABLE L3.D**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**TEST PIT SOIL SAMPLES**  
**SUMMARY OF INORGANIC ANALYTES**

Page 2 of 3

Sample Location=		FF-TP22-011194				FF-TP23-011194				FF-TP31-011194				FF-TP32-011194				
Sample Designation=		9401L245-005				9401L245-006				9401L245-007				9401L245-008				
Sample Collection Date=		11 JAN 94				11 JAN 94				11 JAN 94				11 JAN 94				
Analyte	Units	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Limit
Silver, Total	mg/kg	ND	UJ	0.092	ND	UJ	0.084	ND	UJ	0.095	ND	UJ	0.089					
Aluminum, Total	mg/kg	12000		3.2	6620		3.3	3030		3.6	10300		3.3					
Arsenic, Total	mg/kg	4.3	J	0.46	2.1	J	0.42	16.3	J	1.9	2.9	J	0.45					
Barium, Total	mg/kg	18.2	B	0.65	13.2	B	0.65	200		0.72	22.1	B	0.66					
Beryllium, Total	mg/kg	0.37	B	0.22	0.24	B	0.22	ND	U	0.24	0.29	B	0.22					
Calcium, Total	mg/kg	884	B	3.9	4330		3.9	32300		4.3	1090	B	4.0					
Cadmium, Total	mg/kg	ND	UJ	0.092	ND	UJ	0.084	3.6		0.095	ND	UJ	0.089					
Cobalt, Total	mg/kg	10.4	B	0.43	8.6	B	0.44	2.9	B	0.48	11.8		0.44					
Chromium, Total	mg/kg	12.5	J	0.65	8.8	J	0.65	6.1	J	0.72	12.3	J	0.66					
Copper, Total	mg/kg	10.6		0.43	26.6		0.44	52.4		0.48	27.4		0.44					
Iron, Total	mg/kg	22100		1.3	15500		1.3	12300		1.4	24400		1.3					
Mercury, Total	mg/kg	ND	U	0.049	ND	U	0.055	0.16		0.060	0.076	B	0.046					
Potassium, Total	mg/kg	336	B	144	471	B	145	822	B	161	809	B	147					
Magnesium, Total	mg/kg	2570		10.2	2490		10.3	4630		11.3	3150		10.4					
Manganese, Total	mg/kg	139	J	0.65	273		0.65	299	J	0.72	413	J	0.66					
Sodium, Total	mg/kg	ND	U*	60.1	ND	U*	49.8	324	B	6.5	76	B	6.0					
Nickel, Total	mg/kg	17.7		1.9	11.8		2.0	4.3	B	2.2	18.7		2.0					
Lead, Total	mg/kg	6.9	J	4.6	65.6	J	3.9	3090	J	4.3	67.6	J	4.0					
Antimony, Total	mg/kg	ND	U	5.8	ND	U	5.9	6.7		6.5	ND	U	6.0					
Selenium, Total	mg/kg	ND	UJ	0.46	0.5	J	0.42	ND	UJ	0.48	ND	UJ	0.45					
Thallium, Total	mg/kg	ND	UJ	0.46	ND	UJ	0.42	ND	UJ	4.8	ND	UJ	0.45					
Vanadium, Total	mg/kg	7.4	B	0.86	ND	U*	4.6	ND	U*	6.9	7.7	B	0.88					
Zinc, Total	mg/kg	42.7		0.65	112		0.65	1580		0.72	76.3		0.66					
Cyanide, Total	mg/kg	ND	U	1.2	ND	U	1.1	ND	U	1.2	ND	U	1.1					

NOTE: "\*" indicates a value which was changed to 'Not Detected' following data validation.

**TABLE L3.D**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**TEST PIT SOIL SAMPLES**  
**SUMMARY OF INORGANIC ANALYTES**

Page 3 of 3

Sample Location=	FF-TP33-011194	FB-011194
Sample Designation=	9401L245-009	9401L245-010
Sample Collection Date=	11 JAN 94	11 JAN 94

Analyte	Units	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit
Silver, Total	mg/kg	ND	UJ	0.083	ND	U	0.0004
Aluminum, Total	mg/kg	8170		3.2	0.121	B	0.015
Arsenic, Total	mg/kg	2.9	J	0.42	ND	U	0.002
Barium, Total	mg/kg	21.7	B	0.65	0.0077	B	0.003
Beryllium, Total	mg/kg	0.37	B	0.22	ND	U	0.001
Calcium, Total	mg/kg	2600		3.9	ND	U*	0.179
Cadmium, Total	mg/kg	ND	UJ	0.083	ND	UJ	0.0004
Cobalt, Total	mg/kg	10.3	B	0.43	0.0022	B	0.002
Chromium, Total	mg/kg	9.7	J	0.65	ND	U	0.003
Copper, Total	mg/kg	25.6		0.43	ND	U	0.002
Iron, Total	mg/kg	19700		1.3	0.087	B	0.006
Mercury, Total	mg/kg	0.073	B	0.051	ND	U	0.0001
Potassium, Total	mg/kg	353	B	144	ND	U	0.666
Magnesium, Total	mg/kg	2350		10.2	0.275	B	0.047
Manganese, Total	mg/kg	310	J	0.65	ND	U	0.003
Sodium, Total	mg/kg	ND	U*	55.6	ND	U*	0.0532
Nickel, Total	mg/kg	15.3		1.9	ND	U	0.009
Lead, Total	mg/kg	76.6	J	3.9	ND	U	0.002
Antimony, Total	mg/kg	ND	U	5.8	ND	U	0.027
Selenium, Total	mg/kg	0.45	J	0.42	ND	U	0.002
Thallium, Total	mg/kg	ND	UJ	0.42	ND	U	0.002
Vanadium, Total	mg/kg	9.2	B	0.86	ND	U	0.004
Zinc, Total	mg/kg	102		0.65	ND	U*	0.0142
Cyanide, Total	mg/kg	ND	U	1.1	ND	U	0.01

NOTE: '\*' indicates a value which was changed to 'Not Detected' following data validation.

**TABLE L2.A**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**SUBSURFACE SOIL SAMPLES**  
**SUMMARY OF VOLATILE ORGANIC COMPOUNDS**

FF-B142-121393				FF-B152-121393				FF-B153-121393				FF-B162-112393				Page 2 of 6								
Sample Location=	32184-02-SA	Sample Designation=	32184-04-SA	Sample Collection Date=	13 DEC 93	Sample Depth=	15-17'	Sample Location=	32184-05-SA	Sample Designation=	32186-0012-SA	Sample Collection Date=	13 DEC 93	Sample Depth=	10-12'	Sample Location=	32186-0012-SA	Sample Designation=	32186-0012-SA	Sample Collection Date=	23 NOV 93	Sample Depth=	17-19'	2-1'
Compound	Units	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit					
Chloromethane	ug/kg	ND	U	13	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	11	ND	UJ	11					
Bromomethane	ug/kg	ND	U	13	ND	UJ	11	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	11					
Vinyl Chloride	ug/kg	ND	UJ	13	ND	U	11	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	11					
Chloroethane	ug/kg	1	J	13	ND	U	11	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	11					
Methylene chloride	ug/kg	ND	U	13	2	J	11	1	J	11	ND	UJ*	11	ND	UJ	11	ND	UJ	11					
Acetone	ug/kg	ND	U*	34	ND	U*	15	ND	UJ*	11	ND	UJ*	11	ND	UJ*	11	ND	UJ*	11					
Carbon disulfide	ug/kg	10	J	13	ND	U	11	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	11					
1,1-Dichloroethene	ug/kg	ND	U	13	ND	U	11	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	11					
1,1-Dichloroethane	ug/kg	ND	U	13	ND	U	11	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	11					
1,2-Dichloroethene (cis/trans)	ug/kg	ND	U	13	ND	U	11	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	11					
Chloroform	ug/kg	ND	U	13	ND	U	11	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	11					
1,2-Dichloroethane	ug/kg	ND	U	13	ND	U	11	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	11					
2-Butanone	ug/kg	ND	U*	13	ND	U*	11	ND	UJ*	11	ND	UJ*	11	ND	UJ	11	ND	UJ	11					
1,1,1-Trichloroethane	ug/kg	ND	U	13	ND	U	11	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	11					
Carbon tetrachloride	ug/kg	ND	U	13	ND	U	11	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	11					
Bromodichloromethane	ug/kg	ND	U	13	ND	U	11	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	11					
1,2-Dichloropropane	ug/kg	ND	U	13	ND	U	11	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	11					
cis-1,3-Dichloropropene	ug/kg	ND	U	13	ND	U	11	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	11					
Trichloroethene	ug/kg	ND	U	13	ND	U	11	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	11					
Dibromochloromethane	ug/kg	ND	U	13	ND	U	11	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	11					
1,1,2-Trichloroethane	ug/kg	ND	U	13	ND	U	11	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	11					
Benzene	ug/kg	ND	U	13	ND	U	11	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	11					
trans-1,3-Dichloropropene	ug/kg	ND	U	13	ND	U	11	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	11					
Bromoform	ug/kg	ND	U	13	ND	U	11	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	11					
4-Methyl-2-Pentanone	ug/kg	ND	U	13	NO	U	11	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	11					
2-Hexanone	ug/kg	ND	U	13	ND	U	11	ND	UJ	11	ND	UJ	11	ND	UJ	11	ND	UJ	11					
1,1,2-Tetrachloroethane	ug/kg	ND	U	13	ND	U	11	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	11					
Tetrachloroethene	ug/kg	ND	U	13	ND	U	11	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	11					
Toluene	ug/kg	2	J	13	2	J	11	ND	U	11	ND	U	11	5	J	11	ND	UJ	11					
Chlorobenzene	ug/kg	ND	U	13	ND	U	11	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	11					
Ethylbenzene	ug/kg	ND	U	13	ND	U	11	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	11					
Styrene	ug/kg	ND	U	13	ND	U	11	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	11					
Xylenes (total)	ug/kg	3	J	13	2	J	11	ND	U	11	ND	U	11	ND	UJ	11	ND	UJ	11					
Total VOCs		16			6			1			5			6										

NOTE: \*\* indicates a value which was changed to 'Not Detected' following data validation

**TABLE L2.B**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**SUBSURFACE SOIL SAMPLES**  
**SUMMARY OF SEMIVOLATILE ORGANIC COMPOUNDS**

Page 2 of 6

Sample Location	FF-B132-112393	FF-B142-121393	FF-B152-121393							
Sample Designation	031806-0010-SA	32184-02-SA	32184-04-SA							
Sample Collection Date	23 NOV 93	13 DEC 93	13 DEC 93							
Sample Depth	46'	15-17'	10-12'							
Compound	Units	Sample Value	Reporting Limit	Sample Value	Reporting Limit	Sample Value	Reporting Limit			
Acenaphthene	ug/kg	160	J	420	ND	U	780	230	J	730
Acenaphthylene	ug/kg	ND	U	420	ND	U	780	240	J	730
Anthracene	ug/kg	110	J	420	150	J	780	510	J	730
9H-Carbazole	ug/kg	ND	U	420	ND	U	780	130	J	730
Benzo(a)anthracene	ug/kg	360	J	420	410	J	780	1200	J	730
Benzo(a)pyrene	ug/kg	280	J	420	250	J	780	730	J	730
Benzo(b)fluoranthene	ug/kg	510	J	420	420	J	780	1300	J	730
Benzo(g,h,i)perylene	ug/kg	88	J	420	130	J	780	300	J	730
Benzo(k)fluoranthene	ug/kg	ND	U	420	ND	U	780	ND	U	730
4-Bromophenyl phenyl ether	ug/kg	ND	U	420	ND	U	780	ND	U	730
Butyl benzyl phthalate	ug/kg	ND	U	420	ND	U	780	ND	U	730
4-Chloroaniline	ug/kg	ND	U	420	ND	U	780	ND	U	730
bis(2-Chloroethoxy)-methane	ug/kg	ND	U	420	ND	U	780	ND	U	730
bis(2-Chloroethyl) ether	ug/kg	ND	U	420	ND	U	780	ND	U	730
bis(2-Chloroisopropyl) ether	ug/kg	ND	U	420	ND	U	780	ND	U	730
4-Chloro-3-methylphenol	ug/kg	ND	U	420	ND	U	780	ND	U	730
2-Chloronaphthalene	ug/kg	ND	U	420	ND	U	780	ND	U	730
2-Chlorophenol	ug/kg	ND	U	420	ND	U	780	ND	U	730
4-Chlorophenyl phenyl ether	ug/kg	ND	U	420	ND	U	780	ND	U	730
Chrysene	ug/kg	320	J	420	460	J	780	1100	J	730
Di-n-butyl phthalate	ug/kg	56	J	420	120	J	780	ND	U	730
Dibenz(a,h)anthracene	ug/kg	66	J	420	100	J	780	220	J	730
Dibenzofuran	ug/kg	86	J	420	ND	U	780	200	J	730
1,2-Dichlorobenzene	ug/kg	ND	U	420	ND	U	780	ND	U	730
1,3-Dichlorobenzene	ug/kg	ND	U	420	ND	U	780	ND	U	730
1,4-Dichlorobenzene	ug/kg	ND	U	420	ND	U	780	ND	U	730
3,3'-Dichlorobenzidine	ug/kg	ND	U	420	ND	U	780	ND	U	730
2,4-Dichlorophenol	ug/kg	ND	U	420	ND	U	780	ND	U	730
Diethyl phthalate	ug/kg	ND	U	420	ND	U	780	ND	U	730
2,4-Dimethylphenol	ug/kg	ND	U	420	ND	U	780	ND	U	730
Dimethyl phthalate	ug/kg	ND	U	420	ND	U	780	ND	U	730
4,6-Dinitro-2-methylphenol	ug/kg	ND	U	1000	ND	U	1900	320	J	1800
2,4-Dinitrophenol	ug/kg	ND	U	1000	ND	U	1900	ND	U	1800
2,4-Dinitrotoluene	ug/kg	ND	U	420	ND	U	780	ND	U	730
Di-n-octyl phthalate	ug/kg	ND	U	420	ND	U	780	ND	U	730
bis(2-Ethylhexyl) phthalate	ug/kg	ND	U	420	ND	U	780	ND	U	730
Fluoranthene	ug/kg	830	J	420	820	J	780	2200	J	730
Fluorene	ug/kg	140	J	420	ND	U	780	330	J	730
Hexachlorobenzene	ug/kg	ND	U	420	370	J	780	ND	U	730
Hexachlorobutadiene	ug/kg	ND	U	420	ND	U	780	ND	U	730
Hexachlorocyclo-pentadiene	ug/kg	ND	U	420	ND	U	780	ND	U	730
Hexachloroethane	ug/kg	ND	U	420	ND	U	780	ND	U	730
Indeno(1,2,3-cd)pyrene	ug/kg	120	J	420	140	J	780	360	J	730
Isophorone	ug/kg	ND	U	420	ND	U	780	ND	U	730
2-Methylnaphthalene	ug/kg	ND	U	420	ND	U	780	110	J	730
2-Methylphenol	ug/kg	ND	U	420	ND	U	780	ND	U	730
4-Methylphenol	ug/kg	ND	U	420	ND	U	780	ND	U	730
Naphthalene	ug/kg	ND	U	420	ND	U	780	84	J	730
2-Nitroaniline	ug/kg	ND	U	1000	ND	U	1900	ND	U	1800
3-Nitroaniline	ug/kg	ND	U	1000	ND	U	1900	ND	U	1800
4-Nitroaniline	ug/kg	ND	U	1000	ND	U	1900	ND	U	1800
Nitrobenzene	ug/kg	ND	U	420	ND	U	780	ND	U	730
2-Nitrophenol	ug/kg	ND	U	420	ND	U	780	ND	U	730
4-Nitrophenol	ug/kg	ND	U	1000	ND	U	1900	ND	U	1800
N-Nitrosodiphenylamine	ug/kg	ND	U	420	ND	U	780	ND	U	730
N-Nitroso-di-n-propylamine	ug/kg	ND	U	420	ND	U	780	ND	U	730
Pentachlorophenol	ug/kg	ND	U	1000	ND	U	1900	ND	U	1800
Phenanthrene	ug/kg	480	J	420	410	J	780	1600	J	730
Phenol	ug/kg	ND	U	420	ND	U	780	ND	U	730
Pyrene	ug/kg	660	J	420	790	J	780	1700	J	730
1,2,4-Trichlorobenzene	ug/kg	ND	U	420	ND	U	780	ND	U	730
2,4,5-Trichlorophenol	ug/kg	ND	U	1000	ND	U	1900	ND	U	1800
2,4,6-Trichlorophenol	ug/kg	ND	U	420	ND	U	780	ND	U	730
Total PAHs		1124		4080		12214				
Total Carcinogenic PAHs		1744		1910		5210				
Total SVOCs		4266		4570		12854				

NOTE: \* indicates a value which was changed to "ND" following data validation.

**TABLE L2.B**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**SUBSURFACE SOIL SAMPLES**  
**SUMMARY OF SEMI-VOLATILE ORGANIC COMPOUNDS**

Page 3 of 6

Sample Location	FF-B153-121393	Sample Location	FF-B162-112393	Sample Location	FF-B172-112493				
Sample Designation	32184-05-SA	Sample Designation	031806-0012-SA	Sample Designation	031813-0006-SA				
Sample Collection Date	13 DEC 93	Sample Collection Date	23 NOV 93	Sample Collection Date	24 NOV 93				
Sample Depth	17-19'	Sample Depth	2-4'	Sample Depth	2-4'				
Compound	Units	Sample Value	Reporting Qual	Sample Value	Reporting Qual	Sample Value	Reporting Qual	Sample Value	Reporting Limit
Acenaphthene	ug/kg	340	J	370	J	250	J	730	ND
Acenaphthylene	ug/kg	120	J	370	J	75	J	730	ND
Anthracene	ug/kg	570	J	370	J	480	J	730	ND
9H-Carbazole	ug/kg	220	J	370	J	120	J	730	ND
Benzo(a)anthracene	ug/kg	1300	J	370	J	1200	J	730	ND
Benzo(a)pyrene	ug/kg	760	J	370	J	1200	J	730	ND
Benzo(b)fluoranthene	ug/kg	1400	J	370	J	1900	J	730	47
Benzo(g,h,i)perylene	ug/kg	360	J	370	J	510	J	730	ND
Benzo(k)fluoranthene	ug/kg	ND	U	370	U	ND	U	730	ND
4-Bromophenyl phenyl ether	ug/kg	ND	U	370	U	ND	U	730	ND
Butyl benzyl phthalate	ug/kg	120	J	370	J	ND	J	730	ND
4-Chloroaniline	ug/kg	ND	U	370	U	ND	U	730	ND
bis(2-Chloroethoxy)-methane	ug/kg	ND	U	370	U	ND	U	730	ND
bis(2-Chloroethyl) ether	ug/kg	ND	U	370	U	ND	U	730	ND
bis(2-Chloroisopropyl) ether	ug/kg	ND	U	370	U	ND	U	730	ND
4-Chloro-3-methylphenol	ug/kg	ND	U	370	U	ND	U	730	ND
2-Chloronaphthalene	ug/kg	ND	U	370	U	ND	U	730	ND
2-Chlorophenol	ug/kg	ND	U	370	U	ND	U	730	ND
4-Chlorophenyl phenyl ether	ug/kg	ND	U	370	U	ND	U	730	ND
Chrysene	ug/kg	1100	J	370	J	1400	J	730	ND
Di-n-butyl phthalate	ug/kg	ND	U	370	U	ND	U	730	ND
Dibenz(a,h)anthracene	ug/kg	200	J	370	J	170	J	730	ND
Dibenzofuran	ug/kg	200	J	370	J	ND	J	730	ND
1,2-Dichlorobenzene	ug/kg	ND	U	370	U	ND	U	730	ND
-Dichlorobenzene	ug/kg	ND	U	370	U	ND	U	730	ND
-Dichlorobenzidine	ug/kg	ND	U	370	U	ND	U	730	ND
2,4-Dichlorophenol	ug/kg	ND	U	370	U	ND	U	730	ND
Diethyl phthalate	ug/kg	ND	U	370	U	ND	U	730	ND
2,4-Dimethylphenol	ug/kg	ND	U	370	U	ND	U	730	ND
Dimethyl phthalate	ug/kg	ND	U	370	U	ND	U	730	ND
4,6-Dinitro-2-methylphenol	ug/kg	ND	U	900	U	ND	R	1800	ND
2,4-Dinitrophenol	ug/kg	ND	U	900	U	ND	R	1800	ND
2,4-Dinitrotoluene	ug/kg	ND	U	370	U	ND	U	730	ND
2,6-Dinitrotoluene	ug/kg	ND	U	370	U	ND	U	730	ND
Di-n-octyl phthalate	ug/kg	ND	U	370	U	ND	U	730	ND
bis(2-Ethylhexyl) phthalate	ug/kg	ND	U	370	U	ND	U	730	56
Fluoranthene	ug/kg	2200	J	370	J	2100	J	730	39
Fluorene	ug/kg	370	J	370	J	260	J	730	ND
Hexachlorobenzene	ug/kg	ND	U	370	U	ND	U	730	ND
Hexachlorobutadiene	ug/kg	ND	U	370	U	ND	U	730	ND
Hexachlorocyclo-pentadiene	ug/kg	ND	U	370	U	ND	U	730	ND
Hexachloroethane	ug/kg	ND	U	370	U	ND	U	730	ND
Indeno(1,2,3-cd)pyrene	ug/kg	380	J	370	J	500	J	730	ND
Isophorone	ug/kg	ND	U	370	U	ND	U	730	ND
2-Methylnaphthalene	ug/kg	160	J	370	J	110	J	730	ND
2-Methylphenol	ug/kg	ND	U	370	U	ND	U	730	ND
4-Methylphenol	ug/kg	ND	U	370	U	ND	U	730	ND
Naphthalene	ug/kg	79	J	370	J	ND	J	730	ND
2-Nitroaniline	ug/kg	ND	U	900	U	ND	U	1800	ND
3-Nitroaniline	ug/kg	ND	U	900	U	ND	U	1800	ND
4-Nitroaniline	ug/kg	ND	U	900	U	ND	U	1800	ND
Nitrobenzene	ug/kg	ND	U	370	U	ND	U	730	ND
2-Nitrophenol	ug/kg	ND	U	370	U	ND	U	730	ND
4-Nitrophenol	ug/kg	ND	U	900	U	ND	U	1800	ND
N-Nitrosodiphenylamine	ug/kg	ND	U	370	U	ND	U	730	ND
N-Nitroso-di-n-propylamine	ug/kg	ND	U	370	U	ND	U	730	ND
Pentachlorophenol	ug/kg	ND	U	900	U	ND	R	1800	ND
Phenanthrene	ug/kg	1800	J	370	J	2200	J	730	38
Phenol	ug/kg	ND	U	370	U	ND	U	730	ND
Pyrene	ug/kg	1800	J	370	J	3000	J	730	70
1,2,4-Trichlorobenzene	ug/kg	ND	U	370	U	ND	U	730	ND
1,5-Trichlorophenol	ug/kg	ND	U	900	U	ND	R	1800	ND
-Trichlorophenol	ug/kg	ND	U	370	U	ND	R	730	ND
Total PAHs		12939			15358			194	
Total Carcinogenic PAHs		5500			5880			47	
Total SVOCs		13479			15478			250	

NOTE: \*\* indicates a value which was changed to 'ND' following data validation.

**TABLE L2.C**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**SUBSURFACE SOIL SAMPLES**  
**SUMMARY OF PESTICIDE/PCB COMPOUNDS**

Page 2 of 4

Sample Location=	FF-B142-121393 32184-02-SA 13 DEC 93 15-17'				FF-B152-121393 32184-04-SA 13 DEC 93 10-12'				FF-B153-121393 32184-05-SA 13 DEC 93 17-19'				FF-B162-112393 32186-12-SA 23 NOV 93 21'			
Compound	Units	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit	Sample Value	Reporting Qual	Limit
alpha-BHC	ug/kg	ND	U	2	ND	U	1.9	ND	U	1.9	ND	UJ	3.7			
beta-BHC	ug/kg	ND	U	2	ND	U	1.9	ND	U	1.9	ND	UJ	3.7			
delta-BHC	ug/kg	ND	U	2	ND	U	1.9	ND	U	1.9	ND	UJ	3.7			
gamma-BHC (Lindane)	ug/kg	0.28	J	2	ND	U	1.9	ND	U	1.9	ND	UJ	3.7			
Heptachlor	ug/kg	ND	U	2	ND	U	1.9	1.4	J	1.9	ND	UJ	3.7			
Aldrin	ug/kg	ND	U	2	ND	U	1.9	ND	U	1.9	ND	UJ	3.7			
Heptachlor epoxide	ug/kg	0.89	J	2	3.4	J	1.9	3.3	NJ	1.9	3.4	J	3.7			
Endosulfan I	ug/kg	ND	U	2	ND	U	1.9	4.3	NJ	1.9	4	J	3.7			
Dieldrin	ug/kg	1.5	NJ	3.9	ND	UJ*	30	ND	UJ*	21	ND	UJ*	47			
4,4'-DDE	ug/kg	4.4	J	3.9	ND	U*	1.9	7.2	J	3.7	ND	UJ	7.2			
Endrin	ug/kg	6.3	J	3.9	ND	UJ*	40	ND	U	3.7	43	J	7.2			
Endosulfan II	ug/kg	2.5	J	3.9	ND	U	3.7	ND	U	3.7	13	J	7.2			
4,4'-DDD	ug/kg	9.1	J	3.9	ND	U	3.7	10	J	3.7	9.3	J	7.2			
Endosulfan sulfate	ug/kg	1.1	NJ	3.9	ND	U	3.7	3.8	J	3.7	17	J	7.2			
4,4'-DDT	ug/kg	77	J	7.8	ND	U*	11	58	J	7.4	42	J	7.2			
Methoxychlor	ug/kg	ND	U	20	ND	U	19	ND	U	19	ND	UJ	37			
Endrin ketone	ug/kg	ND	U	3.9	ND	U	3.7	ND	U	3.7	ND	UJ	7.2			
Endrin aldehyde	ug/kg	2.2	UJ	3.9	ND	UJ*	73	14	J	3.7	ND	UJ	7.2			
alpha-Chlordane	ug/kg	1.3	U	2	ND	U	1.9	ND	U	1.9	ND	UJ	3.7			
gamma-Chlordane	ug/kg	ND	U	2	1.9	J	1.9	2.5	J	1.9	ND	UJ	3.7			
Toxaphene	ug/kg	ND	U	200	ND	U	190	ND	U	190	ND	UJ	370			
Aroclor 1016	ug/kg	ND	U	39	ND	U	37	ND	U	37	ND	UJ	72			
Aroclor 1221	ug/kg	ND	U	79	ND	U	74	ND	U	75	ND	UJ	150			
Aroclor 1232	ug/kg	ND	U	39	ND	U	37	ND	U	37	ND	UJ	72			
Aroclor 1242	ug/kg	ND	U	39	ND	U	37	ND	U	37	ND	UJ	72			
Aroclor 1248	ug/kg	ND	U	39	ND	U	37	ND	U	37	ND	UJ	72			
Aroclor 1254	ug/kg	ND	U	39	ND	U	37	190	J	33	ND	UJ	72			
Aroclor 1260	ug/kg	ND	U	39	ND	U	37	ND	U	37	ND	UJ	72			

NOTE: \* indicates a value which was changed to 'ND' following data validation

**TABLE L2.D**  
**NETC NEWPORT - PHASE II RI**  
**SITE 09 - OLD FIRE FIGHTING TRAINING AREA**  
**SUBSURFACE SOIL SAMPLES**  
**SUMMARY OF INORGANIC ANALYTES**

Page 2 of 4

Sample Location	FF-B142-121393				Sample Location	FF-B152-121393				Sample Location	FF-B153-121393				Sample Location	RF-B162-112393			
Sample Designation	32184-02-SA				Sample Designation	32184-04-SA				Sample Designation	32184-05-SA				Sample Designation	031806-0012-SA			
Sample Collection Date	13 DEC 93				Sample Collection Date	13 DEC 93				Sample Collection Date	13 DEC 93				Sample Collection Date	23 NOV 93			
Sample Depth	15-17'				Sample Depth	10-12'				Sample Depth	17-19'				Sample Depth	2-4'			
Analyte	Units	Sample Value	Qual	Reporting Limit	Analyte	Units	Sample Value	Qual	Reporting Limit	Analyte	Units	Sample Value	Qual	Reporting Limit	Analyte	Units	Sample Value	Qual	Reporting Limit
Aluminum	mg/kg	7490		NA	Arsenic	mg/kg	9660		NA	Boron	mg/kg	8620		NA	Cadmium	mg/kg	9020		NA
Antimony	mg/kg	5.6	UJ	NA	Barium	mg/kg	5.3	UJ	NA	Beryllium	mg/kg	5.7	J	NA	Chromium	mg/kg	6.8	J	NA
Arsenic	mg/kg	9.2		NA	Barium	mg/kg	5.3		NA	Beryllium	mg/kg	5.5		NA	Cadmium	mg/kg	5.8	J	NA
Barium	mg/kg	25.7	B	NA	Beryllium	mg/kg	25.3	B	NA	Cadmium	mg/kg	28.9	B	NA	Chromium	mg/kg	23.1	B	NA
Beryllium	mg/kg	0.28	B	NA	Cadmium	mg/kg	0.33	B	NA	Chromium	mg/kg	0.36	B	NA	Cobalt	mg/kg	0.22	U	NA
Cadmium	mg/kg	0.86	B	NA	Chromium	mg/kg	0.86	B	NA	Cobalt	mg/kg	0.77	B	NA	Copper	mg/kg	0.66	U	NA
Calcium	mg/kg	6250		NA	Cobalt	mg/kg	4550		NA	Copper	mg/kg	11400		NA	Iron	mg/kg	2250		NA
Chromium	mg/kg	17.6		NA	Copper	mg/kg	11.9		NA	Iron	mg/kg	17.2		NA	Lead	mg/kg	24		NA
Cobalt	mg/kg	5.9	B	NA	Iron	mg/kg	23.8		NA	Lead	mg/kg	8.1	B	NA	Magnesium	mg/kg	9.7	B	NA
Copper	mg/kg	35.2		NA	Lead	mg/kg	21000		NA	Magnesium	mg/kg	48.2		NA	Manganese	mg/kg	83.4		NA
Iron	mg/kg	19900		NA	Manganese	mg/kg	86.4		NA	Manganese	mg/kg	24700		NA	Manganese	mg/kg	39700		NA
Lead	mg/kg	252		NA	Manganese	mg/kg	3000		NA	Manganese	mg/kg	292		NA	Manganese	mg/kg	92.9		NA
Magnesium	mg/kg	3990		NA	Manganese	mg/kg	291	J	NA	Manganese	mg/kg	3940		NA	Manganese	mg/kg	3380		NA
Manganese	mg/kg	259	J	NA	Manganese	mg/kg	0.07	B	NA	Manganese	mg/kg	419	J	NA	Manganese	mg/kg	303	J	NA
Mercury	mg/kg	0.16		NA	Manganese	mg/kg	0.17	B	NA	Manganese	mg/kg	0.17		NA	Nickel	mg/kg	0.1	B	NA
Nickel	mg/kg	15		NA	Nickel	mg/kg	17.2		NA	Nickel	mg/kg	19.2		NA	Potassium	mg/kg	32.9		NA
Potassium	mg/kg	1010	B	NA	Potassium	mg/kg	470	B	NA	Potassium	mg/kg	1030	B	NA	Selenium	mg/kg	588	B	NA
Selenium	mg/kg	0.51	J	NA	Selenium	mg/kg	0.44	U	NA	Selenium	mg/kg	0.45	U	NA	Silver	mg/kg	0.44	U	NA
Silver	mg/kg	1.2	U	NA	Silver	mg/kg	1.1	U	NA	Silver	mg/kg	1.1	U	NA	Sodium	mg/kg	1.1	U	NA
Sodium	mg/kg	682	B	NA	Sodium	mg/kg	373	U	NA	Sodium	mg/kg	571	B	NA	Thallium	mg/kg	373	U	NA
Thallium	mg/kg	0.47	UJ	NA	Thallium	mg/kg	0.44	UJ	NA	Thallium	mg/kg	0.45	UJ	NA	Vanadium	mg/kg	0.44	UJ	NA
Vanadium	mg/kg	19		NA	Vanadium	mg/kg	19.2		NA	Vanadium	mg/kg	19.3		NA	Zinc	mg/kg	19.8		NA
Zinc	mg/kg	97.7	J	NA	Zinc	mg/kg	121	J	NA	Zinc	mg/kg	156	J	NA	Zinc	mg/kg	123	J	NA
Cyanide, Total	mg/kg	0.58	U	NA	Cyanide, Total	mg/kg	0.55	U	NA	Cyanide, Total	mg/kg	0.56	U	NA	Cyanide, Total	mg/kg	0.55	UJ	NA

**PDI Soil Sample Analytical Results**

**Sample ID**

SB-406-0002

SB-407-0002

SB-407-0204

SB-411-0204

SB-411-0608

SB-411-1012

SB-411-1416

SB-412-0204

SB-412-0608

SB-412-1012

SB-415-0002

SB-415-0608

SB-416-0002

SB-418-0002

SB-433-0204

SB-433-0608

SB-411-2022

SB-415-0204

SB-416-0406

*Ree Carrasco*

**ANALYTICAL RESULTS**  
**OFFTA PDI SITE 09**  
**NEWPORT, RHODE ISLAND**

Sample Number		OFF-SB-406-0002	OFF-SB-407-0002	OFF-SB-407-0204	OFF-SB-411-0204	OFF-SB-411-0608	OFF-SB-411-1012	OFF-SB-411-1416	OFF-SB-412-0204	
Sample Location		406	407	407	411	411	411	411	412	
Date Sampled		12/3/2003	12/1/2003	12/1/2003	11/24/2003	11/24/2003	11/24/2003	11/24/2003	11/25/2003	
Interval		0.0-2.0	0.0-2.0	2.0-4.0	2.0-4.0	6.0-8.0	10.0-12.0	14.0-16.0	2.0-4.0	
QC Identifier	Soil Direct Exposure Residential	None	Field Dup. OFF-SB-412 0204							
<b>Volatile Organic Analysis (UG/KG)</b>										
1,1-Dichloroethane	920000	8 U	6 U	5 U	9 U	6 U	5 U	1 J	6 U	
2-Butanone	10000000	8 U	6 U	5 U	10 U	7 U	5 U	8	6	
2-Hexanone		8 U	6 U	5 U	9 U	6 U	5 U	6 U	6 U	
Acetone	7800000	39 B	18	15	240 J*	960 *	260	240 J*	480	
Benzene	2500	8 U	6 U	5 U	9 U	6 U	5 U	6 U	6 U	
Methylene Chloride	45000	14	11	7	21	9	8	12	18	
Tetrachloroethene	12000	8 U	6 U	5 U	9 U	6 U	5 U	6 U	6 U	
Toluene	190000	8 U	6 U	5 U	9 U	6 U	5 U	6 U	6 U	
Total Xylenes	110000	8 U	6 U	5 U	4 J	6 U	1 J	6 U	6 U	
Trichloroethene	13000	8 U	6 U	5 U	9 U	6 U	5 U	6 U	6 U	
Trichlorofluoromethane		8 U	6 U	5 U	9 U	6 U	5 U	6 U	6 U	
<b>Semivolatile Organic Analysis (UG/KG)</b>										
2-Methylnaphthalene	123000	410 U	1800 U	1800 U	42 J	52 J	170 J	1900 U	410 U	
Acenaphthene	43000	83 J	1800 U	1800 U	36 J	76 J	110 J	330 J	410 U	
Acenaphthylene	23000	69 J	1800 U	1800 U	91 J	77 J	120 J	330 J	410 U	
Anthracene	35000	190 J	270 J	290 J	170 J	190 J	380 J	1300 J	410 U	
Benzaldehyde		71 J	1800 U	1800 U	360 U	380 U	370 U	1900 U	410 U	
Benz(a)anthracene	900	600	1000 J	1000 J	480	520	930	3600	43 J	
Benz(a)pyrene	400	460	860 J	1000 J	410	270 J	610	2900	410 U	
Benz(b)fluoranthene	900	510	1100 J	1400 J	460	520	1100	3300	42 J	
Benz(g,h,i)perylene	800	63 J	380 J	380 J	290 J	290 J	670	1700 J	410 U	
Benz(k)fluoranthene	900	280 J	570 J	520 J	190 J	190 J	410	1400 J	410 U	
bis(2-Ethylhexyl)phthalate	46000	68 J	1800 U	1800 U	38 J	820	140 J	1900 U	200 J	
Butylbenzylphthalate		120 J	1800 U	1800 U	360 U	380 U	370 U	1900 U	410 U	
Carbazole		130 J	1800 U	1800 U	40 J	67 J	96 J	470 J	410 U	
Chrysene	400	510	930 J	960 J	480	490	970	3300	45 J	
Dibenz(a,h)anthracene	400	60 J	1800 U	1800 U	82 J	82 J	160 J	600 J	410 U	
Dibenzofuran		45 J	1800 U	1800 U	360 U	48 J	91 J	1900 U	410 U	
Fluoranthene	20000	990	1700 J	1700 J	690	870	1800	7900	66 J	
Fluorene	28000	84 J	1800 U	1800 U	38 J	64 J	120 J	520 J	410 U	
Indeno(1,2,3-cd)pyrene	900	230 J	330 J	330 J	260 J	240 J	540	1500 J	410 U	
Naphthalene	54000	410 U	1800 U	1800 U	360 U	54 J	130 J	210 J	410 U	
Phenanthrene	40000	740	1300 J	1400 J	460	670	1400	5600	410 U	
Pyrene	13000	990	2200	2500	900	960	1900	7400	75 J	
<b>Pesticide/PCB Analysis (UG/KG)</b>										
4,4'-DDD	4.0	U	3.6 U	3.6 U	3.6 U	0.64 JP	3.6 U	7.9 P	1.2 JP	
4,4'-DDE	4.0	U	3.6 U	3.6 U	3.6 U	1.6 JP	3.6 U	5.3 P	11 P	
4,4'-DDT	4.0	U	5.0 P	11 P	3.6 U	1.1 JP	3.6 U	3.8 U	6.6	
alpha-Chlordane	2.1	U	1.8 U	1.9 U	2.1 U					
Aroclor-1254	40	U	36 U	36 U	36 U	38 U	36 U	400	41 U	
Aroclor-1260		40 U	36 U	53 P	36 U	38 U	36 U	38 U	41 U	
beta-BHC	2.1	U	1.8 U	1.9 U	2.1 U					
Endrin Ketone	4.0	U	3.6 U	3.6 U	3.6 U	3.8 U	3.6 U	8.0 P	4.1 U	
gamma-Chlordane	2.1	U	1.8 U	1.9 U	1.9 U	1.9 U	1.9 U	6.5 P	2.1 U	
<b>TAL Metal Analysis (MG/KG)</b>										
Aluminum	12100	12300	*	10900 *	9820	12200	11300	9680	13200	
Antimony	10	7.0 N	0.84 BN*	1.1 N*	7.8 N	9.6 N	7.4 N	8.2 N	6.6 N	
Arsenic	1.7	6.7	5.8	6.9	7.8	12.8	6.6	9.5	11.5	
Barium	5500	49.3	60.6	43.3	26.9	36.1	40.1	40.9	35.9	
Beryllium	0.4	0.56	0.27	0.19 B*	0.36	0.54	0.50	0.46	0.54	
Cadmium	39	0.035 U	0.38	0.48	0.16 B	0.26	0.29	0.50	0.016 U	
Calcium	1790	1800	*	10600 *	3610	3490	14900	13000	1660	
Chromium	1400	16.2	13.2	14.9	13.2	17.2	14.3	24.7	15.8	
Cobalt		8.6 E	11.5	9.2	9.1	9.2	7.8	8.6	7.0	
Copper	3100	29.1	67.3 N*	29.0 N*	35.5	37.7	59.3	54.3	15.7	
Iron		23900	29900	*	40000 *	25700	29800	24800	25700	21800
Lead	150	266 E	217	192	63.4	88.8	143	559	31.1	
Magnesium		3260	3550	*	3460 *	3330	3420	3500	4000	2380
Manganese	390	450 E	445	424	491	557	424	234	321	
Mercury	23	0.076	0.027 B	0.043	0.039	0.16	0.14	0.28	0.063	
Nickel	1000	21.4 E	20.2	20.0	16.8	18.7	17.0	19.3	14.4	
Potassium		560	341	331	503	434	617	873	378	
Selenium	390	2.6	0.14 UN	0.16 UN	0.23 U	0.27 U	0.25 U	0.27 U	0.27 U	
Silver	200	0.049 U	2.5	2.9	0.033 U	0.037 U	0.036 U	0.038 U	0.038 U	
Sodium		65.7	83.4	103	48.6	70.7	234	560	76.9	
Thallium	55	2.6	0.090 UN	0.11 UN	3.4	4.2	3.5	3.1	2.6	
Vanadium	550	38.1	31.6	57.7	21.8	34.0	17.3	22.1	19.9	
Zinc	6000	207	139	*	190	111 E	119 E	130 E	147 E	63.4 E

Black Background = Criteria Exceeded; U - Not detected; UJ - Detection limit approximate; J - Quantitation approximate;  
R - Rejected; NA - Not Analyzed

**ANALYTICAL RESULTS**  
**OFTA PDI SITE 09**  
**NEWPORT, RHODE ISLAND**

Sample Number		OFF-SB-DUP07	OFF-SB-412 0608	OFF-SB-412 1012	OFF-SB-415 0002	OFF-SB-DUP03	OFF-SB-415 0204	OFF-SB-415 0002	OFF-SB-416 0002	OFF-SB-418-0002
Sample Location		412	412	412	415	415	415	416	418	
Date Sampled		11/25/2003	11/25/2003	11/25/2003	11/18/2003	11/18/2003	11/19/2003	11/19/2003	12/3/2003	
Interval		2.0-4.0	6.0-8.0	10.0-12.0	0.0-2.0	0.0-2.0	2.0-4.0	0.0-2.0	0.0-2.0	
QC Identifier		Soil Direct Exposure Residential	Field Dup. OFF-SB-412 0204	None	None	Field Dup. OFF-SB-415 0002	Field Dup. OFF-SB-415 0002	None	None	None
<b>Volatile Organic Analysis (UG/KG)</b>										
1,1-Dichloroethane	920000	6	U	NA	6	U	6	U	7	U
2-Butanone	10000000	5	J	NA	13		6	U	7	U
2-Hexanone		6	U	NA	6	U	1	J	6	U
Acetone	7800000	580	*	NA	3600	*	230		450	
Benzene	2500	6	U	NA	4	J	6	U	6	U
Methylene Chloride	45000	17		NA	14		19		13	
Tetrachloroethene	12000	6	U	NA	6	U	6	U	2	J
Toluene	190000	6	U	NA	3	J	6	U	6	U
Total Xylenes	110000	6	U	NA	6	U	6	U	6	U
Trichloroethene	13000	6	U	NA	6	U	6	U	2	J
Trichlorofluoromethane		6	U	NA	6	U	6	J	7	U
									7	U
									7	U
<b>Semivolatile Organic Analysis (UG/KG)</b>										
2-Methylnaphthalene	123000	410	U	NA	130	J	390	U	39	J
Acenaphthene	43000	410	U	NA	100	J	42	J	400	U
Acenaphthylene	23000	410	U	NA	84	J	89	J	110	J
Anthracene	35000	410	U	NA	410		160	J	140	J
Benzaldehyde		410	U	NA	370	U	390	U	390	U
Benzo(a)anthracene	900	42	J	NA	740		480		470	
Benzo(a)pyrene	400	410	U	NA	590		420		440	
Benzo(b)fluoranthene	900	51	J	NA	720		540		580	
Benzo(g,h,i)perylene	800	410	U	NA	450		300	J	310	J
Benzo(k)fluoranthene	900	410	U	NA	310	J	210	J	190	J
bis(2-Ethylhexyl)phthalate	48000	280	J	NA	610		41	J	390	U
Butylbenzylphthalate		410	U	NA	370	U	390	U	390	U
Carbazole		410	U	NA	370	U	60	J	390	U
Chrysene	400	44	J	NA	680		450		450	
Dibenz(a,h)anthracene	400	410	U	NA	93	J	77	J	80	J
Dibenzofuran		410	U	NA	76	J	390	U	390	U
Fluoranthene	20000	72	J	NA	1300		1000		970	
Fluorene	28000	410	U	NA	150	J	50	J	390	U
Indeno(1,2,3-cd)pyrene	900	410	U	NA	350	J	260	J	270	J
Naphthalene	54000	410	U	NA	100	J	390	U	390	U
Phenanthrene	40000	50	J	NA	1100		590		430	
Pyrene	13000	93	J	NA	1900		950		980	
									1600	
									910	
									200	
<b>Pesticide/PCB Analysis (UG/KG)</b>										
4,4'-DDD		1.3	JP	NA	14	P	5.8	P	5.0	P
4,4'-DDE		10		NA	4.3	P	20	P	21	P
4,4'-DDT		6.6	P	NA	3.7	U	16		16	
alpha-Chlordane		2.1	U	NA	1.9	U	2.0	U	2.0	U
Aroclor-1254		40	U	NA	85		39	U	40	U
Aroclor-1260		40	U	NA	37	U	39	U	40	U
beta-BHC		2.1	U	NA	1.9	U	2.0	U	2.0	U
Endrin Ketone		4.0	U	NA	3.7	U	3.9	U	4.0	U
gamma-Chlordane		2.1	U	NA	1.9	U	2.0	U	2.0	U
									2.8	P
									1.9	U
									1.9	U
<b>TAL Metal Analysis (MG/KG)</b>										
Aluminum		14000		12000		8860		11200		11700
Antimony		10	6.2	N	9.6	N	21.2	N	4.8	N
Arsenic		1.7	11.1		8.9		11.6		10.6	
Barium		5500	35.4		38.2		44.3		32.6	
Beryllium		0.4	0.55		0.44		0.38		0.55	
Cadmium		39	0.018	U	0.24	B	1.5		0.016	U
Calcium		1640		3660		15200		2400		2690
Chromium		1400	15.2		25.6		35.4		14.2	
Cobalt			7.4		9.3		4.4		8.7	
Copper		3100	14.7		40.0		104		21.8	
Iron		21900		41000		75400		22300		19800
Lead		150	28.6		118		186		77.4	
Magnesium			2820		4070		3160		2770	
Manganese		390	339		574		536		303	
Mercury		23	0.13		0.097		0.20		0.066	
Nickel		1000	16.1		23.0		34.3		17.6	
Potassium			365		500		826		423	
Selenium		390	0.30	U	0.25	U	0.25	U	0.27	U
Silver		200	0.042	U	0.036	U	0.035	U	0.038	U
Sodium			68.5		122		360		52.3	
Thallium		5.5	2.6		4.3		8.0		2.5	
Vanadium		550	20.3		26.0		18.8		20.3	
Zinc		6000	77.0	E	124	E	130	E	78.2	
									67.3	
									90.2	
									119	
									54.1	

Black Background = Criteria Exceeded; U - Not detected; UJ - Detection limit approximate; J - Quantitation approximate;  
R - Rejected; NA - Not Analyzed

**ANALYTICAL RESULTS**  
**OFFTA PDI SITE 09**  
**NEWPORT, RHODE ISLAND**

Sample Number	OFF-SB-433-0204	OFF-SB-433-0608	
Sample Location	433	433	
Date Sampled	11/26/2003	11/26/2003	
Interval	2.0-4.0	6.0-8.0	
QC Identifier	Soil Direct Exposure Residential None		None
<b>Volatile Organic Analysis (UG/KG)</b>			
2-Butanone	10000000	6	5 U
Acetone	7800000	120	440 *
Benzene	2500	3 J	5 U
Methylene Chloride	45000	12	12
Toluene	190000	2 J	5 U
<b>Semivolatile Organic Analysis (UG/KG)</b>			
Anthracene	35000	270 J	1800 U
Benzo(a)anthracene	900	670 J	230 J
Benzo(a)pyrene	400	620 J	250 J
Benzo(b)fluoranthene	900	910 J	390 J
Benzo(g,h,i)perylene	800	230 J	220 J
Benzo(k)fluoranthene	900	350 J	1800 U
Chrysene	400	640 J	220 J
Fluoranthene	20000	1200 J	270 J
Indeno(1,2,3-cd)pyrene	900	210 J	1800 U
Phenanthrene	40000	1000 J	190 J
Pyrene	13000	1500 J	520 J
<b>Pesticide/PCB Analysis (UG/KG)</b>			
4,4'-DDD		4.0 U	5.6 P
4,4'-DDE		4.0 U	3.7 JP
4,4'-DDT		10 P	14
alpha-Chlordane		2.0 U	6.0
gamma-Chlordane		2.0 U	5.6 P
Heptachlor		2.0 U	2.4 P
<b>TAL Metal Analysis (MG/KG)</b>			
Aluminum		12300	8120
Antimony	10	7.4 N	7.3 N
Arsenic	1.7	10.6	5.7
Barium	5500	50.4	27.0
Beryllium	0.4	0.49	0.35
Cadmium	39	0.28	0.12 B
Calcium		7490	7350
Chromium	1400	17.4	26.4
Cobalt		9.3	6.8
Copper	3100	41.8	33.4
Iron		28000	24800
Lead	150	150	96.6
Magnesium		3250	2930
Manganese	390	417	318
Mercury	23	0.076	0.049
Nickel	1000	18.8	21.2
Potassium		585	577
Selenium	390	0.27 U	0.26 U
Silver	200	0.038 U	0.036 U
Sodium		56.8	70.5
Thallium	5.5	3.3	2.8
Vanadium	550	22.8	28.8
Zinc	6000	165 E	89.3 E

Black Background = Criteria Exceeded; U - Not detected; UJ - Detection limit approximate; J - Quantitation approximate;  
 R - Rejected; NA - Not Analyzed

**ANALYTICAL RESULTS**  
**OFFTA PDI SITE 09**  
**NEWPORT, RHODE ISLAND**

Sample Number		OFF-SB-411-2022	OFF-SB-415-0608	OFF-SB-416-0406	
Sample Location		411	415	416	
Date Sampled		11/24/2003	11/18/2003	11/19/2003	
Interval		20.0-22.0	6.0-8.0	4.0-6.0	
QC Identifier	Soil Direct Exposure Residential	None	None	None	
<b>Low Concentration PAH (SIM) Analysis (UG/KG)</b>					
2-Methylnaphthalene	123000	24	U	3.6	U
Acenaphthene	43000	24	U	3.6	U
Acenaphthylene	23000	24	U	3.6	U
Anthracene	35000	24	U	3.6	U
Benzo(a)anthracene	900	48		19	880
Benzo(a)pyrene	400	47		18	820
Benzo(b)fluoranthene	900	60		22	1100
Benzo(g,h,i)perylene	800	30		11	450
Benzo(k)fluoranthene	900	25		7.9	470
Chrysene	400	72		21	890
Dibenz(a,h)anthracene	400	24	U	3.6	U
Fluoranthene	20000	67		30	1000
Fluorene	28000	24	U	3.6	U
Indeno(1,2,3-cd)pyrene	900	24	U	8.6	370
Naphthalene	54000	24	U	3.6	U
Phenanthrene	40000	47		15	440
Pyrene	13000	94		36	1200
<b>Gasoline Range Organic Analysis (UG/KG)</b>					
Gasoline Range Organics		2900	U	2500	U
<b>TAL Metal Analysis (MG/KG)</b>					
Aluminum		7650	E	8070	
Antimony	10	0.76	BN	7.5	N
Arsenic		1.7	4.3	*	23.6
Barium		5500	20.3	*	10.0
Beryllium		0.4	0.081	B	0.35
Cadmium		39	0.013	U	0.016
Calcium			1520	E	948
Chromium		1400	7.5	*	7.7
Cobalt			7.3	E	3.7
Copper		3100	17.4	*	43.2
Iron			17000		31600
Lead		150	16.2	N*	182
Magnesium			3380	*	2370
Manganese		390	409	E	197
Mercury		23	0.023	U*	0.064
Nickel		1000	12.7	E	13.1
Potassium			616	*	215
Selenium		390	0.20	U	0.26
Silver		200	2.3	E	0.036
Sodium			317	*	41.4
Thallium		5.5	0.13	U	2.9
Vanadium		550	12.1	E	10.9
Zinc		6000	54.5	E	30.8
<b>Total Petroleum Hydrocarbon Analysis (MG/KG)</b>					
Total Petroleum Hydrocarbons		500	300	13	U

Black Background = Criteria Exceeded; U - Not detected; UJ - Detection limit approximate; J - Quantitation approximate;  
R - Rejected; NA - Not Analyzed

**PDI Soil Sample Analytical Results**

Sample ID

SB-406-0002

SB-407-0002

SB-407-0204

SB-411-0204

SB-411-0608

SB-411-1012

SB-411-1416

SB-412-0204

SB-412-0608

SB-412-1012

SB-415-0002

SB-415-0608

SB-416-0002

SB-418-0002


SB-433-0204

SB-433-0608

SB-411-2022

SB-415-0204

SB-416-0406



**ANALYTICAL RESULTS: DETECTED CONTAMINANTS IN MOUND SAMPLES**  
**OFFTA PDI DECEMBER 2003: SITE 09**  
**NEWPORT, RHODE ISLAND**

Sample Number		OFF-SB-406-0002	OFF-SB-407-0002	OFF-SB-407-0204	OFF-SB-411-0204	OFF-SB-411-0608	OFF-SB-411-1012	OFF-SB-411-1416	OFF-SB-412-0204	
Sample Location		406	407	407	411	411	411	411	412	
Date Sampled		12/3/2003	12/1/2003	12/1/2003	11/24/2003	11/24/2003	11/24/2003	11/24/2003	11/25/2003	
Interval		0.0-2.0	0.0-2.0	2.0-4.0	2.0-4.0	6.0-8.0	10.0-12.0	14.0-16.0	2.0-4.0	
QC Identifier	Preliminary Remediation Goal (PRG)	None	Field Dup. OFF-SB-412-0204							
<b>Volatile Organic Analysis (UG/KG)</b>										
1,1-Dichloroethane		8	U	6	U	5	U	9	U	6
2-Butanone		8	U	6	U	5	U	10		7
2-Hexanone		8	U	6	U	5	U	9	U	8
Acetone		39	B	18		15		240	J*	960
Benzene		8	U	6	U	5	U	9	U	6
Methylene Chloride		14		11		7		21		9
Tetrachloroethene		8	U	6	U	5	U	9	U	6
Toluene		8	U	6	U	5	U	9	U	6
Total Xylenes		8	U	6	U	5	U	4	J	6
Trichloroethene		8	U	6	U	5	U	9	U	6
Trichlorotrifluoroethane		8	U	6	U	5	U	9	U	6
<b>Semivolatile Organic Analysis (UG/KG)</b>										
2-Methylnaphthalene		410	U	1800	U	1800	U	42	J	52
Acenaphthene		83	J	1800	U	1800	U	36	J	76
Acenaphthylene		69	J	1800	U	1800	U	91	J	77
Anthracene		190	J	270	J	290	J	170	J	190
Benzaldehyde		71	J	1800	U	1800	U	360	U	380
Benz(a)anthracene		900	600	1000	J	1000	J	480		520
Benzo(a)pyrene		400	460	860	J	1000	J	410		270
Benzo(b)fluoranthene		900	510	1100	J	1400	J	460		520
Benzo(g,h,i)perylene		800	63	J	380	J	390	J	290	J
Benzo(k)fluoranthene		900	280	J	570	J	520	J	190	J
bis(2-Ethyhexyl)phthalate			68	J	1800	U	1800	U	38	J
Butylbenzylphthalate			120	J	1800	U	1800	U	360	U
Carbazole			130	J	1800	U	1800	U	40	J
Chrysene		400	510	930	J	980	J	480		490
Dibenz(a,h)anthracene		400	60	J	1800	U	1800	U	82	J
Dibenzofuran			45	J	1800	U	1800	U	360	U
Fluoranthene			990		1700	J	1700	J	690	
Fluorene			84	J	1800	U	1800	U	38	J
Indeno(1,2,3-cd)pyrene		900	230	J	330	J	330	J	260	J
Naphthalene			410	U	1800	U	1800	U	360	U
Phenanthrene			740		1300	J	1400	J	460	
Pyrene			990		2200		2500		900	
<b>Pesticide/PCB Analysis (UG/KG)</b>										
4,4'-DDD			4.0	U	3.6	U	3.6	U	0.64	JP
4,4'-DDE			4.0	U	3.6	U	3.6	U	1.6	JP
4,4'-DDT			4.0	U	5.0	P	11	P	3.6	U
alpha-Chlordane			2.1	U	1.8	U	1.9	U	1.9	U
Aroclor-1254			40	U	36	U	36	U	36	U
Aroclor-1260			40	U	36	U	53	P	36	U
beta-BHC			2.1	U	1.8	U	1.9	U	1.9	U
Endrin Ketone			4.0	U	3.6	U	3.6	U	3.6	U
gamma-Chlordane			2.1	U	1.8	U	1.9	U	1.9	U
<b>TAL Metal Analysis (MG/KG)</b>										
Aluminum		12100		12300	*	10900	*	9820		12200
Antimony		10	7.0	N	0.84	BN*	1.1	N*	7.8	N
Arsenic		6.2	6.7		5.8	*	6.9	*	7.8	
Barium			49.3		60.6	*	43.3	*	26.9	
Beryllium			0.4	0.56	0.27	*	0.19	B*	0.36	
Cadmium			0.035	U	0.38	*	0.48	*	0.16	B
Calcium			1790		1800	*	10600	*	3610	
Chromium			16.2		13.2	*	14.9	*	13.2	
Cobalt			8.6	E	11.5	*	9.2	*	9.1	
Copper			29.1		67.3	N*	29.0	N*	35.5	
Iron			23900		29900	*	40000	*	25700	
Lead			150	268	E	217	*	192	*	63.4
Magnesium			3260		3550	*	3460	*	3330	
Manganese		390	450	E	445	*	424	*	491	
Mercury			0.076		0.027	B	0.043		0.039	
Nickel			21.4	E	20.2	*	20.0	*	16.8	
Potassium			560		341	*	331	*	503	
Selenium			2.6		0.14	UN	0.16	UN	0.23	U
Silver			0.040	U	2.5		2.9		0.033	U
Sodium			69.7		83.4	*	103	*	48.6	
Thallium			2.6		0.090	UN	0.11	UN	3.4	
Vanadium			38.1		31.6	*	57.7	*	21.8	
Zinc			207		139	*	190	*	111	E
<b>Total Petroleum Hydrocarbons (mg/kg)</b>										
Extractable TPH		500	36		92		190		94	
										230
										290
										340
										41

Black Background = Criteria Exceeded; U - Not detected; UJ - Detection limit approximate; J - Quantitation approximate;  
R - Rejected; NA - Not Analyzed

**ANALYTICAL RESULTS: DETECTED CONTAMINANTS IN MOUND SAMPLES**  
**OFFTA PDI DECEMBER 2003: SITE 09**  
**NEWPORT, RHODE ISLAND**

Sample Number		OFF-SB-DUP07	OFF-SB-412-0608	OFF-SB-412-1012	OFF-SB-415-0002	OFF-SB-DUP03	OFF-SB-415-0204	OFF-SB-416-0002	OFF-SB-418-0002	
Sample Location		412	112	412	415	415	415	416	418	
Date Sampled		11/25/2003	11/25/2003	11/25/2003	11/18/2003	11/18/2003	11/19/2003	11/19/2003	12/3/2003	
Interval		2.0-4.0	6.0-8.0	10.0-12.0	0.0-2.0	0.0-2.0	2.0-4.0	0.0-2.0	0.0-2.0	
QC Identifier	Preliminary Remediation Goal (PRG)	Field Dup. OFF-SB-412-0204	None	None	Field Dup. OFF-SB-415-0002	Field Dup. OFF-SB-415-0002	None	None	None	
<b>Volatile Organic Analysis (UG/KG)</b>										
1,1-Dichloroethane		6	U	NA	6	U	6	U	7	U
2-Butanone		5	J	NA	13	11	6	U	7	U
2-Hexanone		6	U	NA	6	U	1	J	6	U
Acetone		580	*	NA	3600	230	450	25	23	46
Benzene		6	U	NA	4	J	6	U	7	U
Methylene Chloride		17		NA	14	19	13		17	10
Tetrachloroethene		6	U	NA	6	U	2	J	13	7
Toluene		6	U	NA	3	J	6	U	7	U
Total Xylenes		6	U	NA	8	J	6	U	7	U
Trichloroethene		6	U	NA	6	U	6	U	2	J
Trichlorofluoromethane		6	U	NA	6	U	6	U	7	U
<b>Semivolatile Organic Analysis (UG/KG)</b>										
2-Methylnaphthalene		410	U	NA	130	J	390	U	39	J
Acenaphthene		410	U	NA	100	J	42	J	400	U
Acenaphthylene		410	U	NA	84	J	89	J	110	J
Anthracene		410	U	NA	410		160	J	140	J
Benzaldehyde		410	U	NA	370	U	390	U	340	U
Benzo(a)anthracene		900	42	J	NA	740	480		470	840
Benzo(a)pyrene		400	410	U	NA	590	420		440	800
Benzo(b)fluoranthene		900	51	J	NA	780	540		580	1100
Benzo(g,h,i)perylene		800	410	U	NA	450	300	J	310	J
Benzo(k)fluoranthene		900	410	U	NA	310	J	210	J	190
bis(2-Ethylhexyl)phthalate		280	J	NA	610	41	J	390	U	40
Butylbenzylphthalate		410	U	NA	370	U	60	J	390	U
Carbazole		410	U	NA	370	U	60	J	390	U
Chrysene		400	44	J	NA	680	450		450	880
Dibenz(a,h)anthracene		400	410	U	NA	93	J	77	J	80
Dibenzofuran		410	U	NA	76	J	390	U	390	U
Fluoranthene		72	J	NA	1300		1000		970	2100
Fluorene		410	U	NA	150	J	50	J	390	U
Indeno(1,2,3-cd)pyrene		900	410	U	NA	350	J	260	J	270
Naphthalene		410	U	NA	100	J	390	U	390	U
Phenanthrene		50	J	NA	1100		590		430	1200
Pyrene		93	J	NA	1900		950		980	1600
										910
										200
<b>Pesticide/PCB Analysis (UG/KG)</b>										
4,4'-DDD		1.3	JP	NA	14	P	5.8	P	5.0	P
4,4'-DDE		10		NA	4.3	P	20	P	21	P
4,4'-DDT		6.6	P	NA	3.7	U	16		16	
alpha-Chlordane		2.1	U	NA	1.9	U	2.0	U	2.0	U
Aroclor-1254		49	U	NA	85		39	U	40	U
Aroclor-1260		40	U	NA	37	U	39	U	40	U
beta-BHC		2.1	U	NA	1.9	U	2.0	U	2.0	U
Endrin Ketone		4.0	U	NA	3.7	U	3.9	U	4.0	U
gamma-Chlordane		2.1	U	NA	1.9	U	2.0	U	2.0	U
										2.6
										P
										1.9
										U
										1.9
<b>TAL Metal Analysis (MG/KG)</b>										
Aluminum		14000		12000		8860		11200		11700
Antimony		10	6.2	N	9.6	N	21.2	N	5.7	N
Arsenic		6.2	11.1		8.9		11.6		10.6	
Barium		35.4		38.2		44.3		32.6		35.0
Beryllium		0.4	0.65		0.44		0.38		0.55	
Cadmium		0.018	U	0.24	B	1.5	0.016	U	0.016	U
Calcium		1640		3860		15200		2400		2690
Chromium		15.2		25.6		35.4		14.2		17.3
Cobalt		7.4		9.3		4.4		8.7		7.3
Copper		14.7		40.0		104		21.8		19.8
Iron		21900		41000		75400		22300		19800
Lead		150	28.6	118		186	77.4		63.8	
Magnesium			2820		4070		3160		2770	
Manganese		390	339		574		536		303	
Mercury			0.13		0.097		0.20		0.066	
Nickel			16.1		23.0		34.3		17.6	
Potassium			365		500		826		423	
Selenium			0.30	U	0.25	U	0.25	U	0.27	U
Silver			0.042	U	0.036	U	0.035	U	0.038	U
Sodium			68.5		122		360		52.3	B
Thallium			2.6		4.3		8.0		2.5	
Vanadium			20.3		26.0		18.8		20.3	
Zinc			77.0	E	124	E	180	E	78.2	
										67.3
										90.2
										119
										54.1
<b>Total Petroleum Hydrocarbons (mg/kg)</b>										
Extractable TPH		500	38	210		760		370		140
										470
										95
										31

Black Background = Criteria Exceeded; U - Not detected; UJ - Detection limit approximate; J - Quantitation approximate;  
R - Rejected; NA - Not Analyzed

**ANALYTICAL RESULTS: CONTAMINANTS DETECTED AT MOUND/SOIL INTERFACE**  
**OFFTA PDI DECEMBER 2003: SITE 09**  
**NEWPORT, RHODE ISLAND**

Sample Number	OFF-SB-433-0204	OFF-SB-433-0608		
Sample Location	433	433		
Date Sampled	11/26/2003	11/26/2003		
Interval	2.0-4.0	6.0-8.0		
QC Identifier	Preliminary Remediation Goal (PRG)	None	None	
<b>Volatile Organic Analysis (UG/KG)</b>				
2-Butanone	6	5	U	
Acetone	120	440	*	
Benzene	3	J	5	U
Methylene Chloride	12		12	
Toluene	2	J	5	U
<b>Semivolatile Organic Analysis (UG/KG)</b>				
Anthracene	270	J	1800	U
Benzo(a)anthracene	900	670	J	J
Benzo(a)pyrene	400	620	J	250
Benzo(b)fluoranthene	900	910	J	330
Benzo(g,h,i)perylene	800	230	J	220
Benzo(k)fluoranthene	900	350	J	1800
Chrysene	400	640	J	220
Fluoranthene		1200	J	270
Indeno(1,2,3-cd)pyrene	900	210	J	1800
Phenanthrene		1000	J	190
Pyrene		1500	J	520
<b>Pesticide/PCB Analysis (UG/KG)</b>				
4,4'-DDD	4.0	U	5.6	P
4,4'-DDE	4.0	U	3.7	JP
4,4'-DDT	10	P	14	
alpha-Chlordane	2.0	U	6.0	
gamma-Chlordane		2.0	U	5.6
Heptachlor		2.0	U	2.4
<b>TAL Metal Analysis (MG/KG)</b>				
Aluminum	12300		8120	
Antimony	10	7.4	N	7.3
Arsenic	6.2	10.6		5.7
Barium		50.4		27.0
Beryllium	0.4	0.49		0.35
Cadmium		0.28		0.12
Calcium		7490		7350
Chromium		17.4		26.4
Cobalt		9.3		6.8
Copper		41.8		33.4
Iron		28000		24800
Lead	150	150		96.6
Magnesium		3250		2930
Manganese	390	417		318
Mercury		0.076		0.049
Nickel		18.8		21.2
Potassium		585		577
Selenium		0.27	U	0.26
Silver		0.038	U	0.036
Sodium		56.8		70.5
Thallium		3.3		2.8
Vanadium		22.8		28.8
Zinc		165	E	89.3
<b>Total Petroleum Hydrocarbons (mg/kg)</b>				
Extractable TPH	500	62		410

Black Background = Criteria Exceeded; U - Not detected; UJ - Detection limit approximate; J - Quantitation approximate;  
R - Rejected; NA - Not Analyzed

**ANALYTICAL RESULTS: CONTAMINANTS DETECTED AT MOUND/SOIL INTERFACE**  
**OFFTA PDI DECEMBER 2003: SITE 09**  
**NEWPORT, RHODE ISLAND**

Sample Number		OFF-SB-411 2022	OFF-SB-415 0608	OFF-SB-416 0406	
Sample Location		411	415	416	
Date Sampled		11/24/2003	11/18/2003	11/19/2003	
Interval		20.0-22.0	6.0-8.0	4.0-6.0	
QC Identifier	Preliminary Remediation Goal (PRG)	None	None	None	
<b>Low Concentration PAH (SIM) Analysis (UG/KG)</b>					
2-Methylnaphthalene		24	U	3.6	U
Acenaphthene		24	U	3.6	U
Acenaphthylene		24	U	3.6	U
Anthracene		24	U	3.6	U
Benzo(a)anthracene	900	48		19	880
Benzo(a)pyrene	400	47		18	820
Benzo(b)fluoranthene	900	60		22	1100
Benzo(g,h,i)perylene	800	30		11	450
Benzo(k)fluoranthene	900	25		7.9	470
Chrysene	400	72		21	890
Dibenz(a,h)anthracene	400	24	U	3.6	U
Fluoranthene		67		30	1000
Fluorene		24	U	3.6	U
Indeno(1,2,3-cd)pyrene	900	24	U	8.8	370
Naphthalene		24	U	3.6	U
Phenanthrene		47		15	440
Pyrene		94		36	1200
<b>Gasoline Range Organic Analysis (UG/KG)</b>					
Gasoline Range Organics		2900	U	2500	U
<b>TAL Metal Analysis (MG/KG)</b>					
Aluminum		7650	E	8070	9630
Antimony	10	0.76	BN	7.5	N
Arsenic	6.2	4.3	*	23.6	11.8
Barium		20.3	*	10.0	B
Beryllium	0.4	0.081	B	0.35	0.43
Cadmium		0.013	U	0.016	U
Calcium		1520	E	948	1840
Chromium		7.5	*	7.7	12.6
Cobalt		7.3	E	3.7	10.2
Copper		17.4	*	43.2	33.9
Iron		17000		31600	*
Lead	150	16.2	N*	182	136
Magnesium		3380	*	2370	3070
Manganese	390	409	E	197	570
Mercury		0.023	U*	0.064	0.081
Nickel		12.7	E	13.1	18.8
Potassium		616	*	215	389
Selenium		0.20	U	0.26	U
Silver		2.3	E	0.036	U
Sodium		317	*	41.4	B
Thallium		0.13	U	2.9	2.6
Vanadium		12.1	E	10.9	16.8
Zinc		54.5	E	30.8	119
<b>Total Petroleum Hydrocarbon Analysis (MG/KG)</b>					
Total Petroleum Hydrocarbons		500	300	13	U
					170

Black Background = Criteria Exceeded; U - Not detected; UJ - Detection limit approximate; J - Quantitation approximate;  
R - Rejected; NA - Not Analyzed

**APPENDIX E**  
**CALCULATIONS**

**Mound Volume Calculations**  
**OFFTA Site**  
**NAVSTA Newport, RI**

1/23/2004

**Central Mound**

E1	A1	E2	A2	Aavg	E2-E1	Vol (sf)	Vol (CY)
11	26,794	12	23,254	25,024	1	25,024	927
12	23,254	13	20,909	22,082	1	22,082	818
13	20,909	14	18,780	19,845	1	19,845	735
14	18,780	15	16,733	17,757	1	17,757	658
15	16,733	16	14,977	15,855	1	15,855	587
16	14,977	17	13,292	14,135	1	14,135	524
17	13,292	18	11,744	12,518	1	12,518	464
18	11,744	19	10,352	11,048	1	11,048	409
19	10,352	20	9,041	9,697	1	9,697	359
20	9,041	21	7,857	8,449	1	8,449	313
21	7,857	22	6,752	7,305	1	7,305	271
22	6,752	23	5,708	6,230	1	6,230	231
23	5,708	24	4,728	5,218	1	5,218	193
24	4,728	25	3,815	4,272	1	4,272	158
25	3,815	26	3,000	3,408	1	3,408	126
26	3,000	27	2,280	2,640	1	2,640	98
27	2,280	28	1,688	1,984	1	1,984	73
28	1,688	29	1,107	1,398	1	1,398	52
29	1,107	30	530	819	1	819	30
30	530	30.7	-	265	0.7	186	7
						<b>Total</b>	<b>7,032</b>

**Mound No. 1**

E1	A1	E2	A2	Aavg	E2-E1	Vol (sf)	Vol (CY)
9	7,211	10	5,498	6,355	1	6,355	235
10	5,494	11	3,962	4,728	1	4,728	175
11	3,962	12	2,494	3,228	1	3,228	120
12	2,494	13	1,317	1,906	1	1,906	71
13	1,317	13.7	-	659	0.7	461	17
						<b>Total</b>	<b>618</b>

**Mound No. 2**

E1	A1	E2	A2	Aavg	E2-E1	Vol (sf)	Vol (CY)
8	22,334	9	19,286	20,810	1	20,810	771
9	19,286	10	16,703	17,995	1	17,995	666
10	16,703	11	13,933	15,318	1	15,318	567
11	13,933	12	10,706	12,320	1	12,320	456
12	10,706	13	8,314	9,510	1	9,510	352
13	8,314	14	6,238	7,276	1	7,276	269
14	6,238	15	4,275	5,257	1	5,257	195
15	4,275	16	2,612	3,444	1	3,444	128
16	2,612	17	1,062	1,837	1	1,837	68
17	1,062	17.7	-	531	0.7	372	14
						<b>Total</b>	<b>3,487</b>

**TOTAL** **11,136**